

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	100% STATE
				ROADWAY 0005 RURAL	ROADWAY 0005 URBAN
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6514	1885	4629
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	615	31	584
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	103229	30927	72302
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	454	327	127
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2058	223	1835
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	287	34	253
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	37351	10820	26531
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	615	31	584
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	98682	28358	70324
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	454	327	127

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = chhallendeska	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or\pvc\work\pvc\chhallendeska\108355915\10876679-4ht-500.dgn		DRAWN -	REVISED -						42	(139-), 36-1, 110-1RS-1	BOND	68	7
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -		CONTRACT NO. 76679								
PLOT DATE = 6/13/2014		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	