

# SUMMARY OF QUANTITIES

COUNTY:	Hardin (069)	
ROUTE:	FAP 782, IL 1	
FUNDING:	100% STATE	
LOCATION:	RURAL	RURAL
TOTAL QUANTITY	ROADWAY 0005	ROADWAY 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	RURAL ROADWAY 0005	RURAL ROADWAY 0005
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	104,458	99,051	5,407
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	6,545	6,206	339
40600990	TEMPORARY RAMP	SQ YD	23	21	2
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	13,059	12,383	676
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	154,753	146,742	8,011
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	800	756	44
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	525	496	29
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	75	71	4
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	101,748	96,202	5,546
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,700	1,672	28
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11.0	10.4	0.6
67100100	MOBILIZATION	L SUM	1.0	0.9	0.1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.9	0.1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0	0.9	0.1

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
o:\p\work\p\p\dot\l\af\c\hd\1\00102000\78438\shs-dwr.ssq.indr.dgn		DRAWN -	REVISED -			782	114RS-3.115RS-4	HARDIN	17	5	
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -			SCALE:		SHEET 1 OF 2 SHEETS		STA. TO STA.	
PLOT DATE = 5/27/2014		DATE -	REVISED -			CONTRACT NO. 78438 ILLINOIS FED. AID PROJECT					