

RAISED REFLECTIVE PAVEMENT MARKERS

IL 1 HARDIN COUNTY LOCATION STATION TO STATION			PROJECT LENGTH (INFO ONLY) FEET	NOTE (INFO ONLY)	RAISED REF PVMT MRK			RAISED REF PVMT MKR REMOVAL EACH
STA	TO	STA			CNT LINE EACH	LANE LINE EACH	EDGE LINE EACH	
IL 1 RURAL SECTION								
STA 823+44.00	TO STA	824+25.50	81.50	2 LANE	2			2
EQN STA 824+25.50 BK =	STA	826+27.30 AH		STA EQN				
STA 826+27.30	TO STA	926+88.67	10061.37	2 LANE	126			126
STA 926+88.67	TO STA	928+41.33	OMISSION	OMISSION				
STA 928+41.33	TO STA	967+57.30	3915.97	2 LANE	49			49
EQN STA 967+57.30 BK =	STA	965+96.30 AH		STA EQN				
STA 965+96.30	TO STA	994+91.00	2894.70	2 LANE	36			36
STA 994+91.00	TO STA	996+31.40	OMISSION	OMISSION				
EQN STA 996+31.40 BK =	STA	996+38.64 AH		STA EQN				
STA 996+38.64	TO STA	999+85.00	OMISSION	OMISSION				
STA 999+85.00	TO STA	1015+10.22	1525.22	2 LANE	19			19
STA 1015+10.22	TO STA	1016+33.22	OMISSION	OMISSION				
STA 1016+33.22	TO STA	1032+66.00	1632.78	2 LANE	20			20
STA 1032+66.00	TO STA	1038+20.00	OMISSION	OMISSION				
STA 1038+20.00	TO STA	1199+05.00	16085.00	2 LANE	202			202
STA 1199+05.00	TO STA	1200+96.00	191.00	TRANSITION	3		10	13
STA 1200+96.00	TO STA	1231+16.10	3020.10	3 LANE	37	76	5	118
EQN STA 1231+16.10 BK =	STA	1231+20.50 AH		STA EQN				
STA 1231+20.50	TO STA	1239+35.00	814.50	3 LANE	10	20		30
STA 1239+35.00	TO STA	1240+73.00	138.00	TRANSITION	2	4		6
STA 1240+73.00	TO STA	1242+00.00	127.00	4 LANE	2	8		10
STA 1242+00.00	TO STA	1242+60.00	60.00	4 LANE ++	1	1		2
STA 1242+60.00	TO STA	1243+15.00	55.00	3 LANE +++	1	1		2
STA 1243+15.00	TO STA	1244+16.00	101.00	3 LANE +++	1	2		3
STA 1244+16.00	TO STA	1252+92.00	876.00	3 LANE	11	22		33
STA 1252+92.00	TO STA	1255+04.00	212.00	TRANSITION	3			3
STA 1255+04.00	TO STA	1307+26.60	5222.60	2 LANE	66			66
EQN STA 1307+26.60 BK =	STA	1307+26.80 AH		STA EQN				
STA 1307+26.80	TO STA	1317+51.50	1024.70	2 LANE	13			13
EQN STA 1317+51.50 BK =	STA	1317+51.80 AH		STA EQN				
STA 1317+51.80	TO STA	1318+14.00	62.20	RURAL	1			1
RURAL TOTALS			48100.64		605	134	15	754
IL 1 URBAN SECTION								
STA 1318+14.00	TO STA	1319+17.00	103.00	URBAN	3			3
STA 1319+17.00	TO STA	1321+30.00	213.00	2 LANE	4			4
STA 1321+30.00	TO STA	1345+87.00	2457.00	2 LANE	32			32
URBAN TOTALS			2773.00		39	0	0	39
PROJECT TOTALS			50873.64		644	134	15	793
					793			