

SIDEWALK SCHEDULE

LOCATION				PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	PROCESSING MODIFIED SOIL 12"	LIME	PROTECTIVE COAT	DETECTABLE WARNINGS
				SO FT	SO YD	TON	SO YD	SO FT
VETERANS MEMORIAL DRIVE								
STA	76+00.00	TO	STA 79+94.00	3551.5	471.3	11.7	395.5	18.7
STA	80+25.48	TO	STA 87+67.36	7190.8	956.9	23.7	799.0	20.0
STA	88+59.32	TO	STA 98+57.50	10052.2	1373.5	34.0	1116.9	88.2
STA	98+69.50	TO	STA 100+28.00	1253.2	173.6	4.9	139.2	
STA	100+40.00	TO	STA 101+05.00	488.8	67.8	1.9	54.3	
STA	101+29.00	TO	STA 102+06.31	564.0	76.1	2.1	62.7	18.4
SOUTH 34TH STREET								
STA	10+10.77	TO	STA 12+91.21	2856.5	376.9	9.3	317.4	58.5
STA	12+91.21	TO	STA 27+26.69	14181.3	1883.0	46.6	1575.7	39.9
STA	27+58.89	TO	STA 34+36.24	5753.9	761.4	18.8	639.3	43.4
TOTALS				45892.1	6140.5	152.0	5100.0	287.1
USE				45893	6141	152	5100	288

PAVEMENT MARKING SCHEDULE

LOCATION				MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS
				FOOT	FOOT	SO FT
VETERANS MEMORIAL DRIVE						
STA	79+90.69	TO	STA 80+35.30	78.1		
STA	87+67.64	TO	STA 88+87.98	418.7		
SOUTH 34TH STREET						
STA	10+44.93	TO	STA 10+46.93		24.0	
STA	24+89.72	TO	STA 25+63.21	240.0		9.0
STA	27+19.53	TO	STA 27+78.97	96.4		
TOTALS				833.3	24.0	9.0
USE				834	24	9

BICYCLE RAILING SCHEDULE

LOCATION	BICYCLE RAILING, SPECIAL	CONCRETE STRUCTURES
VETERANS MEMORIAL DRIVE		
STA 99+31.85	RT	CU YD
		23.5
		1.8
TOTALS		
USE		24
		1.8

STORM SEWER SCHEDULE

LOCATION				PIPE CULVERTS, CLASS A, TYPE 1 15"	CONTROLLED LOW-STRENGTH MATERIAL	TRENCH BACKFILL	REMOVING CATCH BASIN	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	STONE DUMPED RIPRAP, CLASS A4	STONE DUMPED RIPRAP, CLASS A5	FILTER FABRIC	AGGREGATE DITCH CHECKS	INLET AND PIPE PROTECTION
				FOOT	CU YD	CU YD	EACH	EACH	SO YD	SO YD	SO YD	TON	EACH
VETERANS MEMORIAL DRIVE													
STA	78+38.96	16.81	FT RT										1
STA	79+32.15	17.02	FT RT										1
STA	82+21.01	23.72	FT RT										1
STA	82+92.21	92.21	FT RT									6.2	1
STA	84+50.00	27.72	FT RT										1
STA	85+86.00	27.72	FT RT										1
STA	87+25.00	27.72	FT RT										1
STA	90+67.00	27.72	FT RT										1
STA	93+16.55	26.50	FT RT										1
STA	94+31.99	23.22	FT RT										1
STA	95+49.99	19.82	FT RT										1
STA	96+64.99	16.52	FT RT										1
STA	97+42.62	13.75	FT RT										1
STA	98+14.76	13.65	FT RT										1
STA	98+23.84	40.00	FT RT	89.0		2.1		1					1
STA	99+25.10	40.00	FT RT					1					1
STA	98+40.26	27.55	FT RT		1.3		1		11.0	24.3	35.3		1
SOUTH 34TH STREET													
STA	10+12.61	72.93	FT RT										1
STA	10+53.92	20.37	FT RT										1
STA	11+08.00	19.06	FT RT										1
STA	12+10.00	19.06	FT RT										1
STA	13+12.00	19.06	FT RT										1
STA	14+29.00	19.22	FT RT										1
STA	16+00.00	19.06	FT RT										1
STA	17+50.00	19.06	FT RT										1
STA	19+00.00	19.06	FT RT										1
STA	20+50.00	19.06	FT RT										1
STA	22+75.00	19.06	FT RT										1
STA	22+75.00	41.10	FT RT										1
STA	24+50.00	19.06	FT RT										1
STA	26+25.00	19.06	FT RT										1
STA	28+25.00	19.06	FT RT										1
STA	30+75.00	19.06	FT RT										1
STA	33+00.00	19.15	FT RT										1
TOTALS				89.0	1.3	2.1	1	2	11.0	24.3	35.3	6.2	31
USE				89	2	3	1	2	11	25	36	7	31

REVISION 9/4/14 - PROFILE REVISION STATION 80+37.17 TO 87+51.38
- REMOVED LIME MODIFICATION OF EXISTING SOIL