SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FEDERAL 20% STATE 0005	100% STATE 0005				
20200100	EARTH EXCAVATION	CU YD	115	115					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	496	496					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2					
25200110	SODDING, SALT TOLERANT	SQ YD	596	596	1				
25200200	SUPPLEMENTAL WATERING	UNIT	25	25					
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	37194	37194					
40600370	LONGITUDINAL JOINT SEALANT	FOOT	36315	36315					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	83	83					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	867	867					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	306	306					
40602985	HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70	TON	6172	6172					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FEDERAL 20% STATE 0005	100% STATE 0005				
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	5400	5400					
42001300	PROTECTIVE COAT	SQ YD	1071	1071					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4658	4658					
42400800	DETECTABLE WARNINGS	SQ FT	305	305					
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	55102	55102					
44000600	SIDEWALK REMOVAL	SQ FT	4429	4429					
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	1585	1585					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	880	880					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	385	385					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	275	275					
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	11	11					
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	37	37					

1 REVISED SHEET 9/10/2025

* SPECIALTY ITEMS

NON PARTICIPATING ITEMS

FILE NAME = pw://ildot-pw.bentley.com:PWIDOT/Documents/IDOT Offices/District 1/ORD Projects/D142620/CADData/CADsheets/-SHEETS.dgn	USER NAME = Phillip.Steed	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 7/1/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAU 3593 (LINCOLN AVE.)–138TH ST. TO IL 83 (SIBLEY BLVD.)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3593	2020-043-RS&SW	COOK	46	3
		CONTRACT NO. 62L15		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

REV-SEP

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FEDERAL 20% STATE 0005	100% STATE 0005				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE	FOOT	655	655					
	24"								
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	644	644					
					1				
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	580	580					
	REMOVAL								
* 89502376	REBUILD EXISTING HANDHOLE	EACH	4	4					
* X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1					
X4400501	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2380	2380					
	AND REPLACEMENT LESS THAN OR EQUAL TO								
	10 FEET								
X4400503	COMBINATION CURB AND GUTTER REMOVAL	FOOT	594	594					
	AND REPLACEMENT GREATER THAN 10 FEET								
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1388		1388				
X6030310	FRAMES AND LIDS TO BE ADJUSTED	EACH	58	58					
	(SPECIAL)								
X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	12	12					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 80% FEDERAL 20% STATE 0005	100% STATE 0005				
	* X8860105	DETECTOR LOOP REPLACEMENT	FOOT	1326	1326					
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	111		111				
	Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	5	5					
	X7100061	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Ø	Z0076600	TRAINEES	HOUR	500	500					
Ø	Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	500	500					
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30					
	20101200	TREE ROOT PRUNING	EACH	20	20					
						1				
	K1004595	PRUNING FOR SAFETY AND EQIUPMENT CLEARANCE	L SUM	1	1					
	X2010516	SELECTIVE CLEARING	UNIT	1	1					

1 REVISED SHEET 9/10/2025

Ø 0042

* SPECIALTY ITEMS

NON PARTICIPATING ITEMS

FILE NAME = pw://ildot-pw.bentley.com:PWIDOT/Documents/IDOT Offices/District 1/ORD Projects/D142620/CADData/CADsheets/-SOQ-NN.dgn	USER NAME = PhillipSteed	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 7/1/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAU 3593 (LINCOLN AVE.)–138TH ST. TO IL 83 (SIBLEY BLVD.)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3593	2020-043-RS&SW	COOK	46	5
		CONTRACT NO. 62L15		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

REV-SEP