

INDEX OF SHEETS	
SHEET NO.	DESCRIPTION
1	COVER SHEET
2	COMMITMENTS, INDEX OF SHEETS, HIGHWAY STANDARDS, AND CONSTRUCTION NOTES
3	LIGHTING CONTROLLER LOCATIONS AND LEGEND
4	SUMMARY OF QUANTITIES
5	LIGHT TOWER AND LUMINAIRE INFORMATION (TAZEWELL COUNTY)
6 - 7	LIGHT TOWER LUMINAIRE REPLACEMENT I-74 AT RIVERFRONT DR. FLYOVER
8 - 9	LIGHT TOWER LUMINAIRE REPLACEMENT I-74 AT IL 116 (MAIN ST.)
10	LIGHT TOWER LUMINAIRE REPLACEMENT I-74 AT FONDULAC DR.
11-13	LIGHT TOWER LUMINAIRE REPLACEMENT I-74 AT WASHINGTON ST.
14	I-74 WB RAMP F-6 TUNNEL LUMINAIRE REPLACEMENT
15-22	I-74 WB RAMP F-6 TUNNEL EXISTING PLANS (FOR INFORMATION ONLY)
23	LUMINAIRE PERFORMACE TABLE - HIGH MAST LUMINAIRES
24	LUMINAIRE PERFORMACE TABLE - TUNNEL LUMINAIRES

HIGHWAY STANDARDS	
000001-08	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH & FOOT
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006-05	OFF-ROAD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701101-05	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-12	APPROACH TO LANE CLOSURE, FREEWAY/ EXPRESSWAY
701406-13	LANE CLOSURE, FREEWAY/ EXPRESSWAY, DAY OPERATIONS ONLY
701428-01	TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/ EXPRESSWAY
701456-05	PARTIAL EXIT RAMP CLOSURE, FREEWAY/ EXPRESSWAY
701601-09	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701901-10	TRAFFIC CONTROL DEVICES
821101-03	LUMINARE WIRING IN POLE
701426-09	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS >/= 45 MPH
720001-01	SIGN PANEL MOUNTING DETAILS

THERE HAVE BEEN NO COMMITMENTS MADE IN CONJUCTION WITH THIS PROJECT.

CONSTRUCTION NOTES	
1.	ANY MAINTENANCE OF EXISTING LIGHTING WILL BE CONSIDERED EXTRA WORK IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
2.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING EXISTING IDOT ELECTRICAL FACILITIES AT HIS/HER OWN EXPENSE IF REQUIRED. THE CONTRACTOR SHALL ALSO BE LIABLE FOR ANY DAMAGE TO IDOT FACILITIES RESULTING FROM INACCURATE LOCATING.
3.	THE CONTRACTOR SHALL VERIFY FIELD CONDITIONS PRIOR TO BIDDING. THERE WILL BE NO ADDITIONAL COMPENSATION PAID FOR CLAIMS THAT ARISE FROM A FAILURE TO FULLY INVESTIGATE EXISTING FIELD CONDITIONS.
4.	ELECTRICAL WORK SHALL CONFORM WITH NATIONAL, STATE, AND LOCAL CODES.
5.	ALL SURPLUS MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.
6.	REMOVAL OF EXISTING ITEMS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT BID PRICES FOR THE PROPOSED ITEMS.
7.	ALL HPS LAMPS SHALL BE DISPOSED OF AT A CERTIFIED DISPOSAL FACILITY. ALL COSTS, INCLUDING DISPOSAL AND SHIPPING CHARGES, SHALL BE INCLUDED IN THE COST OF THE PROPOSED PAY ITEMS FOR LUMINAIRE LAMP REPLACEMENT. THE CONTRACTOR SHALL SUBMIT SUPPORTING DOCUMENTATION FOR ALL DISPOSAL ACTIVITIES.
8.	THE CONTRACTOR MAY ELECT TO WORK DURING NON-PEAK HOURS AND WEEKENDS, HOWEVER, ALL COSTS ASSOCIATED WITH WORKING DURING THESE TIME PERIODS SHALL BE INCLUDED IN THE BID PRICES FOR THE PAY ITEMS. THERE WILL BE NO ADDITIONAL COMPENSATION FOR SHIFT DIFFERENTIALS AND PREMIUM TIME HOURS.
9.	PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL ACQUIRE ALL PERTINENT MANUFACTURER'S OPERATION AND MAINTENANCE MANUALS FOR THE TOWER LOWERING DEVICES AND LUMINAIRES. THE CONTRACTOR SHALL BE FAMILIAR AND KNOWLEDGEABLE IN THE MAINTENANCE AND OPERATION OF THE LIGHTING EQUIPMENT.
10.	THE CONTRACTOR SHALL HAVE ALL REQUIRED EQUIPMENT AND SUFFICIENT SUPPLIES OF ALL REQUIRED MATERIALS AVAILABLE AT THE IMMEDIATE WORK SITE TO MINIMIZE WORK OPERATIONS AND TRAFFIC DISRUPTIONS, INCREASE OPERATIONAL EFFICIENCY, AND PREVENT UNNECESSARY LOWERING OF THE LUMINAIRE RING.
11.	THE LANE CLOSURES FOR WORK ON THE 7 HIGH MAST TOWERS IN THE CENTER MEDIAN ON THE PEORIA SIDE OF THE MURRAY BAKER BRIDGE SHALL BE RESTRICTED TO OFF-PEAK HOURS (8:30AM TO 3:30PM) ON SUNDAY ONLY, SEE TABLE FOR DETAILS.
12.	THE LANE CLOSURES FOR WORK ON THE 7 HIGH MAST TOWERS IN THE CENTER MEDIAN ON THE TAZEWELL SIDE OF THE MURRAY BAKER BRIDGE SHALL BE RESTRICTED TO OFF-PEAK HOURS (8:30AM TO 3:30PM) ON SUNDAY ONLY, SEE TABLE FOR DETAILS.
13.	EXISTING LUMINAIRE WIRING, FUSES, AND FUSE HOLDERS WILL BE REUSED WITH THE PROPOSED HIGH MAST, TUNNEL, UNDERPASS, AND ROADWAY LUMINAIRES. IF THE EXISTING ITEMS ARE DAMAGED, INCOMPATIBLE, OR NOT RE-USABLE, THE CONTRACTOR SHALL FURNISH AND INSTALL NEW ITEMS AS REQUIRED FOR LUMINAIRE INSTALLATION AND AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS REQUIRED FOR LUMINAIRE INSTALLATION. ALL MATERIAL SHALL CONFORM TO THE STANDARD SPECIFICATIONS. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE PROPOSED LUMINAIRES.
14.	EXISTING LUMINAIRE MOUNTING BRACKETS AND HARDWARE WILL BE REUSED WITH THE PROPOSED HIGH MAST, TUNNEL, UNDERPASS, AND ROADWAY LUMINAIRES. IF THE EXISTING ITEMS ARE DAMAGED, INCOMPATIBLE, OR NOT RE-USABLE, THE CONTRACTOR SHALL FURNISH AND INSTALL NEW ITEMS AS REQUIRED FOR LUMINAIRE INSTALLATION AND AS DIRECTED BY THE ENGINEER. . THE CONTRACTOR SHALL FURNISH AND INSTALL BRACKETS, HARDWARE, AND ALL OTHER ITEMS REQUIRED FOR LUMINAIRE INSTALLATION. ALL BRACKETS AND HARDWARE SHALL BE GALVANIZED STEEL OR STAINLESS STEEL. ALL MATERIAL SHALL CONFORM TO THE STANDARD SPECIFICATIONS. THE COST OF THIS WORK-
15.	THE CONTRACTOR SHALL VERIFY EXISTING LUMINAIRE VOLTAGES PRIOR TO ORDERING MATERIAL.

IF THE EXISTING ITEMS ARE DAMAGED, THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04. IF THE EXISTING ITEMS ARE INCOMPATIBLE WITH THE LUMINAIRE SUPPLIED BY THE CONTRACTOR, THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE LUMINAIRE

IF THE EXISTING ITEMS ARE DAMAGED, THIS WORK SHALL BE PAID ACCORDING TO ARTICLE 109.04. IF THE EXISTING ITEMS ARE INCOMPATIBLE WITH THE LUMINAIRE SUPPLIED BY THE CONTRACTOR, THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE LUMINAIRE.

MODEL: 340MODEL.NAMES
FILE: 340INDEX.SHEETS

	USER NAME = \$USERS	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMMITMENTS, INDEX OF SHEETS, HIGHWAY STANDARDS, AND CONSTRUCTION NOTES	SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -	CHECKED -	REVISED -									74	72[(8-9)L-1,(10)L];(90-11)L	PEORIA,TAZEWELL	24	2
	PLOT SCALE = \$SCALES	DATE -	REVISED -									CONTRACT NO. 68K25				
	PLOT DATE = \$DATES											ILLINOIS FED. AID PROJECT				