LETTING ITEM NO.: 02A LETTING DATE: SEPTEMBER 19, 2025 DIXON MUNICIPAL AIRPORT CHARLES R. WALGREEN FIELD DIXON, ILLINOIS

CONSTRUCTION PLANS FOR DIXON MUNICIPAL AIRPORT

REHABILITATE RUNWAY 12/30

ILLINOIS PROJECT: C73-5064 SBG PROJECT: 3-17-SBGP-197


JULY 25, 2025



INFORMATION FOR EXCAVATORS


INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIEN OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES OF HIS OF ERATIONAL FUNDS, OBTAINE FROM
RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE
RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OI
THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811



DIXON MUNICIPAL AIRPORT CHARLES R. WALGREEN FIELD DIXON, ILLINOIS





PROJECT

LOCATION



APPROACH CATEGORY B **DESIGN GROUP I**

DIXON MUNICIPAL AIRPORT DIXON TOWNSHIP (SECTION: 3) OPPOSITE LINCOLN HIGHWAY 38 (FRANKLIN GROVE ROAD)

UNICOM RADIO FREQUENCY - 123.05

LOCATION MAP


SITE PLAN

INDEX TO SHEETS

- COVER SHEET
- 2. INDEX TO SHEETS AND SUMMARY OF QUANTITIES
- 3. SITE PLAN AND PROJECT CONTROL PLAN
- 4. CONSTRUCTION SAFETY AND PHASING PLAN 1
- 5. CONSTRUCTION SAFETY AND PHASING PLAN 2
- 6. CONSTRUCTION SAFETY AND PHASING PLAN 3
- 7. CONSTRUCTION SAFETY AND PHASING PLAN GENERAL NOTES AND DETAILS 1
- 8. CONSTRUCTION SAFETY AND PHASING PLAN GENERAL NOTES AND DETAILS 2
- 9. STORMWATER POLLUTION PREVENTION PLAN
- 10. STORMWATER POLLUTION PREVENTION PLAN NOTES
- 11. TYPICAL SECTIONS AND PAVEMENT REHABILITATION DETAILS
- 12. EXISTING CONDITIONS/REMOVALS 1
- 13. EXISTING CONDITIONS/REMOVALS 2
- 14. EXISTING CONDITIONS/REMOVALS 3
- 15. RUNWAY 12-30 PLAN AND PROFILE 1
- 16. RUNWAY 12-30 PLAN AND PROFILE 2
- 17. RUNWAY 12-30 PLAN AND PROFILE 3
- 18. PAVEMENT MARKING PLAN 1
- 19. PAVEMENT MARKING PLAN 2
- 20. PAVEMENT MARKING PLAN 3
- 21. PAVEMENT MARKING DETAILS
- 22. GEOTECHNICAL ENGINEERING INFORMATION

SUMMARY OF QUANTITIES

| ITEM | DESCRIPTION | UNIT | ESTIMATED QUANTITY | RECORD QUANTITY |
|----------|------------------------------------|--------|--------------------|--------------------|
| AR150510 | ENGINEER'S FIELD OFFICE | L SUM | 1 | |
| AR150520 | MOBILIZATION | L SUM | 1 | |
| AR152410 | UNCLASSIFIED EXCAVATION | CU YD | 100 | |
| AR152480 | SHOULDER ADJUSTMENT | SQ YD | 2,600 | |
| AR152540 | SOIL STABILIZATION FABRIC | SQ YD | 190 | |
| AR156520 | INLET PROTECTION | EACH | 12 | |
| AR208515 | POROUS GRANULAR EMBANKMENT | CU YD | 65 | |
| AR209607 | CRUSHED AGGREGATE BASE COURSE - 7" | SQ YD | 190 | |
| AR401610 | BITUMINOUS SURFACE COURSE | TON | 2,415 | |
| AR401630 | BITUMINOUS SURFACE TEST SECTION | EACH | 1 | |
| AR401650 | BITUMINOUS PAVEMENT MILLING | SQ YD | 20,970 | |
| AR401915 | REM & REP BIT PAVEMENT - TYPE A | SQ YD | 185 | |
| AR401916 | REM & REP BIT PAVEMENT - TYPE B | SQ YD | 920 | |
| AR403673 | REFLECTIVE CRACK CONTROL TREATMENT | SQ YD | 185 | |
| AR603510 | BITUMINOUS TACK COAT | GALLON | 2,520 | |
| AR620520 | PAVEMENT MARKING - WATERBORNE | SQ FT | 4,950 | |
| AR620525 | PAVEMENT MARKING - BLACK BORDER | SQ FT | 3,000 | |
| AR620900 | PAVEMENT MARKING REMOVAL | SQ FT | 470 | |
| AR901510 | SEEDING | ACRE | 0.6 | |
| AR908515 | HEAVY-DUTY HYDRAULIC MULCH | ACRE | 0.6 | |



DUCT MARKER DETAIL

IL. CONTRACT: DI035
IL. LETTING ITEM: 02A

IL. PROJECT: **C73-5064**S.B.G. PROJECT: **3-17-SBGP-197**

| REVISIONS | | | | | | | | | | |
|-----------|----|------|--|--|--|--|--|--|--|--|
| NUMBER | BY | DATE | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

DIXON MUNICIPAL AIRPORT
DIXON, ILLINOIS
REHABILITATE RUNWAY 12/30
INDEX TO SHEETS AND
SUMMARY OF QUANTITIES

CRAWFORD, MAPHY & TILLY, INC.
CONSULTING ENGNEERS
License No. 184-000613

DESIGN BY: STL

DRAWN BY: JRO

CHECKED BY: DKP

APPROVED BY: DKP


DATE: 07/25/2025


JOB No: 22004684-00


FINAL

SHEET 2 OF 22 SHEETS

DATE: Thursday, July 17, 2025 8:57:38 AM FILE: K:\DivorAn\22004884-0\ BehahBwut230\Daw\Sheek\2200488400 - Divon







- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING SAFETY REQUIREMENTS.
- A MINIMUM OF 10 DAYS PRIOR TO THE PRECONSTRUCTION MEETING THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS
- A MINIMUM OF 10 DAYS PRIOR TO THE PRECONSTRUCTION MEETING THE CONTRACTOR SHALL SUBMIT THE SPCD FOR APPROVAL.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL SIGN THE SWPPP CERTIFICATION STATEMENT.
- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE RESIDENT ENGINEER. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT.
- ALL EXISTING TAXIWAY AND BLINWAY AIRFIELD LIGHTING CIRCUITS FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER AND AIRPORT FOR ALL PHASES, ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO THE
- ALL EXISTING AND PROPOSED FENCE LINES, EXCEPT AS OTHERWISE NOTED, SHALL BE MAINTAINED AND SHALL SERVE AS CONSTRUCTION ABOUND THE PERIMETER OF THE PROJECT, ALL EXISTING GATES. SHALL BE MAINTAINED, CLOSED AND LOCKED AS DIRECTED BY THE AIRPORT OWNER'S REPRESENTATIVE. SHOULD THE CONTRACTOR CHOOSE TO KEEP A GATE OPEN FOR CONSTRUCTION OPERATIONS. A COMPETENT SECURITY GUARD SHALL MONITOR THE OPEN GATE. ANY COST SHALL NOT BE PAID FOR SEPARATELY, BUT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL AT ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK SHALL BE REQUIRED TO BE ONSITE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE AIRPORT PAYMENT FOR DUST CONTROL SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 11. PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL INCLUDING BUT NOT LIMITED TO, TEMPORARY CONSTRUCTION FENCING, BARRICADES, SIGNING, FLAGGER, AIR OPERATIONS AREA (A.O.A) LATH AND RIBBON, ETC. SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 12. ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT UNLESS A SPECIFIC PAY ITEM IS PROVIDED.

1. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRECONSTRUCTION CONFERENCE WITH THE AIRPORT, RESIDENT ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRECONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT
- ON OR BEFORE THE PRECONSTRUCTION CONFERENCE, THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE UPDATED ON A WEEKLY BASIS. ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT.
- THE CONTRACTOR SHALL BE REQUIRED TO ESTABLISH A COORDINATION PLAN WITH THE AIRPORT OR HIS/HER DESIGNATED REPRESENTATIVE, REGARDING DE-ENERGIZING AND ENERGIZING OF THE AIRFIELD CIRCUITS IMPACTED BY CONSTRUCTION ACTIVITY.

2. PHASING

- TOTAL CONTRACT TIME SHALL BE 29 CALENDAR DAYS.
- PHASING SHALL BE AS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET

3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

- ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET.
- WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES
- 3. AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING AIRCRAFT AT ALL TIMES.
- SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARY RELOCATE EQUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS. THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO

4. PROTECTION OF NAVIGATION AIDS (NAVAIDS)

THE CONTRACTOR SHALL REMAIN CLEAR OF THE ILS CRITICAL AREAS AND OTHER NAVAIDS FACILITIES AT ALL TIMES.

5. CONTRACTOR ACCESS

- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN AND CONSTRUCTION SAFETY AND PHASING PLAN
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE EXISTING GATE SHOWN. THE ENTRANCE SHALL BE SIGNED ACCORDINGLY AS TO ALLOW ONLY CONSTRUCTION VEHICLES ACCESS IF APPLICABLE AND WILL ONLY BE ACCESSIBLE DURING THE CONTRACTOR'S SCHEDULED WORK DAY ALL SIGNAGE SHALL CONFORM TO IDOT CONSTRUCTION STANDARDS FOR VEHICLES ENTERING AND LEAVING THE SITE.
- SUPERVISORY PERSONNEL SHALL DEMONSTRATE IN THE PRESENCE OF THE AIRPORT MANAGER THAT THEY ARE FAMILIAR WITH AIRPORT RADIO AND AIRPORT DRIVING PROCEDURES IN ORDER TO PERFORM WORK. OTHER CONSTRUCTION PERSONNEL CAN BE WITHIN THE AIRFIELD LIMITS PROVIDED THAT THEY ARE UNDER ESCORT AND IN THE PRESENCE OF AN AUTHORIZED SUPERVISOR. KNOWLEDGE OF THE AIRPORTS PROCEDURES BY THE SUPERVISORY PERSONNEL MUST BE DEMONSTRATED PRIOR TO THE START OF CONSTRUCTION.
- THE CONTRACTOR'S STORAGE AND STAGING AREA WILL BE AS SHOWN IN THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET.
- THE CONTRACTOR'S MATERIAL AND EQUIPMENT, WHEN NOT IN USE, SHALL BE STORED IN THE CONTRACTOR'S STAGING AREA. ALL DELIVERIES, FOUIPMENT REFUELING, FOUIPMENT MAINTENANCE AND EQUIPMENT TRANSFER SHALL TAKE PLACE WITHIN THE CONTRACTOR'S STAGING AREA
- THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE
- ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS TAXIWAYS AND APRONS OPEN TO AIRCRAFT TRAFFIC SHALL BE UNDER CONTROL BY A FLAGMAN OR ESCORT MONITORING AIRPORT TRAFFIC ON THE RADIO. THE CONTRACTOR SHALL PROVIDE HIS OWN FLAGMEN
- ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE CONTRACTOR FOR HAUL ROADS, STORAGE AREAS AND/OR STAGING AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION, NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR
- ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR.

6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY AIRPORT OPERATIONS OR THE RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT.
- CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS

7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD PAVEMENTS
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS.

8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER.
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 72 HOLIBS NOTICE TO AIRPORT OPERATIONS PRIOR TO CLOSING ANY PAVEMENTS SO THAT PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT.
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO FQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
- IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL 911.
- CONTACTS FOR THIS PROJECT WILL BE DETERMINED AT THE PRECONSTRUCTION MEETING PRIOR TO THE PROJECT START

10. INSPECTION REQUIREMENTS

- THE CONTRACTOR SHALL INSPECT THE JORSITE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX C OF FAA AC 150/5370-2 MAY BE USED TO AID IN THE INSPECTIONS.
- THE CONTRACTOR SHALL ATTEND AN INSPECTION OF EACH PHASE WORK AREA PRIOR TO OPENING THE AREA TO AIRPORT OPERATIONS.

11. UNDERGROUND UTILITIES

- IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROURD UTILITIES AT CRITICAL POINTS. SEE SECTION 70-16 OF THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED. ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE LITH ITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER ANY SLICH MAINS AND/OR SERVICES. DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER.
- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR UTILITY LOCATES. SEE SECTION 70-16 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT INFORMATION.
- SHOULD A UTILITY COMPANY OR GOVERNMENT AGENCY BE UNABLE TO LOCATE FACILITIES, THE CONTRACTOR SHALL LOCATE THESE FACILITIES. PAYMENT FOR THIS LOCATION SHALL BE INCIDENTAL TO THE IMPROVEMENTS REQUIRING THE LOCATE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL AIRPORT OWNED UTILITIES AND SHALL BE CONSIDERED INCIDENTAL TO THE

12. PENALTIES

NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT BUILES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS

13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR.

14. RUNWAY AND TAXIWAY VISUAL AIDS

RUNWAY OR TAXIWAY CLOSURES (IF REQUIRED) ARE AS DETAILED IN THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET FOR THIS PROJECT. IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOW THE REQUIREMENTS OF FAA AC 150/5370-2 (LATEST EDITION)

15. MARKING AND SIGNS FOR ACCESS ROUTES

MARKING AND SIGNAGE FOR THE ACCESS ROUTE SHALL BE AS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET OR AS DIRECTED BY THE RESIDENT ENGINEER.

16. HAZARD MARKING AND LIGHTING

- THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS. TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT
- ALL CONSTRUCTION FQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2 AND 150/5210-5 AT ALL TIMES WHILE OPERATING ON AIRPORT
- BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE 3. CONSTRUCTION SAFETY AND PHASNG PLAN SHEET OR AS DIRECTED BY THE RESIDENT ENGINEER, THE CONTRACTOR SHALL PLACE ALL BARRICADES AND CONSTRUCTION SETBACK LINES ITEMS AS SHOWN PRIOR TO INITIATING WORK IN EACH PHASE. ALL COSTS TO FURNISH, INSTALL, REPOSITION, AND MAINTAIN THESE ITEMS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT
- THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT.
- ACCESS TO ACTIVE RUNWAY AND TAXIWAY PAVEMENTS SHALL BE SIGNED WITH STOP SIGNS MOUNTED ON IDOT TYPE II BARRICADES (2 EACH, RIGHT AND LEFT). IN ADDITION TO THE STOP SIGNS, WARNING SIGNS (2 FACH RIGHT AND LEFT) SHALL BE MOUNTED. WARNING SIGNS SHALL STATE "UNAUTHORIZED ACCESS NOT ALLOWED"

17. PROTECTION

CONTRACTOR PERSONNEL, VEHICLES, EQUIPMENT AND BARRICADES SHALL NOT BE ALLOWED WITHIN THE TAXIWAY OBJECT FREE AREA (TOFA) OF ACTIVE TAXIWAYS, RUNWAY OBSTACLE FREE ZONE (ROFZ) AND THE RUNWAY SAFETY AREA (RSA) OF ACTIVE RUNWAYS.

18. OTHER LIMITATIONS ON CONSTRUCTION

- IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT
- THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING RUNWAYS AND TAXIWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS ONTO EXISTING PAVEMENTS, THIS DEBRIS SHALL BE REMOVED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION OPERATION WORKING HOURS.
- THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT THE WORK ZONE AND MAINTAIN SANITARY FACILITIES FOR EMPLOYEES TO USE. FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE USED.
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICAL AREA LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVEABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY.
- THE CONTRACTOR SHALL SUPPLY AND HAVE IN THEIR POSSESSION AT ALL TIMES AT LEAST ONE AIRPORT RADIO. IN THE EVENT THAT THE AIRPORT MANAGER NEEDS TO CONTACT THE CONTRACTOR DIRECTLY, THE OPERATOR OF SAID RADIO SHALL BE FAMILIAR WITH AIRPORT RADIO PROCEDURES AND TUNED INTO THE GROUND CONTROL FREQUENCY.
- BROKEN CONCRETE, BROKEN ASPHALT, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE SPECIFIED.

AIRFIELD LIGHTS AND SIGNS NOTES

- CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND TAXIWAY LIGHTS ON CLOSED TAXIWAYS INCLUDING LIGHTS/SIGNS ON OTHER SIDE OF BARRICADE LINES WITHIN THE AIRCRAFT MOVEMENT AREA UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL COST INCIDENTAL TO THE CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE
- CONTRACTOR SHALL TURN OFF BLINWAY FDGE LIGHTING REGULATOR AND LOCK-OUT/TAG-OUT CIRCUIT BREAKER AND CUT OUT INSIDE THE ELECTRICAL VAULT. DURING ALL RUNWAY CLOSURES. CONTRACTOR SHALL COORDINATE ACCESS TO THE VAULT WITH THE AIRPORT MANAGER/RESIDENT ENGINEER PRIOR TO RE-OPENING THE RUNWAY, THE CONTRACTOR SHALL COORDINATE WITH AIRPORT MANAGER/RESIDENT ENGINEER TO RE-ENERGIZE THE RUNWAY CIRCUIT

IL. CONTRACT: DI035

IL. LETTING ITEM: 02A

IL. PROJECT: C73-5064 S.B.G. PROJECT: 3-17-SBGP-197

REVISIONS NUMBER BY DATE

> THIS BAR IS FOLIAL TO 2" AT FULL SCALE (34X22)

> > 12/30

DIXON MUNICIPAL AIRPORT DIXON, ILLINOIS REHABILITATE RUNWAY 12/3

PHASING I ETAILS - 1 Y AN AND EFT.

JCTION SAE

N N N

STE

ë

PLAN


RS &


U

DESIGN BY STL DRAWN BY JRO CHECKED BY DKP APPROVED BY 07/25/2025 JOB No: 22004684-00

FINAL

SHEET 7 OF 22 SHEETS






CLOSED RUNWAY MARKER DETAIL

NOT TO SCALE

NOTES

- 1. MARKERS SHALL BE SOLID YELLOW.
- 2. MARKERS SHALL BE MATERIAL APPROVED BY THE ENGINEER.
- CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE
- MARKERS ON PAVEMENT SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN, HOWEVER, WHEN WORK IS NECESSARY FOR THAT AREA OR PAVEMENT IS OPEN TO TAXIING AIRCRAFT, THE MARKERS SHALL BE RELOCATED OFF THE PAVEMENT AS SHOWN ON THE DETAIL.
- 5. COST OF FURNISHING, INSTALLING, MAINTAINING, RELOCATING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE
- 6. DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT, WHERE APPLICABLE, PERSONNEL. THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET. THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE CONSTRUCTION ACTIVITY




CONSTRUCTION SETBACK LINE DETAIL

NOT TO SCALE

NOTES

1. PLACE CONSTRUCTION SETBACK LINES AT LOCATIONS OF CONSTRUCTION OPERATIONS NEAR RUNWAY OBSTACLE FREE ZONES AND TAXIWAY OBJECT FREE AREAS WHEN RUNWAYS/TAXIWAYS ARE



AIRSIDE LOW PROFILE LIGHTED BARRICADE NOT TO SCALE

BARRICADE NOTES

- 1. FLASHER OR STEADY BURN LIGHTS SHALL BE BATTERY OPERATED. LENS SHALL BE RED AND BE ABLE TO ROTATE 90^.
- FACING OF BARRICADE SHALL BE COVERED WITH REFLECTIVE TAPE OR PAINT.
- BARRICADES TO BE PLACED WITH A MAXIMUM OF 4' SPACING END TO END UP TO THE EDGE OF PAVEMENT ALONG OPERATIONAL PAVEMENT ADJACENT TO CONSTRUCTION AS DIRECTED BY THE RESIDENT ENGINEER. ALTERNATE FLASHER OR STEADY BURN LENSES SO THAT EVERY OTHER LENS IS ROTATED 90°
- FLASHER OR STEADY BURN LIGHTS SHALL BE SECURED TO THE BARRICADES, AS APPROVED BY THE RESIDENT ENGINEER.
- BARRICADES SHALL BE OF LOW MASS, EASILY COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT OR ANY OF IT COMPONENTS, AND WEIGHTED TO AVOID BEING BLOWN OVER.
- 6. BARRICADES SHALL BE OF A COMMERCIAL DESIGN AND SHALL MEET CURRENT FAA REQUIREMENTS.
- PLACE ALL BARRICADES OUTSIDE RUNWAY SAFETY AREAS, RUNWAY OBSTACLE FREE ZONES AND OUTSIDE TAXIWAY OBJECT FREE AREAS.
- ALL COST ASSOCIATED WITH THE LOW PROFILE BARRICADES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

CONTRACTOR ACCESS ROUTE NOTES


ALL PAVEMENTS OR TURF AREAS UTILIZED BY THE CONTRACTOR FOR AN ACCESS ROUTE, STAGING, OR STORAGE SHALL BE REPAIRED AND RESTORED TO THEIR ORIGINAL CONDITION TO THE SATISFACTION OF THE AIRPORT. NO ADDITIONAL COMPENSATION TO PROTECT, REPAIR. OR RESTORE THESE AREAS SHALL BE MADE.

| | CONSTRU | JCTION PC | INT TABLE | | |
|-------|-----------------------|--------------|--------------|---------------------|------------------|
| POINT | NEAREST ACTIVE RUNWAY | LATITUDE | LONGITUDE | GROUND ELEVATION | TOP ELEVATION |
| Α | RUNWAY 8/26 | 41°50'15.12" | 89°26'44.58" | 778.0 | 803.0 |
| В | RUNWAY 8/26 | 41°50'15.11" | 89°26'43.26" | 778.0 | 803.0 |
| С | RUNWAY 8/26 | 41°50'14.12" | 89°26'43.27" | 778.0 | 803.0 |
| D | RUNWAY 8/26 | 41°50'14.13" | 89°26'44.59" | 778.0 | 803.0 |
| E | RUNWAY 8/26 | 41°50'01.84" | 89°26'53.74" | 778.0 | 803.0 |
| F | RUNWAY 8/26 | 41°50'02.80" | 89°26'41.51" | 780.0 | 805.0 |
| G | RUNWAY 8/26 | 41°50'00.96" | 89°26'35.05" | 781.0 | 806.0 |
| Н | RUNWAY 8/26 | 41°50'01.44" | 89°26'32.16" | 782.0 | 807.0 |
| 1 | RUNWAY 8/26 | 41°50'03.38" | 89°26'36.44" | 782.0 | 807.0 |
| J | RUNWAY 8/26 | 41°50'03.60" | 89°26'38.83" | 781.0 | 806.0 |
| К | RUNWAY 8/26 | 41°50'09.02" | 89°26'38.38" | 782.0 | 807.0 |

MAXIMUM ANTICIPATED HEIGHT OF CONSTRUCTION EQUIPMENT 25'

NOTE - ALL PHASES

ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER. ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO CONTRACT.



CLOSED TAXIWAY MARKER DETAIL

NOT TO SCALE

CLOSED TAXIWAY MARKER DETAIL NOTES


- CLOSED TAXIWAY MARKERS SHALL BE PAINTED WITH
 TEMPORARY MARKING CAPABLE OF BEING REMOVED WITH LOW PRESSURE WATER BLASTING OR OTHER MATERIAL THAT DOES NOT VIOLATE THE OBJECT FREE AREA CRITERIA AND RUNWAY SAFETY AREA CRITERIA PER ADVISORY CIRCUI AR 150/5300-13A (LATEST EDITION) AND ARE APPROVED BY THE
- 2. CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE
- 3. COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 4. PLACE MARKERS OVER TAXIWAY CENTERLINE.
- 5. MARKERS SHALL BE ADEQUATELY SECURED TO PREVENT MOVEMENT BY PROPELLER WASH, JET BLAST OR OTHER WIND
- MARKERS ARE ONLY REQUIRED FOR TAXIWAYS CLOSED THREE (3) CONSECUTIVE DAYS OR MORE.

DESIGN AIRCRAFT APPROACH CATEGORY: B **DESIGN AIRPORT GROUP: I**

RUNWAY 12/30 OBSTACLE FREE ZONE TOTAL WIDTH = 250' BUNWAY 8/26 OBSTACLE FREE ZONE TOTAL WIDTH= 250 TAXIWAY CENTERLINE TO OBJECT SEPARATION = 44.5'
TAXILANE CENTERLINE TO OBJECT SEPARATION = 39.5'

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE SPECIAL PROVISIONS SECTION 50-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS

REPLACE AUTOMATED WEATHER OBSERVATION SYSTEM.



CONSTRUCTION EQUIPMENT AND TRUCK/VEHICLE SIGNAL FLAG

NOT TO SCALE

IL. CONTRACT: DI035 IL. LETTING ITEM: **02A** IL. PROJECT: C73-5064 S.B.G. PROJECT: 3-17-SBGP-197

REVISIONS NUMBER BY DATE

> THIS BAR IS FOLIAL TO 2" AT FULL SCALE (34X22).

12/30 DIXON MUNICIPAL AIRPO DIXON, ILLINOIS REHABILITATE RUNWAY 12 CONSTRUCTION SAEFTY AND GENERAL NOTES AND D DIXON, IL REHABILITATE F

AIRPORT

Σ U

DESIGN BY STL JRO CHECKED BY DKP 07/25/2025 JOB No: 22004684-00

FINAL

SHEET 8 OF 22 SHEETS

STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NUPPES

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONARI F AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE AT THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION:

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF REHABILITATION OF AN EXISTING BITUMINOUS PAVEMENT AT DIXON MUNICIPAL AIRPORT. THE PROJECT INCLUDES TURF SHOULDER ADJUSTMENT, VARIOUS PAVEMENT ITEMS, PAVEMENT MARKING AND OTHER MISCELLANEOUS CONSTRUCTION WORK.

DESCRIPTION OF CONSTRUCTION ACTIVITY:

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS GRUBBING, EXCAVATION AND GRADING:

PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL. SUCH AS:

INLET PROTECTION

VARIABLE DEPTH BITUMINOUS PAVEMENT MILLING AND PAVING.

TURF SHOULDER ADJUSTMENT, SEEDING AND MULCHING.

INSTALLATION OF NEW PAVEMENT MARKING.

REMOVAL AND DISPOSAL OF TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES.

AREA OF CONSTRUCTION SITE:

IT IS ESTIMATED THAT LESS THAN 1 ACRE OF LAND WILL BE DISTURBED BY GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE
 PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED
 PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO A STORM SEWER SYSTEM.

EROSION AND SEDIMENT CONTROL:

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, SOD, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, AND ALL OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.

AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.

DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTIONS SHALL BE INSTALLED AS CALLED OUT IN THE PLAN AND DIRECTED BY THE ENGINEER.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILLR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION BEIJATED ACTIVITIES.

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.

EARTH STOCKPILES SHALL BE <u>TEMPORARILY SEEDED, AT THE CONTRACTOR'S EXPENSE</u>, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN SEVEN (7) DAYS.

THE DOWN STREAM SIDE OF ALL STOCKPILES SHALL BE ENCOMPASSED WITH EROSION CONTROL BARRIER.

AS CONSTRUCTION PROCEEDS. THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS

CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS WITHIN THE STAGING AREA ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT PERIODICALLY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2" OR GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE RESIDENT ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT THE EROSION AND SEDIMENT CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER PROSION CONTROL WORK IS NEFCESSARY

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND EROSION CONTROL ITEMS.

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SOIL CONTAMINATION FROM BUILDING MATERIALS, FERTILIZERS, CHEMICALS, PAVEMENT MARKING, WASTE PILES, FUEL CONTAINMENT, AND ANY OTHER POTENTIAL HAZARDOUS MATERIALS THAT MAY EXIST ONSITE.

NO DEDICATED CONCRETE OR ASPHALT BATCH PLANTS SHALL BE LOCATED ON THIS SITE.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

COST OF MAINTAINING THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE INCLUDED INCLUDED IN THE UNIT BID PRICE FOR THE VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RE-SEEDED AND/OR SODDED.

MAINTENANCE AFTER CONSTRUCTION:

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS.
MAINTENANCE OF TEMPORARY AND PERMANENT EROSION CONTROL SYSTEMS UP TO THIS DATE WILL BE REQUIRED BY THE
CONTRACTOR.

DOCUMENTATION:

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL POST A SIGN OR OTHER NOTICE NEAR THE MAIN ENTRANCE OF THE CONSTRUCTION SITE. IF THIS IS NOT POSSIBLE, THEN IT MAY BE PERMITTED TO POST THIS NOTICE IN A LOCAL PUBLIC BUILDING. THE SIGN OR NOTICE MUST CONTAIN THE FOLLOWING:

1. THE LOCATION OF THE SWPPP AND NAME AND 24/7 TELEPHONE NUMBER OF THE CONTACT PERSON.

THROUGHOUT CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AND UPDATE AN "AS-BUILT" SET OF STORM WATER POLLUTION PREVENTION PLANS IN THE PROJECT FILES. THE SWPPP SHALL BE UPDATED WITHIN 7-DAYS OF ANY MODIFICATIONS TO THE PLANS. THE SWPPP AND ALL REVISIONS SHALL BE RETAINED FOR THREE YEARS AFTER FINAL STABILIZATION OF THE SITE, WHICH SHALL BE DEFINED AS VEGETATION COVER OF AT LEAST 70% OF HISTORIC CONDITIONS.

A STORM WATER POLLUTION PREVENTION PLAN EROSION CONTROL INSPECTION REPORT (FORM BC 2259) SHALL BE BE COMPLETED WITH INSPECTION FREQUENCIES AS OUTLINED HEREIN, SWPPP REPORTS SHALL BE RETAINED FOR THREE YEARS AFTER THE DATE OF FINAL STABILEZATION AS DEFINED HEREIN.

GENERAL NOTES FOR SOIL EROSION AND SEDIMENT CONTROL

- ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.
- NO WORK SHALL BE PERFORMED IN FLOWING WATER. WORK IN AND NEAR FLOWING WATER SHALL BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE ACCEPTABLE
- 3. CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN THE PATH OF STREAM FLOW.
- TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
- PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME.
- THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY.
 ADJACENT STREETS SHALL BE KEPT FREE OF SOIL AND DEBRIS.
- 7. SHOULD IT BE NECESSARY TO REMOVE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS, THE CONTRACTOR SHALL FIRST OBTAIN PERMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- ALL OTHER SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE RESIDENT ENGINEER, STEPHENSON COUNTY, FREEPORT-ALBERTUS AIRPORT, IDOT DIVISION OF AERONAUTICS, AND THE IEPA SHALL BE IMPLEMENTED IMPEDIATELY UPON NOTIFICATION OF THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE ENGINEER, PRIOR TO ANY CONCRETE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER, LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND FINISHING TOOLS. ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY.
- 10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL MEASURES ARE CONSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS.
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT, CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL. THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION METERIAL IS NOT DISPOSED OF IN THE WETLANDS.
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED BY AN APPROVED MEANS.
- 13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON A REGULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER, WHICHEVER IS LESS.
- 14. ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OPERATIONAL.
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER, ALL OPEN AREAS THAT ARE TO REMAIN IDLE THAPOUGHOUT THE WINTER SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING.
- 16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.

IL. CONTRACT: DI035
IL. LETTING ITEM: 02A

IL. PROJECT: C73-5064

S.B.G. PROJECT: 3-17-SBGP-197

REVISIONS

NUMBER BY DATE

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

Z

S

DIXON MUNICIPAL AIRPORT
DIXON, ILLINOIS
REHABILITATE RUNWAY 12/30
ORMWATER POLLUTION PREVENTION
NOTES

CRAWFORD, MAPPHY 8 TLLY, NC.
CONSULTING ENGINEERS
LICENSE No. 184-000613

 DESIGN BY:
 STL

 DRAWN BY:
 JRO

 CHECKED BY:
 STL

 APPROVED BY:
 DKP

 DATE:
 07/25/2025


 JOB No:
 22004684-00

FINAL

SHEET 10 OF 22 SHEETS

ILE: K:\DixonAp\22004684.00 RehabRwy1230\Draw\Sheets/2200468400 - Dixon - Swppp Notes.dwg

ursday, July 17, 2025 8:58:04 AM




RUNWAY 12/30 TYPICAL SECTION A-A

NOT TO SCALE

LEGEND

- (A) NEW 2" AND VARIABLE DEPTH BITUMINOUS SURFACE MILLING (401) NEW 2" BITUMINOUS SURFACE COURSE (401)
- NEW BITUMINOUS TACK COAT (603)
- 0 EXISTING BITUMINOUS PAVEMENT (DEPTH VARIES)
- (D) EXISTING 7" CRUSHED AGGREGATE BASE COURSE
- EXISTING GROUNDLINE (E)
- SHOULDER ADJUSTMENT (152), SEEDING (901) AND
- HEAVY-DUTY HYDRAULIC MULCHING (908)

| | | HMA MIXTURE REQU | UIREMENTSTABLE | | |
|------------------------------------|------------------------------------|---|-------------------|-----------|---------------------------|
| ITEM | RUNWAY/TAXIWAY (<60K LBS) N DES | PG BINDER | AGGREGATE QUALITY | MAX RAP % | DENSITY ACCEPTANCE |
| 401: HMA SURFACE | N30@ 3.0% | SBS PG 70-28 | A | 0 (N/A) | PWL |
| 403: HMA BASE (REM & REP PAV'T) | N30 @ 3.0% | SBS PG 70-28 (TOP LIFT) PG-64-22 (LOWER LIFTS) | В | 20% | PATCHING: NUCLEAR DENSITY |




STABILIZATION TYPICAL SECTION

NOT TO SCALE


STABILIZATION NOTES:


- LOCATIONS FOR FURNISHING AND PLACING POROUS GRANULAR EMBANKMENT SHALL BE AS THE FIELD CONDITIONS WARRANT AT THE TIME OF CONSTRUCTION. THIS MATERIAL IS INTENDED TO REPAIR SOFT SUBGRADE AS DIRECTED BY THE RESIDENT ENGINEER. NO ADJUSTMENT IN UNIT PRICE WILL BE ALLOWED FOR AN INCREASE OR DECREASE IN IN ONLY FRICE WILL BE ALLOWED FOR AN INCREASE ON DECREASE IN QUANTITIES. EXCAVATION OF THE SOFT SUBGRADE SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR UNCLASSIFIED EXCAVATION (REFER TO STABILIZATION TYPICAL SECTION).
- 2. STABILIZATION TYPICAL SECTION APPLIES TO REMOVE AND REPLACE BITUMINOUS PAVEMENT TYPE B IF REQUIRED.

- TOPSOIL REQUIRED FOR FILL SHALL BE INCLUDED IN THE COSTS FOR SHOULDER ADJUSTMENT (AR152480).
- 2. LIMITS OF TURF SHOULDER SHALL BE ADJUSTED IN THE FIELD AS REQUIRED AT NO ADDITIONAL COST TO THE CONTRACT.
- 3. THE DEFAULT WIDTH OF SHOULDER ADJUSTMENT, TOPSOILING, SEEDING AND HEAVY DUTY MULCHING SHALL BE 5'. IF THE EXISTING ELEVATION CANNOT BE MET AFTER 5' AT A 5% MAXIMUM SLOPE, THESE ITEMS MAY EXTEND OUT AN ADDITIONAL 5' MAXIMUM AT A 5% MAXIMUM SLOPE.
- SHOULDER DROP-OFF SHOULD BE 1.5-INCH WITH A PLUS/MINUS TOLERANCE OF 1/2 INCH FROM THE EDGE OF THE PAVEMENT TO THE ADJACENT UNPAVED AREAS.



KEY MAP





REMOVE AND REPLACE BITUMINOUS PAVEMENT - TYPE B

NOT TO SCALE

PAVEMENT REMOVAL AND REPLACEMENT NOTES

- DEPTHS OF EXISTING PAVEMENTS SECTIONS ARE APPROXIMATE BASED ON DATA SUPPLIED BY RECORDS, AIRPORT PERSONNEL, AND PAVEMENT CORES. THE CONTRACTOR SHALL VERIFY THE TYPE AND THICKNESS OF MATERIAL TO REMOVE. NO EXTRA COMPENSATION WILL BE ALLOWED FOR ANY VARIATION IN THE PAVEMENT SECTIONS ACTUALLY ENCOUNTERED
- 2. PAVEMENT REMOVAL AND REPLACEMENT QUANTITIES ARE ESTIMATED. EXISTING MEDIUM TO HIGH SEVERITY TRANSVERSE CRACKS ARE SPACED AT VARIABLE INTERVALS. THE RESIDENT ENGINEER SHALL LAY OUT PAVEMENT REMOVAL AND REPLACEMENT AREAS IN THE FIELD DURING CONSTRUCTION.
- 3. THIS WORK SHALL BE DETERMINED IN THE FIELD WITH THE AIRPORT/ENGINEER.
- 4. CONTRACTOR SHALL CONSTRUCT THE TOP 4" OF THE FULL DEPTH PAVEMENT REMOVAL AND REPLACEMENT WITH BITUMINOUS SURFACE COURSE (401).
- 5. THE EXISTING SURFACES ARE CONSTRUCTED TO EXISTING SURFACE GRADES AFTER THE COMPLETION OF OPERATIONS FOR REMOVE AND REPLACE BITUMINOUS TYPE A AND TYPE B.
- 6. CONTRACTOR SHALL INSTALL TACK COAT BETWEEN PAVEMENT LIFTS. COST INCIDENTAL TO REMOVE AND REPLACE BITUMINOUS TYPE

IL. CONTRACT: DI035 IL. LETTING ITEM: **02A** IL. PROJECT: C73-5064 S.B.G. PROJECT: 3-17-SBGP-197

REVISIONS NUMBER BY DATE

THIS BAR IS FOLIAL TO 2" AT FULL SCALE (34X22).


TYPICAL SECTIONS AND AVEMENT REHABILITATION DETAIL DIXON MUNICIPAL AIRPORT DIXON, ILLINOIS REHABILITATE RUNWAY 12/30


JRPHY & IGINEERS ΣU


DESIGN BY STL DRAWN BY JRO CHECKED BY DKP APPROVED BY 07/25/2025 JOB No: 22004684-00


FINAL


SHEET 11 OF 22 SHEETS














| _ | | | _ | | | | | _ | | | _ | | | Т | | | _ | | | _ | | | | | _ | | | | | | 3 |
|---|---------------|--------|--------|---------|-------|--------|---|-----------------|-----------|------|--------|--------|-------|-----|---------|--------|------------|-------------|-----|--------|---------|--------|--------------------|--------|--------|----|------------|--------|------------|---|-------|
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 193 | 15. | | | | | | | 4.53 | 783.13 | | | | | | | | -05.39 | EV = 783.79 | | | | 1 | FLEV = 784.30 | | | | ٥ | | 228+29.77 | 5 | |
| က် | ELEV = 782.51 | | NE' | W CENTE | RLI | NE | | VPI = 224+54.53 | ELEV = 78 | | | | | | | | VPI = 226- | ELEV = 7 | | | | | VPI = ZZ ELEV = | | | | VAY 30 END | 8+02 | VPI = 228- | | 7 |
| Λ | ш / | _ | \$U | | | HLE | | 7 | | | | 0. | 44% | | | | | | | 0. | 50% | | | 0 | .35 | i% | EGN. | STA 22 | VPI = 228 | | |
| | | | | 0.41% | | | | - | 4 | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | EX | (ISTING | CEN | TEF | RLINE | SUR | FAC | CE PROF | ILE | | | | | | | | | |
| | Š | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| NOTE OF THE PARTY | STING ELEVAI | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 702.50 NE | | 782.70 | 782.70 | | 82.91 | 782.92 | 3 | 183. | /83.11 | 0000 | 783.33 | /83.32 | 33.55 | 100 | 93.54 | 783 77 | 27 007 | 0,70 | | 784.01 | 784.04 | 784.26 | 784.27 | 784.45 | 784 43 | | 784.62 | 784.62 | | | |
| 1 | 7 | 2 | 12 | | ~ | 12 | ì | ا | ١. | ì | ۱ | 7 | ~ | 1 | ۲ | ř | Ĭ | ۲ | | ~ | K | 2 | 2 | ~ | 1 | | 2 | 7 | | | ŀ |

| | | _ | RUN | NAY 12/30 | GRADIN | G TABLE | | _ | |
|-----------|-----------|-----------|--------|-----------|-----------|---------|------------|-----------|---------|
| | 37.5' LEF | T OF CENT | ERLINE | | CENTERLIN | IE | 37.5' RIGI | HT OF CEN | TERLINE |
| STATION | PROP | EXST | MILL | PROP | EXST | MILL | PROP | EXST | MILL |
| | ELEV. | ELEV. | DEPTH | ELEV. | ELEV. | DEPTH | ELEV. | ELEV. | DEPTH |
| 200+00.00 | 775.77 | 775.77 | 0.17 | 776.30 | 776.26 | 0.13 | 775.82 | 775.82 | 0.17 |
| 200+50.00 | 776.35 | 776.35 | 0.17 | 776.80 | 776.95 | 0.32 | 776.43 | 776.43 | 0.17 |
| 201+00.00 | 776.61 | 776.61 | 0.17 | 777.31 | 777.24 | 0.10 | 776.73 | 776.73 | 0.17 |
| 201+50.00 | 776.95 | 776.95 | 0.17 | 777.62 | 777.58 | 0.13 | 777.06 | 777.06 | 0.17 |
| 202+00.00 | 777.21 | 777.21 | 0.17 | 777.93 | 777.89 | 0.13 | 777.33 | 777.33 | 0.17 |
| 202+50.00 | 777.50 | 777.50 | 0.17 | 778.23 | 778.18 | 0.12 | 777.66 | 777.66 | 0.17 |
| 203+00.00 | 777.84 | 777.84 | 0.17 | 778.54 | 778.50 | 0.13 | 777.96 | 777.96 | 0.17 |
| 203+50.00 | 778.19 | 778.19 | 0.17 | 778.85 | 778.85 | 0.17 | 778.31 | 778.31 | 0.17 |
| 204+00.00 | 778.51 | 778.51 | 0.17 | 779.14 | 779.15 | 0.18 | 778.61 | 778.61 | 0.17 |
| 204+50.00 | 778.80 | 778.80 | 0.17 | 779.43 | 779.43 | 0.17 | 778.87 | 778.87 | 0.17 |
| 205+00.00 | 779.05 | 779.05 | 0.17 | 779.71 | 779.71 | 0.17 | 779.16 | 779.16 | 0.17 |
| 205+50.00 | 779.32 | 779.32 | 0.17 | 780.00 | 779.98 | 0.15 | 779.46 | 779.46 | 0.17 |
| 206+00.00 | 779.65 | 779.65 | 0.17 | 780.29 | 780.29 | 0.17 | 779.74 | 779.74 | 0.17 |
| 206+50.00 | 779.98 | 779.98 | 0.17 | 780.58 | 780.57 | 0.16 | 780.04 | 780.04 | 0.17 |
| 207+00.00 | 780.25 | 780.25 | 0.17 | 780.87 | 780.86 | 0.16 | 780.32 | 780.32 | 0.17 |
| 207+50.00 | 780.49 | 780.49 | 0.17 | 781.16 | 781.16 | 0.17 | 780.60 | 780.60 | 0.17 |
| 208+00.00 | 780.75 | 780.75 | 0.17 | 781.44 | 781.45 | 0.18 | 780.86 | 780.86 | 0.17 |
| 208+50.00 | 780.98 | 780.98 | 0.17 | 781.68 | 781.73 | 0.22 | 781.15 | 781.15 | 0.17 |
| 209+00.00 | 781.23 | 781.23 | 0.17 | 781.92 | 781.93 | 0.18 | 781.29 | 781.29 | 0.17 |
| 209+50.00 | 781.27 | 781.27 | 0.17 | 782.01 | 782.01 | 0.17 | 781.42 | 781.42 | 0.17 |
| 210+00.00 | 781.40 | 781.40 | 0.17 | 782.03 | 782.04 | 0.18 | 781.42 | 781.42 | 0.17 |
| 210+50.00 | 781.38 | 781.38 | 0.17 | 782.05 | 782.05 | 0.17 | 781.46 | 781.46 | 0.17 |
| 211+00.00 | 781.40 | 781.40 | 0.17 | 782.03 | 782.03 | 0.17 | 781.40 | 781.40 | 0.17 |
| 211+50.00 | 781.35 | 781.35 | 0.17 | 781.95 | 781.94 | 0.16 | 781.32 | 781.32 | 0.17 |
| 212+00.00 | 781.25 | 781.25 | 0.17 | 781.85 | 781.85 | 0.17 | 781.26 | 781.26 | 0.17 |
| 212+50.00 | 781.15 | 781.15 | 0.17 | 781.74 | 781.74 | 0.17 | 781.16 | 781.16 | 0.17 |
| 213+00.00 | 781.16 | 781.16 | 0.17 | 781.67 | 781.67 | 0.17 | 781.16 | 781.16 | 0.17 |
| 213+50.00 | 781.20 | 781.20 | 0.17 | 781.65 | 781.65 | 0.17 | 781.22 | 781.22 | 0.17 |
| 213+87.60 | 781.14 | 781.14 | 0.17 | 781.65 | 781.65 | 0.17 | 781.21 | 781.21 | 0.17 |
| 217+48.00 | 781.17 | 781.17 | 0.17 | 781.66 | 781.66 | 0.17 | 781.08 | 781.08 | 0.17 |
| 218+00.00 | 781.12 | 781.12 | 0.17 | 781.63 | 781.64 | 0.18 | 781.11 | 781.11 | 0.17 |
| 218+50.00 | 780.97 | 780.97 | 0.17 | 781.57 | 781.55 | 0.15 | 780.96 | 780.96 | 0.17 |
| 219+00.00 | 780.90 | 780.90 | 0.17 | 781.51 | 781.51 | 0.17 | 780.93 | 780.93 | 0.17 |
| 219+50.00 | 781.01 | 781.01 | 0.17 | 781.61 | 781.63 | 0.19 | 781.05 | 781.05 | 0.17 |
| 220+00.00 | 781.13 | 781.13 | 0.17 | 781.72 | 781.72 | 0.17 | 781.12 | 781.12 | 0.17 |
| 220+50.00 | 781.25 | 781.25 | 0.17 | 781.86 | 781.86 | 0.17 | 781.26 | 781.26 | 0.17 |
| 221+00.00 | 781.36 | 781.36 | 0.17 | 782.00 | 781.97 | 0.14 | 781.37 | 781.37 | 0.17 |
| 221+50.00 | 781.52 | 781.52 | 0.17 | 782.15 | 782.15 | 0.17 | 781.56 | 781.56 | 0.17 |
| 222+00.00 | 781.65 | 781.65 | 0.17 | 782.26 | 782.28 | 0.19 | 781.68 | 781.68 | 0.17 |
| 222+50.00 | 781.74 | 781.74 | 0.17 | 782.39 | 782.35 | 0.13 | 781.77 | 781.77 | 0.17 |
| 223+00.00 | 781.88 | 781.88 | 0.17 | 782.50 | 782.50 | 0.17 | 781.93 | 781.93 | 0.17 |
| 223+50.00 | 782.09 | 782.09 | 0.17 | 782.70 | 782.71 | 0.18 | 782.09 | 782.09 | 0.17 |
| 224+00.00 | 782.31 | 782.31 | 0.17 | 782.91 | 782.92 | 0.18 | 782.27 | 782.27 | 0.17 |
| 224+50.00 | 782.53 | 782.53 | 0.17 | 783.11 | 783.11 | 0.17 | 782.52 | 782.52 | 0.17 |
| 225+00.00 | 782.73 | 782.73 | 0.17 | 783.32 | 783.32 | 0.17 | 782.75 | 782.75 | 0.17 |
| 225+50.00 | 782.93 | 782.93 | 0.17 | 783.55 | 783.54 | 0.16 | 782.97 | 782.97 | 0.17 |
| 226+00.00 | 783.15 | 783.15 | 0.17 | 783.76 | 783.77 | 0.18 | 783.19 | 783.19 | 0.17 |
| 226+50.00 | 783.44 | 783.44 | 0.17 | 784.01 | 784.04 | 0.20 | 783.44 | 783.44 | 0.17 |
| 227+00.00 | 783.71 | 783.71 | 0.17 | 784.26 | 784.27 | 0.18 | 783.69 | 783.69 | 0.17 |
| 227+50.00 | 783.92 | 783.92 | 0.17 | 784.45 | 784.42 | 0.14 | 783.93 | 783.93 | 0.17 |
| 228+01.70 | 784.00 | 784.00 | 0.17 | 784.61 | 784.61 | 0.17 | 783.90 | 783.90 | 0.17 |


IL. CONTRACT: DI035 IL. LETTING ITEM: **02A** IL. PROJECT: C73-5064 S.B.G. PROJECT: 3-17-SBGP-197 REVISIONS NUMBER BY DATE THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22). က RUNWAY 12-30 PLAN AND PROFILE DIXON MUNICIPAL AIRPORT DIXON, ILLINOIS REHABILITATE RUNWAY 12/30


CAWFORD, MURPHY & TILY, INC.
CONSULTING ENGINEERS
License No. 184-000613


| DESIGN BY: | STL |
|--------------|-------------|
| DRAWN BY: | JRO |
| CHECKED BY: | STL |
| APPROVED BY: | DKP |
| DATE: | 07/25/2025 |
| JOB No: | 22004684-00 |

FINAL

SHEET 17 OF 22 SHEETS








RUNWAY 12 LANDING DESIGNATOR

20'

N.T.S.

CENTER OF OUTER EDGES OF NUMERALS IS CENTERED ON THE PAVEMENT CENTERLINE. TYPICAL OF ALL DOUBLE RUNWAY DESIGNATIONS.



RUNWAY 30 LANDING DESIGNATOR

PAVEMENT MARKING NOTES

- 1. THE PAVEMENT SURFACE SHALL BE CLEAN AND DRY PRIOR TO MARKING.
- 2. WHEN YELLOW TAXIWAY STRIPING CROSSES ANY WHITE RUNWAY STRIPING, THE TAXIWAY STRIPE SHALL BE TERMINATED 6" EACH SIDE OF RUNWAY STRIPE EXCEPT RUNWAY/RUNWAY HOLDLINE (3').
- 3. ALL NEW AIRFIELD PAVEMENT MARKING SHALL HAVE REFLECTIVE BEADS AND 6"
- 4. BLACK BORDER DOES NOT RECEIVE REFLECTIVE BEADS.

NEW 6" OR 12" YELLOW TAXIWAY CENTERLINE STRIPE WITH 6" BLACK

120' TYP.


NEW TAXIWAY EXIT MARKING DETAIL

N.T.S.

- 5. ALL NUMERALS SHALL CONFORM TO FAA ADVISORY CIRCULAR 150/5340-1 (LATEST
- 6. WHEN EXISTING MARKINGS ARE TO BE REPAINTED OVER, THE CONTRACTOR SHALL SCRAPE THE EXISTING MARKINGS TO REMOVE LOOSE PAINT PRIOR TO NEW MARKING APPLICATION.
- 7. PAINT SHALL BE APPLIED IN TWO APPLICATIONS. THE FIRST APPLICATION WILL OCCUR ONCE THE SURFACE COURSE IS IN PLACE AND ACCEPTED BY THE RESIDENT ENGINEER. THE FIRST APPLICATION WILL NOT CONTAIN BEADS AND BLACK BORDER. A PERIOD OF 30 DAYS SHALL ELAPSE BETWEEN THE PLACEMENT OF THE FIRST PAINT APPLICATION AND SECOND PAINT APPLICATION. THE SECOND APPLICATION SHALL CONTAIN GLASS BEADS AND BLACK BORDER. PAINT SHALL BE APPLIED AT THE LOCATIONS AND TO THE DIMENSIONS AND SPACING AS SPECIFIED. PAINT SHALL NOT BE APPLIED UNTIL THE LAYOUT AND CONDITION OF THE SURFACE HAS BEEN APPROVED BY THE RESIDENT ENGINEER.


NEW CENTERLINE

WHITE WITH 6" BLACK




DASHED RUNWAY

N.T.S.



N.T.S.



TAXIWAY CENTERLINE CONTINUOUS

| NEW 12" X 120' WHITE DASHED (TYPICAL) |
|---|
| NEW 6" BLACK BORDER 12/30 CENTERLINE |

FINAL SHEET 21 OF 22 SHEETS

STL

JRO

DKP

07/25/2025 22004684-00

IL. CONTRACT: DI035

IL. LETTING ITEM: 02A IL. PROJECT: C73-5064

S.B.G. PROJECT: 3-17-SBGP-197

REVISIONS

BY

THIS BAR IS EQUAL TO 2"

AT FULL SCALE (34X22).

DATE

PAVEMENT MARKING DETAILS

DIXON MUNICIPAL AIRPORT DIXON, ILLINOIS REHABILITATE RUNWAY 12/30

CMT

DESIGN BY:

DRAWN BY:

CHECKED BY:

APPROVED BY:

JOB No:

NUMBER

