CONSTRUCTION PLANS

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21


AIRPORT AUTHORITY OF FLORA FLORA MUNICIPAL AIRPORT (FOA) FLORA, CLAY COUNTY, ILLINOIS


IDA PROJECT NO. FOA-5137 SBG PROJECT NO. 3-17-SBGP-TBD

100% SUBMITTAL JULY 25, 2025


NOTICE TO CONTRACTORS AND BIDDERS

THESE CONSTRUCTION PLANS RELY UPON THE SPECIAL PROVISIONS TO PROVIDE FOR A COMPLETE DESCRIPTION OF THE WORK AND CONSTRUCTION REQUIREMENTS. THE PLANS SHALL ONLY BE USED IN COMBINATION WITH ALL CONTRACT DOCUMENTS.





LOCATION MAP









JULY 25, 2025

	INDEX OF SHEETS				
SHEET NO.	SHEET TITLE				
1	COVER SHEET				
2	SUMMARY OF QUANTITIES AND INDEX OF SHEETS				
3	SITE AND SAFETY PLAN				
4	SAFETY NOTES AND DETAILS				
5	PHASING PLAN - PHASE 1				
6	PHASING PLAN - PHASE 2				
7	EXISTING AIRFIELD LIGHTING DEMOLITION PLAN - SHEET 1				
8	EXISTING AIRFIELD LIGHTING DEMOLITION PLAN - SHEET 2				
9	EXISTING AIRFIELD LIGHTING DEMOLITION PLAN - SHEET 3				
10	EXISTING AIRFIELD LIGHTING DEMOLITION PLAN - SHEET 4				
11	EXISTING AIRFIELD LIGHTING DEMOLITION PLAN - SHEET 5				
12	EXISTING AIRFIELD LIGHTING DEMOLITION PLAN - SHEET 6				
13	PROPOSED AIRFIELD LIGHTING PLAN - SHEET 1				
14	PROPOSED AIRFIELD LIGHTING PLAN - SHEET 2				
15	PROPOSED AIRFIELD LIGHTING PLAN - SHEET 3				
16	PROPOSED AIRFIELD LIGHTING PLAN - SHEET 4				
17	PROPOSED AIRFIELD LIGHTING PLAN - SHEET 5				
18	PROPOSED AIRFIELD LIGHTING PLAN - SHEET 6				
19	AIRFIELD LIGHTING NOTES 1				
20	LIGHT LENS SCHEDULES				
21	AIRFIELD LIGHT DETAILS				
22	TAXI GUIDANCE SIGN SCHEDULE AND NOTES				
23	LIGHTED TAXI GUIDANCE SIGN DETAILS				
24	UNLIGHTED TAXI GUIDANCE SIGN DETAILS				
25	AIRFIELD LIGHTING CABLE SPLICE DETAILS				
26	CONDUIT TRENCH DETAIL				
27	CABLE AND DUCT MARKER DETAILS				
28	HANDHOLE AND SPLICE CAN DETAILS				
29	ELECTRICAL NOTES SHEET 1				
30	ELECTRICAL NOTES SHEET 2				
31	GROUNDING DETAILS SHEET 1				
32	GROUNDING DETAILS SHEET 2				
33	GROUNDING DETAILS SHEET 3				
34	GROUNDING DETAILS SHEET 4				
35	GROUND RESISTANCE TESTING DETAILS				
36	GROUNDING NOTES				
37	ELECTRICAL LEGEND AND ABBREVIATIONS				
38	AIRPORT VAULT EQUIPMENT PLAN				
39	EXISTING ONE-LINE DIAGRAM FOR VAULT AND AIRFIELD				
40	ELECTRICAL ONE-LINE DIAGRAM FOR VAULT				
41	AIRFIELD LIGHTING CONTROL WIRING SCHEMATIC				
42	SERIES CIRCUIT CABLE TESTING DETAILS				

	SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	AS-BUILT QUANTITY	1	
AR108108	1/C #8 5 KV UG CABLE	FOOT	13,440		7	
AR109410	VAULT WIRING	LSUM	1		7	
AR110012	2" DIRECTIONAL BORE	FOOT	360		7	
AR110202	2 PVC DUCT, DIRECT BURY	FOOT	10,440			
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	2		7	
AR125462	TAXI GUIDANCE SIGN, UNLIT	EACH	2		7	
AR125511	MIRL, BASE MOUNTED-LED	EACH	48		7	
AR125565	SPLICE CAN	EACH	4		7	
AR150510	ENGINEER'S FIELD OFFICE	LSUM	1		7	
AR150520	MOBILIZATION	LSUM	1		7	
AR150530	TRAFFIC MAINTENANCE	LSUM	1		7	
AR800476	REMOVE AIRFIELD LIGHTING	LSUM	1		7	
AR800564	CABLE AND CCR TESTING AND CALIBRATION	LSUM	1		7	

GENERAL NOTES

- THE PROJECT PAY ITEMS ARE INTENDED TO BE INCLUSIVE OF ALL WORK TO BE PERFORMED AS SHOWN IN THESE PLANS. ALL INCIDENTAL WORK REQUIRED TO COMPLETE THE PROJECT TO THE SATISFACTION OF THE RESIDENT ENGINEER IS TO BE INCLUDED IN THE COSTS OF PERFORMING THESE ITEMS. THE CONTRACTOR SHALL FURNISH ALL LABOR, MATERIAL, EQUIPMENT, AND TRANSPORTATION NECESSARY TO CONSTRUCT ALL ELEMENTS OF THE PROJECT AS DESCRIBED IN THE CONSTRUCTION PLANS AND SPECIFICATIONS.
- 2. THE RULES, REGULATIONS, AND SPECIFICATIONS ENUMERATED HEREIN SHALL BE CONSIDERED AS MINIMUM REQUIREMENTS. THEY SHALL NOT PROHIBIT THE CONTRACTOR FROM FURNISHING AND INSTALLING HIGHER GRADES OF MATERIAL THAN ARE SPECIFIED HEREIN, IF APPROVED BY THE ENGINEER.
- 3. ACCESS TO THE SITE SHALL BE RESTRICTED EXCLUSIVELY TO THE DESIGNATED CONSTRUCTION ENTRANCE, STAGING AREA, AND HAUL ROUTE. NO EQUIPMENT OR PERSONNEL SHALL BE PERMITTED OUTSIDE THE GENERAL
- 4. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT AND KEEP CLEAN OF DEBRIS ALL EXISTING AIRFIELD AND ROADWAY PAVEMENTS AT ALL TIMES. ANY DAMAGE TO EXISTING ELECTRICAL, DRAINAGE, AND PAVEMENT STRUCTURES SHALL BE IMMEDIATELY REPAIRED AT NO ADDITIONAL COST TO THE CONTRACT.
- 5. CONTRACTOR IS REQUIRED TO PROVIDE THEIR OWN RESTROOM FACILITIES.
- 6. THE OWNER SHALL HAVE THE RIGHT OF FIRST REFUSAL FOR ALL SALVAGEABLE MATERIAL REMOVED ON THE
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING PERMITS FOR HAULING ON PUBLIC ROADS, AS APPLICABLE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CORRECTING ANY DAMAGES TO ANY PAVEMENTS (PUBLIC OR PRIVATE) CAUSED BY HIS/HER CONSTRUCTION EQUIPMENT OR PERSONNEL.
- 8. THE CONTRACTOR SHALL PROVIDE ONE SET OF PRELIMINARY REDLINED RECORD DRAWINGS TO THE RESIDENT ENGINEER AT THE COMPLETION OF THE PROJECT FOR INCORPORATION INTO THE OFFICIAL RECORD DRAWINGS
- 9. APPROXIMATE LOCATIONS OF UNDERGROUND UTILITIES ARE SHOWN THROUGHOUT THESE PLANS. THE CONTRACTOR SHALL DETERMINE EXACT LOCATIONS AND PROTECT THESE UTILITIES DURING CONSTRUCTION. ANY UTILITIES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. CONTRACTOR SHALL COORDINATE WITH THE PROPER AUTHORITIES FOR THE PURPOSE OF LOCATING AND PROTECTING EXISTING UNDERGROUND UTILITIES
- 10. THE CONTRACTOR SHALL PROVIDE ALL LAYOUT NEEDS, BOTH VERTICALLY AND HORIZONTALLY.
- 11. ALL REQUESTS FOR INFORMATION SHALL BE PROVIDED IN WRITING AND ALL DIRECTIVES SHALL BE RECEIVED IN
- 12. CHANGES TO THE PROJECT SHALL NOT BE INCORPORATED INTO THE PROJECT UNTIL EXPRESSLY APPROVED BY
- 13. NPDES PERMIT THIS PROJECT WILL NOT DISTURB MORE THAN 1 ACRE, THEREFORE A NPDES PERMIT IS NOT
- 14. MATERIAL CERTIFICATIONS MATERIALS CANNOT BE INSTALLED UNTIL ALL THE MATERIAL CERTIFICATIONS FOR THAT ITEM HAVE BEEN RECEIVED, REVIEWED AND ACCEPTED BY THE RESIDENT ENGINEER. MATERIALS INSTALLED WITHOUT APPROVAL ARE SUBJECT TO REMOVAL AND REPLACEMENT AT THE CONTRACTOR'S EXPENSE.
- 15. CERTIFIED PAYROLLS PAY APPLICATIONS CANNOT BE PROCESSED FOR PAYMENT UNTIL ALL CERTIFIED PAYROLLS FOR THAT PERIOD HAVE BEEN RECEIVED.

UTILITY NOTE

THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY. COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED. THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

J.U.L.I.E. INFORMATION

COUNTY	CLAY
CITY	FLORA
TOWNSHIP	STANFORD
SECTION NO.	
ADDRESS	FLORA MUNICIPAL AIRPORT
	1 AIRPORT ROAD
	FLORA ILLINOIS 62839

BID DOCUMENTS



www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA. ILLINOIS 62839



SIGNED: 7/25/2025 EXPIRES: 11/30/2025

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

	NO.	DATE	DES	CRIPT	ION	
	INO.	DATE	DES	DWN	REV	
	ISSUE:	JULY 25	5, 2025	;		
i	PROJECT NO: 23A1038					
	CAD FIL	E: G-002-S	Q.DWG			

DESIGN BY:

DRAWN BY: CWS 4/30/2025 REVIEWED BY: LDH 6/24/2025

SHEET TITLE

SUMMARY OF **QUANTITIES AND INDEX OF SHEETS**

CONSTRUCTION SAFETY PLAN

- SCOPE OF WORK THE PROPOSED WORK CONSISTS OF REMOVAL AND REPLACEMENT OF THE RUNWAY LIGHTING SYSTEM FOR RUNWAY 3-21, THE ASSOCIATED TAXI SIGNS, CABLING, CONDUITS AND DUCT WORK, JUNCTION STRUCTURES, HANDHOLES, VAULT WORK AND INCIDENTALS.
- RUNWAY 3-21 AND 15-33 WILL BE CLOSED FOR PORTIONS OF THE PROJECT. TO MINIMIZE DISRUPTION TO AIRCRAFT OPERATIONS ASSOICATED WITH THE RUNWAY CLOSURE, CONSTRUCTION WORK MUST BE COMPLETED EXPEDITIOUSLY. RUNWAY CLOSINGS SHALL ONLY BE PERMITTED BY PRIOR AUTHORIZATION OF THE RESIDENT ENGINEER AND THE AIRPORT OWNER.
- GENERAL THE FLORA AIRPORT IS COMPRISED OF TWO RUNWAYS: A SOD RUNWAY 15-33 AND A
 PAVED RUNWAY 3-21. THIS PROJECT REQUIRES THE CONTRACTOR TO LIMIT THE EQUIPMENT
 HEIGHT TO 25' WHILE WORKING UNDER THE RUNWAY APPROACHES.
- 4. IDENTIFICATION WHEN THE CONTRACTORS VEHICLES AND EQUIPMENT ARE ON THE AIRPORT PROPERTY THEY SHALL BE PROPERLY MARKED WITH THREE (3') FOOT SQUARE CHECKERED FLAGS (INTERNATIONAL ORANGE AND WHITE). THE CONTRACTOR WILL ALSO PROVIDE WORKERS WITH SOME TYPE OF TAG OR GARMENT TO IDENTIFY THE PERSON AS BEING PART OF THE CONSTRUCTION CREW
- RADIO CONTROL THE CONTRACTOR WILL BE REQUIRED TO BE IN TWO-WAY RADIO CONTACT (122.70 MHz.) WITH THE AIRPORT UNICOM. THIS WILL KEEP THE CONTRACTOR IN CONSTANT

- CONTACT WITH THE FLORA AIRPORT AND ENABLE THE AIRPORT TO IMMEDIATELY CONTACT THE CONTRACTOR IN CASE OF AN AERONAUTIC EMERGENCY THAT WOULD REQUIRE ACTION BY THE CONTRACTOR AND/OR HIS PERSONNEL.
- 6. AIRPORT SECURITY WILL BE MAINTAINED AT ALL TIMES. ONLY CONTRACTOR EMPLOYEES SHALL BE ALLOWED WITHIN THE PROJECT LIMITS. GATES SHALL BE CLOSED AT ALL TIMES UNLESS THE CONTRACTOR IS IN A CONTINUOUS HAULING OPERATIONS, DURING WHICH TIME HE WILL PROVIDE A PERSON TO MONITOR THE GATE AREA.
- 7. THE CONTRACTOR WILL USE THE AIRPORT ENTRANCE ROAD FOR ACCESS TO THE PROPERTY AS THE DESIGNATED HAUL ROUTE. THE CONTRACTOR SHALL PARK EQUIPMENT AND PLACE MATERIALS WITHIN THE LIMITS OF THE SUBJECT PROPERTY. THE CONTRACTOR WILL BE REQUIRED TO MAINTAIN THE PROPOSED HAUL ROUTE AND SUBJECT PROPERTY THROUGHOUT THE COURSE OF THE PROJECT. ANY AREAS DAMAGED OUTSIDE OF THESE AREAS WILL BE REPAIRED BY THE CONTRACTOR AND AT THE CONTRACTOR'S OWN EXPENSE. AT THE CONCLUSION OF THE PROJECT THE CONTRACTOR WILL RESTORE THE HAUL ROUTE AND PARKING AREA TO ITS ORIGINAL STATE. RESTORATION OF THE HAUL ROUTE AND ANY AREAS USED FOR PARKING WILL BE CONSIDERED INCIDENTAL TO THE PROJECT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 8. ALL CONSTRUCTION EQUIPMENT ON THE AIRPORT SHALL BE MARKED, LIGHTED AND/OR FLAGGED IN ACCORDANCE WITH AC 150/5210-5 (CURRENTEDITION) AND 70/7460-1 (CURRENT EDITION)

	CONTROL POINTS						
POINT#	DESCRIPTION	GROUND (MSL)	HEIGHT (AGL)				
1	CONST. EQUIP. 1	038° 40' 07.59"	-088° 27' 07.77"	471'	25'		
2	CONST. EQUIP. 2	038° 40' 07.19"	-088° 27' 07.77"	471'	25'		
3	HAUL ROUTE	038° 39' 51.24"	-088° 27' 10.04"	467'	25'		
4	BARRICADE 1	038° 40' 07.63"	-088° 27' 01.77"	467'	2'		
5	BARRICADE 2	038° 40' 04.18"	-088° 27' 04.28"	463'	2'		



Offices Nationwide

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839



Junday Hausman

DATE LICENSE SIGNED: 7/25/2025 EXPIRES: 11/30/2025

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DES	CRIPT	ION
NO.	DATE	DES	DWN	REV
SSUE: JULY 25, 2025				
PROJECT NO: 23A1038				


PROJECT NO: 23A1038
CAD FILE: G-003-SFY.DWG


DESIGN BY: ---DRAWN BY: ----

SHEET TITLE

REVIEWED BY: LDH 6/24/2025


SITE AND SAFETY PLAN





- 1. TEMPORARY "CLOSED RUNWAY" MARKINGS SHALL BE "AVIATION YELLOW"
- TEMPORARY "CLOSED RUNWAY" MARKINGS SHALL BE CONSTRUCTED OF PLYWOOD, DOUBLE-LAYERED SNOW FENCE OR APPROVED FABRIC AND SHALL BE SECURED TO PAVEMENT BY SANDBAGS OR OTHER APPROVED METHOD.
- TEMPORARY "CLOSED RUNWAY" MARKINGS SHALL BE PLACED OVER THE RUNWAY DESIGNATION NUMBERS UNLESS OTHERWISE DIRECTED BY THE RESIDENT ENGINEER/TECHNICIAN.
- 7. COST FOR PROVIDING, PLACING, MAINTAINING, RELOCATING AND REMOVING "CLOSED RUNWAY" MARKINGS SHALL BE PAID UNDER TRAFFIC MAINTENANCE, ITEM AR150530. UNLESS OTHERWISE NOTED.

TEMPORARY CLOSURE CROSS DETAIL



LOW-PROFILE BARRICADE DETAIL

DETAIL ABOVE REPRESENTS ONE OPTION FOR LOW-PROFILE BARRICADES. OTHER OPTIONS MAY BE UTILIZED AS LONG AS THEY MEET THE REQUIREMENTS OF THE PROJECT, INCLUDING BARRICADE NOTE 1.

BARRICADE NOTES

- ALL CONSTRUCTION SIGNS AND TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES INCLUDING THE ILLINOIS SUPPLEMENT (LATEST EDITION) AND THE FAA ADVISORY CIRCULARS (LATEST EDITION) UNLESS NOTED OTHERWISE. THE FAA OR MORE STRINGENT SPECIFICATIONS SHALL GOVERN.
- 2. BARRICADES SHALL BE INTERLOCKED END TO END OVER THE LENGTH OF THE PAVEMENT WHERE PROTECTING OPEN RUNWAYS, AND SPACED END TO END A MAXIMUM OF 4 FEET IN OTHER ALL OTHER AREAS. BARRICADES ARE TO BE SET BACK FROM THE ACTIVE RUNWAY OR TAXIWAY CENTERLINE THE DISTANCE AS SHOWN ON THE PLANS.
- CONSTRUCTION RED WARNING LIGHT: THESE ARE PORTABLE, LENS DIRECTED, ENCLOSED LIGHTS. THE COLOR OF THE LIGHT EMITTED SHALL BE RED. THEY MAY BE USED IN EITHER A STEADY BURN (TYPE C) OR LOW INTENSITY FLASHING MODE (TYPE A) UNLESS NOTED OTHERWISE.
- 4. THE LIGHTING SHALL BE MAINTAINED IN OPERATION DURING THE HOURS OF DARKNESS BETWEEN 1/2 HOUR AFTER SUNSET AND 1/2 HOUR BEFORE SUNRISE AND WHEN CONDITIONS EXIST WHICH TEND TO OBSCURE VISION.
- BARRICADES SHALL BE SECURED TO THE GROUND BY APPROVED METHODS TO PREVENT MOVEMENT BY PROP WASH, JET BLAST OR OTHER WIND CURRENTS.
- 6. THE ONLY COLOR COMBINATION ON BARRICADES IS ORANGE AND WHITE. THE ORANGE STRIPES SHALL BE ENCAPSULATED LENS REFLECTIVE SHEETING. THE WHITE STRIPES SHALL BE EITHER ENCAPSULATED OR ENCLOSED LENS REFLECTIVE SHEETING AND MUST BE IN ACCEPTABLE CONDITION.
- COST FOR PROVIDING, PLACING, MAINTAINING, RELOCATING AND REMOVING BARRICADES SHALL BE PAID UNDER TRAFFIC MAINTENANCE, ITEM AR150530, UNLESS OTHERWISE NOTED.

SAFETY NOTES

- ALL PROVISIONS OF THE LATEST EDITION OF FAA ADVISORY CIRCULAR AC 150/5370-2 (CURRENT EDITION), "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION", APPLY TO THIS CONTRACT, EXCEPT AS MODIFIED BY THIS SAFETY PLAN. ANY FURTHER MODIFICATIONS REQUESTED MUST BE APPROVED BY THE AIRPORT, RESIDENT ENGINEER/TECHNICIAN AND THE FAA.
- THE CONTRACTORS SHALL MINIMIZE DISRUPTION OF STANDARD OPERATING PROCEDURES FOR AERONAUTICAL ACTIVITY BY REMAINING WITHIN THE PRESCRIBED STAGING, CONSTRUCTION, AND PHASING AREAS PRESENTED ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEETS.
- NO UNAUTHORIZED PERSONNEL SHALL ENTER ANY AREA OF THE AIRPORT THAT COULD
 POTENTIALLY BE HAZARDOUS. THE AIRPORT MANAGER RESERVES THE RIGHT TO
 SUSPEND OPERATIONS IN ORDER TO MAINTAIN SAFETY AT THE AIRPORT.
- 4. NO CONSTRUCTION VEHICLES SHALL BE DRIVEN ACROSS ANY ACTIVE AIRFIELD PAVEMENT AREA WITHOUT AN APPROPRIATE ESCORT. CONSTRUCTION EQUIPMENT OR CONSTRUCTION ACTIVITY WILL NOT BE PERMITTED WITHIN 250' OF ANY ACTIVE RUNWAY CENTERLINE OR WITHIN 131' OF ANY OTHER ACTIVE AIRPORT TAXIWAY OR APRON.
- CONTRACTOR EQUIPMENT, VEHICLES, AND PROJECT MATERIALS SHALL BE STORED AT THE STAGING AREA SHOWN ON THE PLAN VIEW, EXCEPT AS OTHERWISE PROVIDED FOR AT THE PRECONSTRUCTION CONFERENCE.
- ALL CONSTRUCTION EQUIPMENT OPERATING IN THE PRESCRIBED CONSTRUCTION AREA IS REQUIRED TO DISPLAY A CHECKERBOARD FLAG PROPERLY LOCATED OR A ROTATING BEACON (STROBE) AS SPECIFIED IN AC 150/5210-5, "PAINTING, MARKING, AND LIGHTING OF VEHICLES USED ON AN AIRPORT" LATEST EDITION.
- NO CONSTRUCTION MATERIAL STOCKPILES SHALL BE LOCATED WITHIN 500' OF ANY
 ACTIVE RUNWAY, WITHIN 131' OF ANY OTHER ACTIVE AIRPORT OPERATIONS AREA, OR
 PENETRATE A PART 77 IMAGINARY SURFACE (PROVIDED BY THE RESIDENT
 ENGINEER/TECHNICIAN) EXTENDING OUT AND UPWARDS FROM ALL SIDES OF AN ACTIVE
 RUNWAY.
- 8. CLOSED AIRFIELD PHASING AREAS, OPEN TRENCHES, AND STOCKPILED MATERIALS AT THE CONSTRUCTION SITE SHALL BE PROMINENTLY MARKED WITH LIGHTED BARRICADES WITH STEADY BURNING OR FLASHING RED LIGHTS AS SPECIFIED IN 150/5370-2, "OPERATIONAL SAFETY ON AIRPORT DURING CONSTRUCTION", LATEST EDITION. LIGHTED BARRICADES MUST BE NO TALLER THAN 18" (EXCLUSIVE OF SUPPLEMENTARY LIGHTS AND FLAGS) ON THE TAXIWAYS AND COMPLY WITH ADVISORY CIRCULAR 150/5370-2, LATEST EDITION. CONTRACTOR SHALL NIGHT CHECK BARRICADES DAILY FOR PROPER OPERATION.
- OPEN TRENCHES, EXCAVATIONS, AND STOCKPILED MATERIALS AT THE CONSTRUCTION SITE SHOULD BE PROMINENTLY MARKED WITH ORANGE FLAGS AND LIGHTED WITH FLASHING RED LIGHTS DURING HOURS OF RESTRICTED VISIBILITY AND/OR DARKNESS.
- 10. NO CONSTRUCTION EQUIPMENT GREATER THAN 25' TALL WILL BE PERMITTED ON THE AIRPORT WITHOUT THE APPROVAL OF THE AIRPORT MANAGER AND ADDITIONAL AIRSPACE APPROVAL BY THE FAA. AIRSPACE APPROVALS REQUIRE CONSIDERABLE LEAD TIME AND SHOULD BE REQUESTED WELL IN ADVANCE.
- 11. NO OPEN FLAME WELDING OR TORCH CUTTING OPERATION IS PERMITTED UNLESS ADEQUATE FIRE AND SAFETY PRECAUTIONS ARE PROVIDED AND HAVE BEEN APPROVED BY THE AIRPORT MANAGER NO FLARE POTS ARE ALLOWED ON THE PROJECT.
- 12. SOIL, DEBRIS, AND LOOSE MATERIAL DROPPED OR TRUCKED ONTO AIRPORT ROADS, TAXIWAYS, AND SOD SURFACES, OR WHICH CAN BE BLOWN ONTO SUCH SURFACES, SHALL BE IMMEDIATELY SWEPT, PICKED UP AND REMOVED, OR PLACED INTO CLOSED CONTAINERS. AND DAMAGE TO AIRPORT PROPERTY SHALL BE REPAIRED IMMEDIATELY AT NO COST TO THE OWNER.
- 13. CONTRACTOR SHALL TAKE MEASURES TO AVOID TRACKING ASPHALT MATERIALS ONTO ADJACENT PAVEMENT AREAS, UNLESS SUFFICIENT PROTECTION HAS BEEN APPLIED. HEAVY TRACKING OR DAMAGE TO ADJACENT PAVEMENTS MAY BE CAUSE FOR STOPPING THE WORK UNTIL ACCEPTABLE PROTECTION OR CHANGE IN WORK METHODS HAS BEEN PROVIDED.
- 14. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND MAINTAINING AIRPORT LIGHTING AND NAVIGATIONAL ELECTRICAL SYSTEMS DURING CONSTRUCTION. A CONTACT PERSON AND TELEPHONE NUMBER FOR 24 HOUR EMERGENCY IMMEDIATE REPAIR SHALL BE SUBMITTED TO THE AIRPORT MANAGER AND RESIDENT ENGINEER/TECHNICIAN. HAUL ROUTES CROSSING PAVEMENT, DRAINAGE, MISCELLANEOUS. STRUCTURES AND/OR AIRFIELD CABLES SHALL BE PROTECTED FROM DAMAGE.
- 15. ALL AIRCRAFT AND AIRPORT OPERATIONS HAVE THE RIGHT-OF-WAY. CONTRACTOR TO YIELD TO VEHICLES AND REMAIN CLEAR AT ALL TIMES.

- 16. CONTRACTOR SHALL PLACE, SECURE, AND MAINTAIN LIGHTED BARRICADES AND CLOSURE CROSSES WHEN A RUNWAY/TAXIWAY/APRON IS CLOSED OR AS REQUIRED BY THE PLANS AND DESIGNATED BY THE RESIDENT ENGINEER/TECHNICIAN.
- 17. CONTRACTOR SHALL MARK HAZARDOUS AREA WITH STEADY-BURNING OR FLASHING RED LIGHTS DURING PERIODS OF LOW VISIBILITY AS REQUIRED.
- 18. THE CONTRACTOR SHALL PERIODICALLY PERFORM ONSITE INSPECTIONS THROUGHOUT THE DURATION OF THE PROJECT WITH THE IMMEDIATE REMEDY OF ANY DIFFERENCES, WHETHER CAUSED BY NEGLIGENCE, OVERSIGHT, OR PROJECT SCOPE CHANGE.
- 19. CONTRACTOR SHALL MOVE MAINTENANCE OF TRAFFIC COMPONENTS AT THE WRITTEN DIRECTION OF THE RESIDENT ENGINEER/TECHNICIAN AT NO ADDITIONAL COST.
- 20. CONTRACTOR SHALL NOT REMOVE THE BARRICADES WITHOUT THE APPROVAL BY THE RESIDENT ENGINEER/TECHNICIAN.
- 21. CONTRACTOR SHALL MAINTAIN FLASHERS, SIGNS AND/OR BARRICADES AS REQUIRED BY THE PLANS, CITY OR COUNTY REGULATIONS OR CONTRACTOR ACTIVITIES.

 CONTRACTOR SHALL OBTAIN ANY AND ALL REQUIRED LOCAL PERMITS UNLESS SPECIFIED OTHERWISE.
- 22. THE CONTRACTOR SHALL UTILIZE WATER AND/OR CHEMICALS APPROVED BY THE RESIDENT ENGINEER/TECHNICIAN AS NECESSARY TO CONTROL DUST.
- 23. THE CONTRACTOR WILL BE RESPONSIBLE FOR IMPLEMENTING MEASURES TO CONTROL OR AVOID CREATING ATTRACTANTS TO WILDLIFE. MEASURES MAY INCLUDE CONTINUOUSLY REMOVING ANY WASTE OR LOOSE MATERIALS, PLACEMENT OF MATERIALS IN APPROPRIATE STORAGE CONTAINERS, PROPERLY MAINTAINING FENCES AND GATES TO PREVENT ACCESS, AND PREVENTING PONDING OF WATER THROUGHOUT THE SITE.
- 24. UNLESS SPECIFIED OTHERWISE, COST FOR SAFETY, STAGING, AND TRAFFIC MAINTENANCE ITEMS IS TO BE CONSIDERED INCIDENTAL TO THE PROJECT. SEPARATE PAYMENT SHALL NOT BE MADE.
- 25. THE CONTRACTOR SHALL HAVE THE SAFETY PLAN COMPLIANCE DOCUMENT (SPCD), AS DETAILED IN THE SPECIAL PROVISIONS, SUBMITTED AND APPROVED PRIOR TO BEING ISSUED "NOTICE TO PROCEED".
- 26. ALL RUNWAY/TAXIWAY CLOSURES SHALL BE COORDINATED WITH AIRPORT MANAGEMENT A MINIMUM OF 7 DAYS BEFORE THE DESIRED CLOSING TIME TO ALLOW FOR THE PROPER COORDINATION. AIRPORT MANAGEMENT HAS COMPLETE AUTHORITY IN DETERMINING WHEN THE RUNWAY/TAXIWAY MAY BE CLOSED.
- 27. RUNWAY/TAXIWAY CLOSURE PROCEDURES:
 - CONTACT THE AIRPORT MANAGEMENT OR ASSIGNED REPRESENTATIVE A MINIMUM OF 7 DAYS BEFORE THE DESIRED CLOSING TIME...
 - ISSUANCE OF NOTAM AND DEACTIVATION OF THE APPLICABLE AIRFIELD LIGHTING AND NAVAIDS BY THE AIRPORT MANAGEMENT AND/OR FAA.
 - PLACEMENT OF CROSSES AND BARRICADES.
 - ONLY AT THE TIME THAT ALL OF THE ABOVE ARE COMPLETED MAY ANY CONSTRUCTION OPERATIONS BEGIN WITHIN THE RUNWAY/TAXIWAY AIR OPERATIONS AREA.

RUNWAY/TAXIWAY RE-OPENING PROCEDURES:

- ENSURE ALL PERSONNEL, EQUIPMENT AND MATERIALS ARE CLEAR OF THE AIR OPERATIONS AREA.
- INSPECT THE AREA FOR LOOSE OR TRACKED DEBRIS, PAVEMENT DROP-OFFS, AND OPEN TRENCHES.
- CONTACT AIRPORT MANAGEMENT OR REPRESENTATIVE FOR FINAL INSPECTION OF THE AREA.
- REMOVE BARRICADES AND CROSSES.
- ACTIVATION OF THE AIRFIELD LIGHTING AND NAVAIDS AND CANCELLATION OF THE NOTAM BY THE AIRPORT MANAGEMENT AND/OR FAA.

HANSON Engineering | Planning | Allied Services

Offices Nationwide

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA. ILLINOIS 62839



DATE

SIGNED: 7/25/2025 EXPIRES: 11/30/2
INSTALL MEDIUM
INTENSITY RUNWAY

3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

LIGHTS ON RUNWAY

NO. DATE DESCRIPTION
DES DWN REV
ISSUE: JULY 25, 2025

PROJECT NO: 23A1038
CAD FILE: G-003-SFY.DWG

DESIGN BY: ---DRAWN BY: ---REVIEWED BY: LDH 6/24/2025

SHEET TITLE


SAFETY NOTES AND DETAILS

PHASE 1 NOTES

- WORK TO BE COMPLETED DURING PHASE 1:
 REMOVAL OF EXISTING LIGHTING, SIGNS AND ASSOCIATED CABLING.
 INSTALLATION OF LIGHTING, SIGNS AND ASSOCIATED CABLING.

 - REMOVE/INSTALL EQUIPMENT IN VAULT.
- 2. RUNWAY 3-21 WILL BE CLOSED DURING THIS PHASE.
- 3. RUNWAY 15-33 WILL REMAIN OPEN.

CONTROL POINTS					
POINT #	DESCRIPTION	LATITUDE	LONGITUDE	GROUND (MSL)	HEIGHT (AGL)
1	CONST. EQUIP. 1	038° 40' 07.59"	-088° 27' 07.77"	471'	25'
2	CONST. EQUIP. 2	038° 40' 07.19"	-088° 27' 07.77"	471'	25'
3	HAUL ROUTE	038° 39' 51.24"	-088° 27' 10.04"	467'	25'
4	BARRICADE 1	038° 40' 07.63"	-088° 27' 01.77"	467'	2'
5	BARRICADE 2	038° 40' 04.18"	-088° 27' 04.28"	463'	2'





www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839



INSTALL MEDIUM INTENSITY RUNWAY

LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DES	CRIPT	ION		
INO.	DATE	DES	DWN	REV		
SSUE: JULY 25, 2025						
PROJEC	PROJECT NO: 23A1038					
AD EILE: A SON SELVENING						

CAD FILE: G-003-SFY.DWG DESIGN BY:

DRAWN BY: ----

REVIEWED BY: LDH 6/24/2025


SHEET TITLE

PHASING PLAN -PHASE 1

PHASE 2 NOTES

- WORK TO BE COMPLETED DURING PHASE 2:
 REMOVAL OF EXISTING LIGHTING, SIGNS AND ASSOCIATED CABLING.
 INSTALLATION OF LIGHTING, SIGNS AND ASSOCIATED CABLING.
 - REMOVE/INSTALL EQUIPMENT IN VAULT.
- 2. RUNWAY 3-21 AND RUNWAY 15-33 WILL BE CLOSED DURING THIS PHASE.

CONTROL POINTS						
POINT #	DESCRIPTION	LATITUDE	LONGITUDE	GROUND (MSL)	HEIGHT (AGL)	
1	CONST. EQUIP. 1	038° 40' 07.59"	-088° 27' 07.77"	471'	25'	
2	CONST. EQUIP. 2	038° 40' 07.19"	-088° 27' 07.77"	471'	25'	
3	HAUL ROUTE	038° 39' 51.24"	-088° 27' 10.04"	467'	25'	
4	BARRICADE 1	038° 40' 07.63"	-088° 27' 01.77"	467'	2'	
5	BARRICADE 2	038° 40' 04.18"	-088° 27' 04.28"	463'	2'	





Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839



INSTALL MEDIUM

INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

	NO.	DATE	DES	CRIPT	ION
	NO.	DATE	DES	DWN	REV
į	ISSUE: JULY 25, 2025				
i	PROJECT NO: 23A1038				
(CAD FIL	E: G-003-S	FY.DWG		

DESIGN BY: DRAWN BY: ----

REVIEWED BY: LDH 6/24/2025

SHEET TITLE

PHASING PLAN -PHASE 2

EXISTING STAKE MOUNTED RUNWAY LIGHT TO BE REMOVED

EXISTING BASE MOUNTED RUNWAY LIGHT TO BE REMOVED

EXISTING TAXI/RUNWAY SIGN TO REMAIN

EXISTING RUNWAY THRESHOLD LIGHT TO REMAIN

EXISTING BASE MOUNTED TAXIWAY EDGE LIGHT TO REMAIN


HH EXISTING ELECTRICAL HANDHOLE


SC EXISTING SPLICE CAN

EXISTING WIND CONE

EXISTING WIND TEE

EXISTING PLASI





MATCHLINE STA. 10+00

HANSON Engineering Planning | Allied Service

Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

,

COVERING ELECTRICAL DESIGN

WEVEN N.

LIGHTFOOT

062-047643

E LICENSE NED: 7/29/2025 EXPIRES: 11/3

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21


IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD


NO. DATE DESCRIPTION
DES DWN REV
ISSUE: JULY 25, 2025
PROJECT NO: 23A1038
CAD FILE: E-101-PLNDWG
DESIGN BY: KNL 3/31/2025
DRAWN BY: CWS 4/3/2025

SHEET TITLE


EXISTING AIRFIELD LIGHTING DEMOLITION PLAN -SHEET 1


REVIEWED BY: KNL 6/24/2025





×	EXISTING STAKE MOUNTED RUNWAY LIGHT TO BE REMOVED
×	EXISTING BASE MOUNTED RUNWAY LIGHT TO BE REMOVED
	EXISTING TAXI/RUNWAY SIGN TO REMAIN
Φ	EXISTING RUNWAY THRESHOLD LIGHT TO REMAIN
0	EXISTING BASE MOUNTED TAXIWAY EDGE LIGHT TO REMAIN
□нн	EXISTING ELECTRICAL HANDHOLE
⊠sc	EXISTING SPLICE CAN
	EXISTING WIND CONE
T	EXISTING WIND TEE
	EXISTING PLASI





Professional Service Corporation #184-001084

Hanson Professional Services Inc.

Offices Nationwide


Illinois Licensed

AIRPORT

www.hanson-inc.com

1 AIRPORT ROAD

FLORA, ILLINOIS 62839




INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD





EXISTING AIRFIELD LIGHTING DEMOLITION PLAN -SHEET 2


REVIEWED BY: KNL 6/24/2025



EXISTING STAKE MOUNTED RUNWAY LIGHT TO BE REMOVED EXISTING BASE MOUNTED RUNWAY LIGHT TO BE REMOVED EXISTING TAXI/RUNWAY SIGN TO REMAIN EXISTING RUNWAY THRESHOLD LIGHT TO REMAIN EXISTING BASE MOUNTED TAXIWAY EDGE LIGHT TO ☑ HH EXISTING ELECTRICAL HANDHOLE \triangleright EXISTING WIND CONE EXISTING WIND TEE







Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**


1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN LIGHTFOOT 062-047643

INSTALL MEDIUM INTENSITY RUNWAY


LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD




EXISTING AIRFIELD LIGHTING **DEMOLITION PLAN -**SHEET 3


REVIEWED BY: KNL 6/24/2025



EXISTING STAKE MOUNTED RUNWAY LIGHT TO BE REMOVED EXISTING BASE MOUNTED RUNWAY LIGHT TO BE REMOVED EXISTING TAXI/RUNWAY SIGN TO REMAIN EXISTING RUNWAY THRESHOLD LIGHT TO REMAIN EXISTING BASE MOUNTED TAXIWAY EDGE LIGHT TO HH EXISTING ELECTRICAL HANDHOLE EXISTING SPLICE CAN P EXISTING WIND CONE EXISTING WIND TEE

EXISTING PLASI





phone: 217-788-2450 fax: 217-788-2503 Illinois Licensed Professional Service Corporation #184-001084

www.hanson-inc.com

1525 S. 6th Street Springfield, IL 62568

Hanson Professional Services Inc.

FLORA MUNICIPAL **AIRPORT**


1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN LIGHTFOOT 062-047643


INSTALL MEDIUM

INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD



EXISTING AIRFIELD LIGHTING **DEMOLITION PLAN -**SHEET 4




MATCHLINE (SEE NEXT SHEET)

EXISTING PLASI

EXISTING TELEPHONE

EXISTING GAS

___X___ EXISTING FENCE



HANSON Engineering | Planning | Allied Services

Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, II. 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

LORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN

TO THE SECOND SE

leving of highest

TE LICENS SNED: 7/29/2025 EXPIRE


INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIPTION
DES DWN REV
ISSUE: JULY 25, 2025
PROJECT NO: 23A1038
CAD FILE: E-101-PLNDWG
DESIGN RY: KNI 3/31/2025

EXISTING AIRFIELD LIGHTING DEMOLITION PLAN -SHEET 5

DRAWN BY: CWS 4/3/2025 REVIEWED BY: KNL 6/24/2025



HANSON Engineering | Planning | Allied Service

> Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN

KEVIN N.
LIGHTFOOT
062-047643

ATE LICE

/29/2025 EXPIRES: 11/30/

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIPTION
DESCRIPTION
DES DWN REV

ISSUE: JULY 25, 2025
PROJECT NO: 23A1038


CAD FILE: E-101-PLIDWG


DESIGN BY: KNL 3/31/2025
DRAWN BY: CWS 4/3/2025

SHEET TITLE

EXISTING AIRFIELD LIGHTING DEMOLITION PLAN -SHEET 6

REVIEWED BY: KNL 6/24/2025





HANSON Engineering | Planning | Allied Services

Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

LOIVA, ILLINOIS 02039

COVERING ELECTRICAL DESIGN

ROFESSION

KEVIN N.


LIGHTFOOT

062-047643

E LICENSE


INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21


IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD




PROPOSED AIRFIELD LIGHTING PLAN -SHEET 1

REVIEWED BY: KNL 6/24/2025







HANSO
Engineering | Planning | Allied S

Offices Nationwide
www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839


,



)ATE L


INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21


IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD




PROPOSED AIRFIELD LIGHTING PLAN -SHEET 2

REVIEWED BY: KNL 6/24/2025







HANSON Engineering | Planning | Allied Service

Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD

FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN

WITH THE PROPERTY OF THE PROPERTY

062-047643


Kein I, lightfort

ATE LICE IGNED: 7/29/2025 EXP

3/21

INSTALL MEDIUM
INTENSITY RUNWAY
LIGHTS ON RUNWAY


IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD



DRAWN BY: CWS 4/8/22 REVIEWED BY: KNL 6/24/2025

SHEET TITLE

PROPOSED AIRFIELD LIGHTING PLAN -SHEET 3




PROPOSED L-861(L) BASE MOUNTED RUNWAY EDGE LIGHTS. LOCATE 10 FT

FROM PAVEMENT EDGE. (TYP.)

EXISTING RUNWAY 3 PLASI HOME RUN

120VAC FEEDER CIRCUIT; 2 - 1/C #8 AWG CONDUCTORS. LOCATE AND AVOID.



STA.

MATCHLINE

EXISTING DRAINAGE CULVERT LINE/PIPE.

HANSON Engineering | Planning | Allied Service

Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

,

COVERING ELECTRICAL DESIGN

WEVIN N.

LIGHTFOOT

OF 11

TE LICENS SNED: 7/29/2025 EXPIRE

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIPTION
DES DWN REV

ISSUE: JULY 25, 2025

PROJECT NO: 23A1038

CAD FILE: E-102-PILDOMG

DESIGN BY: KNL 4/6/2025

SHEET TITLE


PROPOSED AIRFIELD LIGHTING PLAN -SHEET 4

DRAWN BY: CWS 4/8/2025 REVIEWED BY: KNL 6/24/2025

MATCHLINE (SEE NEXT SHEET)

EXISTING FENCE

PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UNDERGROUND CONDUCTOR IN 2" SCHED 40 (MIN.) PVC OR HDPE DUCT. SLASHES INDICATE NUMBER OF CONDUCTORS.



HANSON Engineering | Planning | Allied Services

Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839



TE LICENS

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21


IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DES	CRIPT	NOI	
NO.	DATE	DES	DWN	REV	
SSUE:	SSUE: JULY 25, 2025				
PROJECT NO: 23A1038					
CAD FILE: E-102-PLN.DWG					

SHEET TITLE

PROPOSED AIRFIELD LIGHTING PLAN -SHEET 5

DESIGN BY: KNL 4/6/2025
DRAWN BY: CWS 4/8/2025
REVIEWED BY: KNL 6/24/2025



HANSON Engineering | Planning | Allied Service

> Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN

KEVIN N.
LIGHTFOOT
062-047643

DATE LICENSE

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

CAD FILE: E-102-PLN.DWG
DESIGN BY: KNL 4/6/2025
DRAWN BY: CWS 4/8/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

PROPOSED AIRFIELD LIGHTING PLAN -SHEET 6

AIRFIELD LIGHTING REMOVAL, RELOCATION, AND INSTALLATION NOTES

- I. KEEP ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS COORDINATED WITH THE AIRPORT DIRECTOR/MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT). WHERE THE FACILITY IS NOT EQUIPPED WITH LOCK/TAGOUT EQUIPMENT THE RESPECTIVE PERSONNEL WILL BE RESPONSIBLE FOR PROVIDING THE APPROPRIATE LOCKOUT/TAGOUT EQUIPMENT. FAILURE TO SHUT DOWN AND LOCKOUT THE CIRCUIT(S) PRESENTS A DANGEROUS HAZARD FOR PERSONNEL WORKING ON THIS SYSTEM.
- 2. EACH RESPECTIVE PERSON PERFORMING AIRFIELD LIGHTING WORK, VAULT WORK, AND/OR TESTS SHALL BE FAMILIAR WITH, AND QUALIFIED TO WORK ON, 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS, CONSTANT CURRENT REGULATORS AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT. ONLY QUALIFIED ELECTRICAL CONTRACTORS SHALL PERFORM ELECTRICAL WORK ON THIS PROJECT. NEC DEFINES A QUALIFIED PERSON AS FOLLOWS; "ONE WHO HAS SKILLS AND KNOWLEDGE RELATED TO THE CONSTRUCTION AND OPERATION OF THE ELECTRICAL EQUIPMENT AND INSTALLATIONS AND HAS RECEIVED SAFETY TRAINING TO RECOGNIZE AND AVOID THE HAZARDS INVOLVED".
- 3. VERIFY RESPECTIVE CIRCUITS, POWER SOURCES AND SITE CONDITIONS PRIOR TO REMOVING, DISCONNECTING, RELOCATING, INSTALLING, CONNECTING OR WORKING ON THE RESPECTIVE AIRFIELD LIGHTING, DISTANCE REMAINING SIGN, RUNWAY SIGN, TAXI SIGN, NAVAID, VAULT EQUIPMENT OR OTHER DEVICE.
- 4. INSTALL AIRFIELD LIGHTING, SIGNS, SPLICE CANS, ELECTRICAL DUCTS, HANDHOLES, MANHOLES, AND CABLE AT THE LOCATIONS SHOWN AND IN COMPLIANCE WITH THE SPECIFICATIONS, SPECIAL PROVISIONS, RESPECTIVE DETAILS, AND MANUFACTURER'S RECOMMENDATIONS
- 5. NEW AIRFIELD LIGHTING SYSTEM INSTALLATIONS, ADJUSTMENTS, RELOCATIONS, REINSTALLATIONS, AND/OR UPGRADES SHALL USE BASE (L-867 OR L-868) MOUNTED FIXTURES AND 1/C #8, FAA L-824 5000V TYPE C CABLE IN 2" DUCT.
- LIGHTING CABLE FOR AIRFIELD LIGHTING SERIES CIRCUITS SHALL BE 1/C, #8 AWG, FAA L-824, 5000 VOLT, TYPE C UNDERGROUND CABLE IN 2" SCHEDULE 40 MIN. PVC OR HDPE DUCT. CABLE SHALL BE FAA APPROVED.
- 7. IN AREAS WHERE THERE IS A CONGESTION OF CABLES OR WHERE THE PROPOSED CABLE CROSSES AN EXISTING CABLE, THE CONTRACTOR IS REQUIRED TO HAND DIG THE TRENCH NECESSARY FOR THE PROPOSED CABLE. AT OTHER LOCATIONS, THE PROPOSED CABLE MAY BE TRENCHED OR PLOWED INTO PLACE. HAND DIGGING, TRENCHING AND/OR PLOWING WILL BE CONSIDERED INCIDENTAL TO THE PROPOSED CABLES AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 8. GROUND ROD MUST BE INSTALLED AT EACH LIGHT FIXTURE, RUNWAY/TAXI SIGN AND SPLICE CAN. THE PURPOSE OF THE LIGHT BASE GROUND IS PROVIDE A DEGREE OF PROTECTION FOR MAINTENANCE PERSONNEL FROM POSSIBLE CONTACT WITH AN ENERGIZED LIGHT BASE OR MOUNTING STAKE THAT MAY RESULT FROM A SHORTED POWER CABLE OR ISOLATION TRANSFORMER. PER NATIONAL ELECTRICAL CODE ARTICLE 250.53 "GROUNDING ELECTRODE SYSTEM INSTALLATION" RESISTANCE FROM THE GROUND ROD/ELECTRODE TO EARTH GROUND MUST BE 25 OHMS OR LESS VIA MEASUREMENT WITH A GROUND TESTER. GROUNDS RODS FOR LIGHT BASE GROUNDS SHALL BE 3/4-INCH BY 10-FEET MINIMUM LENGTH UL LISTED COPPER-CLAD STEEL SECTIONAL RODS. GROUND RODS SHALL BE PRODUCED FROM 100% DOMESTIC STEEL. EACH GROUND ROD SHALL BE TESTED AND THE RESULTS RECORDED FOR EACH AIRFIELD LIGHT FIXTURE AND RUNWAY/TAXI SIGN INSTALLATION. COPIES OF GROUND SYSTEM TEST RESULTS SHALL BE FURNISHED TO THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT, AND/OR THE RESIDENT ENGINEER/TECHNICIAN.
- HOMERUN CABLES FOR A RESPECTIVE CIRCUIT THAT ARE INSTALLED IN CONDUIT OR DUCT SHALL BE RUN TOGETHER IN THE SAME RACEWAY OR DUCT.
- 10. THE CONTRACTOR SHALL TEST THE RESPECTIVE AIRFIELD LIGHTING CIRCUITS IN AREAS OF WORK WHERE RESPECTIVE CIRCUITS MIGHT BE AFFECTED. THE RESPECTIVE RUNWAY AND TAXIWAY LIGHTING CCR'S (FOR THE AREAS OF WORK ON THIS PROJECT) SHALL BE TESTED FOR PROPER OPERATION BEFORE REMOVAL WORK, MODIFICATIONS, AND/OR ADDITIONS AND AFTER THE NEW CABLES AND LIGHTING SYSTEM MODIFICATIONS AND ADDITIONS HAVE BEEN COMPLETED. CONTRACTOR SHALL TEST AND RECORD THE INPUT CURRENT AND OUTPUT CURRENT FOR EACH CONSTANT CURRENT REGULATOR IN THE AUTOMATIC AND MANUAL MODES OF OPERATIONS. CONTRACTOR SHALL REPORT CONCERNS AND/OR DEFICIENCIES TO THE RESIDENT ENGINEER/TECHNICIAN. TEST RESULTS SHALL BE COORDINATED WITH AND PROVIDED TO THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT, AND RESIDENT ENGINEER/TECHNICIAN.
- 11. FAA AC 150/5370-10G "STANDARDS FOR SPECIFYING CONSTRUCTION OF AIRPORTS", ITEM L-108 "UNDERGROUND POWER CABLE FOR AIRPORTS", REQUIRES THAT EVERY AIRFIELD LIGHTING CABLE SPLICES SHALL BE QUALIFIED IN MAKING CABLE SPLICES AND TERMINATIONS ON CABLES RATED ABOVE 5,000 VOLTS AC. CABLE SPLICING/TERMINATING PERSONNEL SHALL HAVE A MINIMUM OF THREE (3) YEARS CONTINUOUS EXPERIENCE IN TERMINATING/SPLICING MEDIUM VOLTAGE CABLE.

- 12. OTHER CONSTRUCTION PROJECTS MIGHT BE IN PROGRESS AT THE AIRPORT AT THE SAME TIME AS THIS PROJECT. THE CONTRACTOR WILL BE REQUIRED TO COOPERATE WITH ALL OTHER CONTRACTORS AND THE AIRPORT MANAGER IN THE COORDINATION OF THE WORK
- 13. OBTAIN APPROVAL FROM THE AIRPORT MANAGER PRIOR TO SHUTTING DOWN A RUNWAY OR TAXIWAY. WHEN A RESPECTIVE RUNWAY IS CLOSED THE RESPECTIVE RUNWAY LIGHTING AND NAVAIDS FOR THAT RUNWAY SHALL BE SHUT OFF. WHEN A RESPECTIVE TAXIWAY IS CLOSED THE RESPECTIVE TAXIWAY LIGHTING FOR THAT TAXIWAY SHALL BE SHUT OFF.
- 14. THE CONTRACTOR IS REQUIRED TO FILL IN ALL HOLES AND DEPRESSIONS RESULTING FROM THE NEW WORK, WITH EARTH MATERIAL. THE AREAS SHALL BE COMPACTED TO PREVENT FUTURE SETTLEMENT AND FERTILIZED, SEEDED, AND MULCHED IN ACCORDANCE WITH ITEMS 901 AND 908 RESPECTIVELY.
- 15. IN THE EVENT A CONFLICT IS DETERMINED WITH RESPECT TO MANUFACTURER INSTALLATION INSTRUCTIONS, NEC, AND/OR THE CONTRACT DOCUMENTS, CONTACT THE PROJECT ENGINEER FOR FURTHER DIRECTION.
- 16. SEE SAFETY PLAN AND NOTES FOR SAFETY AND CONSTRUCTION COORDINATION REQUIREMENTS.
- 17. EXISTING AIRFIELD LIGHTS AND/OR SIGNS DESIGNATED FOR REMOVAL SHALL BE CAREFULLY REMOVED IN THERE ENTIRETY. THE CONTRACTOR SHALL DISCONNECT AND REMOVE THE EXISTING LIGHTS AND SIGNS, AS NOT TO DAMAGE THEM, INCLUDING MOUNTING STAKES, BASES, FOUNDATIONS AND TRANSFORMERS. THE EXISTING AIRFIELD LIGHTS, TRANSFORMERS, LIGHT BASES, COVERS AND MOUNTING STAKES SHALL BE TURNED OVER TO THE AIRPORT. SIGNS SHALL BE TURNED OVER TO THE AIRPORT FOR THEIR RIGHT OF FIRST REFUSAL. LIGHT BASES AND SIGN FOUNDATIONS SHALL BE REMOVED AND DISPOSED OF OFF SITE. ANY MATERIAL NOT SALVAGED BY THE AIRPORT SHALL BE DISPOSED OF OFF THE AIRPORT SITE. IN A LEGAL MANNER, AT THE CONTRACTOR'S OWN EXPENSE EXISTING DUCTS AND CABLES ASSOCIATED WITH AIRFIELD LIGHTING REMOVALS, RELOCATIONS, REPLACEMENTS AND/OR CABLE OR DUC REPLACEMENTS SHALL BE REMOVED AND DISPOSED OF OFF SITE AT NO ADDITIONAL COST TO THE CONTRACT WHERE ACCESSIBLE AND ABANDONED IN PLACE ELSEWHERE PROVIDE TEMPORARY CABLES AND DUCTS TO ACCOMMODATE AIRFIELD LIGHTING CIRCUITS THAT ARE TO REMAIN ACTIVE DURING CONSTRUCTION. CONTRACTOR MAY REMOVE ABANDONED CABLES AT NO ADDITIONAL COST TO THE CONTRACT AND SHALL HAVE THE SALVAGE RIGHTS TO ABANDONED CABLES REMOVAL OF EXISTING AIRFIELD. LIGHTING WILL BE PAID FOR UNDER ITEM AR800476 REMOVE AIRFIELD LIGHTING PER LUMP SUM
- 18. OWNER SHALL BE KEPT INFORMED OF WORK AND SCHEDULES.
- ROUTE NEW CABLES AND DUCTS TO AVOID INTERFERENCES WITH OTHER UTILITIES, LINES, CABLES AND STRUCTURES.
- 20. ALL ELECTRICAL EQUIPMENT (INCLUDING AIRFIELD LIGHTING AND NAVADS) AND MATERIALS SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 NATIONAL ELECTRIC CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS, AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES, AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, INTERNEK TESTING SERVICES VERIFICATION/ETL LISTING (OR OTHER THIRD PARTY LISTING) AND/OR MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT BE PERMITTED.
- 21. CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF FAA AC NO. 150/5370-2G (OR MOST CURRENT ISSUE) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- 22. CONTRACTOR SHALL COMPLY WITH THE APPLICABLE REQUIREMENTS OF NFPA 70E STANDARD FOR ELECTRICAL SAFETY IN THE WORKPLACE.
- 23. RUNWAY AND TAXIWAY LIGHTING CIRCUITS SHALL BE ACTIVE AT THE END OF EACH CONSTRUCTION DAY FOR AN OPEN RUNWAY OR AN OPEN TAXIWAY. THE CONTRACTOR SHALL PROVIDE TEMPORARY CABLE & CONNECTIONS WHERE NECESSARY TO MAINTAIN A RUNWAY OR TAXIWAY LIGHTING SYSTEM. TEMPORARY CABLE FOR AIRFIELD LIGHTING SERIES CIRCUITS SHALL BE 1/C #8 FAA L-824 5KV UG CABLE IN DUCT OR UNIT DUCT.
- 24. ALL ABOVEGROUND JUMPERS SHALL BE IN A DUCT WITH ALL CONNECTIONS SEALED. THE CONTRACTOR SHALL SECURE, IDENTIFY AND PLACE ALL TEMPORARY EXPOSED WIRING IN CONDUIT, DUCT, OR UNIT DUCT TO PREVENT ELECTROCUTION AND FIRE IGNITION SOURCES AS PER THE REQUIREMENTS OF FAA 150/5370-2G, OPERATION SAFETY ON AIRPORTS DURING CONSTRUCTION, SECTION 2.18.3 "LIGHTING AND VISUAL NAVAIDS". ALL LABOR, MATERIALS, AND TIME NECESSARY TO COMPLY WITH THIS REQUIREMENT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 25. CONTRACTOR SHALL INTERFACE EXISTING AIRFIELD LIGHTING AND/OR SIGNS TO THE NEW, REMOVED, REINSTALLED, ADJUSTED, REPLACED, AND/OR RELOCATED AIRFIELD LIGHTING AND ASSOCIATED CIRCUITS.

- 26. ALL AIRFIELD LIGHT FIXTURES SHALL BE TAGGED BY THE CONTRACTOR IN ACCORDANCE WITH THE RESPECTIVE LIGHT FIXTURE NUMBERS. CONFIRM LIGHT FIXTURE NUMBERING WITH THE AIRPORT MANAGER/MAINTENANCE SUPERVISOR.
- 27. HIGH VOLTAGE CIRCUITS (AIRFIELD LIGHTING 5000 VOLT SERIES CIRCUITS AND OTHER CIRCUITS RATED ABOVE 600 VOLTS) AND LOW VOLTAGE CIRCUITS (RATED 600 VOLTS AND BELOW) SHALL NOT BE INSTALLED IN THE SAME WIREWAY, CONDUIT, DUCT, RACEWAY, JUNCTION STRUCTURE. OR HANDHOLE.
- 28. THE CONTRACTOR IS REQUIRED TO RESTORE ALL DISTURBED PAVEMENT ASSOCIATED WITH REMOVAL WORK AND/OR NEW AIRFIELD LIGHTING INSTALLATIONS.
- 29. NO CONNECTION TO AN ACTIVE LIGHTING CIRCUIT WILL BE BROKEN UNTIL THE CIRCUIT HAS BEEN TURNED OFF IN ACCORDANCE WITH NOTE 1.

THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE FITHER EXPRESSED OR IMPLIED. THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER/TECHNICIAN SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.



Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed
Professional Service Corporation
#184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839



ATE LICE IGNED: 7/29/2025 EXP

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIPTION
DES DWN REV
USSUE: JULY 25, 2025

PROJECT NO: 23A1038

CAD FILE: E-001-NOTES.DWG

DESIGN BY: KNL 3/31/2025 DRAWN BY: CWS 4/4/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

AIRFIELD LIGHTING NOTES 1

	RUNWAY 21-3 LIGHT LENS SCHEDULE						
LIGHT NUMBERS	LENS	ORIENTATION	FIXTURE TYPE	NOTES			
R1-01 TO R1-02	WHITE/YELLOW	YELLOW SIDE FACING SOUTH	L-861(L)	NEW RUNWAY EDGE LIGHT			
R1-03 TO R1-14	BLUE		L-861T(L)	EXISTING TAXIWAY EDGE LIGHTS AT RWY 21 TURNAROUND			
R1-15 TO R1-22	RED/GREEN	GREEN SIDE FACING NORTH (TOWARD RWY 21 APPROACH)	L-861SE(L)	EXISTING RUNWAY THRESHOLD LIGHTS AT RWY 21 END			
R1-23 TO R1-32	WHITE/YELLOW	YELLOW SIDE FACING SOUTH	L-861(L)	NEW RUNWAY EDGE LIGHT			
R1-33 TO R1-37	WHITE/WHITE		L-861(L)	NEW RUNWAY EDGE LIGHT			
R1-38 TO R1-47	WHITE/YELLOW	YELLOW SIDE FACING NORTH	L-861(L)	NEW RUNWAY EDGE LIGHT			
R1-48 TO R1-59	BLUE		L-861T(L)	EXISTING TAXIWAY EDGE LIGHTS AT RWY 3 TURNAROUND			
R1-60 TO R1-67	RED/GREEN	GREEN SIDE FACING SOUTH (TOWARD RUNWAY 3 APPROACH)	L-861SE(L)	EXISTING RUNWAY THRESHOLD LIGHTS AT RWY 3 END			
R1-68 TO R1-76	WHITE/YELLOW	YELLOW SIDE FACING NORTH	L-861(L)	NEW RUNWAY EDGE LIGHT			
R1-77 TO R1-82	WHITE/WHITE		L-861(L)	NEW RUNWAY EDGE LIGHT			
R1-83 TO R1-88	WHITE/YELLOW	YELLOW SIDE FACING SOUTH	L-861(L)	NEW RUNWAY EDGE LIGHT			

NOTE:

PROVIDE NEW LIGHT NUMBER TAGS FOR NEW AND EXISTING LIGHTS ON RWY 3-21 LIGHTING CIRCUIT.



Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN



DATE LICENSE SIGNED: 7/29/2025 EXPIRES: 11/30/2025

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DES	CRIPT	ION		
INO.	DATE	DES	DWN	REV		
SSUE: JULY 25, 2025						
DDO IEC	2DO IECT NO: 2241029					

CAD FILE: E-642-SCHED.DWG

DESIGN BY: KNL 4/26/2025 DRAWN BY: CWS 4/29/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

LIGHT LENS SCHEDULES


AFFIX NON-CORROSIVE, NON-BREAKABLE, TAG TO FIXTURE FACING RUNWAY/TAXIWAY WITH SET SCREW, WIRE TIE, OR METAL BAND. NUMERALS SHALL BE ENGRAVED FOR PERMANENT READABILITY. STAINLESS STEEL OR BRASS TAGS WITH 1/2" HIGH STAMPED LETTERING WILL ALSO BE ACCEPTABLE.

NUMBERING TAG DETAIL

(NOT TO SCALE)

NOTES:

- SEE ELECTRICAL NOTES SHEETS.
- SEE "ELECTRICAL NOTES SHEET 2" AND "GROUNDING NOTES" SHEET FOR GROUNDING NOTES FOR AIRFIELD LIGHTING.
- 3. SEE PROPOSED LIGHTING LAYOUT SHEET(S) FOR LIGHT LOCATIONS
- WHERE GROUND LUGS ARE NOT ACCESSIBLE ON BASE CANS, PROVIDE A UL LISTED PIPE GROUND CLAMP RATED FOR DIRECT BURIAL IN EARTH AND BOND TO THE METAL CONDUIT EXTENSION TO PROVIDE GROUND PATH TO LIGHT BASE.
- THE PROPOSED AIRFIELD LIGHT FIXTURES SHALL CONFORM TO ADVISORY CIRCULAR 150/5345-46 (CURRENT ISSUE(S) IN EFFECT) AND BE FAA APPROVED FOR TYPE L-861T(L) FOR TAXIWAY EDGE LIGHTS. AIRFIELD LIGHT FIXTURES SHALL HAVE LED (LIGHT EMITTING DIODE) ILLUMINATION AND SHALL CONFORM TO THE APPLICABLE REQUIREMENTS OF FAA ENGINEERING BRIEF NO. 67D LIGHT SOURCES OTHER THAN INCANDESCENT AND XENON FOR AIRPORT AND OBSTRUCTION LIGHTING FIXTURES.
- LIGHT BASE CANS FOR THE AIRFIELD LIGHT FIXTURES SHALL CONFORM TO THE REQUIREMENTS OF FAA AC 150/5345-42 (CURRENT ISSUE IN EFFECT), FOR TYPE L-867, CLASS IA, SIZE B (12 IN. NOMINAL DIAMETER) OR SIZE D (16 IN. NOMINAL DIAMETER), AND 24 IN. DEEP AND/OR AS DETAILED ON THE PLANS. EACH LIGHT BASE CAN SHALL INCLUDE INTERNAL AND EXTERNAL GROUND LUGS TO ACCOMMODATE THE RESPECTIVE APPLICATIONS. LIGHT BASE PLATES SHALL BE SIZED AND COMPATIBLE WITH THE RESPECTIVE LIGHT BASES AND LIGHT FIXTURES WITH STAINLESS STEEL BOLTS.
- PRIOR TO INSTALLING THE AIRFIELD LIGHT FIXTURES, APPLY AN OXIDE-INHIBITING, ANTI-SEIZING COMPOUND TO ALL SCREWS, NUTS, BREAKABLE COUPLING, AND ALL PLACES WHERE METAL COMES INTO CONTACT WITH METAL
- SERIES CIRCUIT ISOLATION TRANSFORMERS FOR THE AIRFIELD LIGHTING SHALL BE MANUFACTURED TO FAA SPECIFICATION AC 150/5345-47, (CURRENT EDITION IN EFFECT), AND SHALL BE FAA-APPROVED (ETL/INTERTEK TESTING SERVICES-CERTIFIED). SERIES CIRCUIT TRANSFORMER SHALL BE PROPERLY SIZED FOR THE RESPECTIVE AIRFIELD LIGHTING DEVICE, AND SHALL BE AS RECOMMENDED BY THE RESPECTIVE FOUIPMENT MANUFACTURER CONFIRM PROPER TRANSFORMER SELECTION AND SIZING WITH THE RESPECTIVE EQUIPMENT MANUFACTURER.
- THE CONCRETE USED IN THE CONSTRUCTION OF THE BASES FOR THE AIRFIELD LIGHTING AND SPLICE CANS SHALL BE IN ACCORDANCE WITH ITEM 610 CONCRETE FOR MISCELLANEOUS STRUCTURES.
- 10. IDENTIFICATION TAGS SHALL BE ATTACHED TO EACH AIRFIELD LIGHT FIXTURE.
- 11. PER ILLINOIS STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS ITEM 108, ITEM 125, AND FAA AC 150/5370-10H ITEM L-108 AND L-125, RUBBER AND PLASTIC ELECTRICAL TAPES SHALL BE SCOTCH ELECTRICAL TAPE NUMBERS 130C LINERLESS RUBBER SPLICING TAPE (2" WIDE) AND 88 (1.5" WIDE) RESPECTIVELY, AS MANUFACTURED THE MINNESOTA MINING AND MANUFACTURING COMPANY, OR EQUIVALENT.



LIGHTING CONNECTION SCHEMATIC

NOT TO SCALE

www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA. ILLINOIS 62839



INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DES	CRIPT	ION	
INO.	DATE	DES	DWN	REV	
ISSUE:	JULY 25	5, 2025	5		
PROJEC	CT NO: 2	3A103	8		
CAD FIL	E: E-501-D	ETL.DWG	•		
DESIGN	BY: KN	L 3/3	1/2025		
	BV: CW	2 1/1/	2025		

REVIEWED BY: KNL 6/24/2025

AIRFIELD LIGHT **DETAILS**

	TAXI GUIDANCE SIGN SCHEDULE							
SIGN	LOCATION	PROF	POSED	GROUND	REMARKS			
NUMBER	LOCATION	SIDE A	SIDE B	RESISTANCE	NEWANNO			
R1-TGS7	RUNWAY 21 INTERSECTION WITH RUNWAY 36-18	36 -18			NEW SIGN TYPE: L-858R(L), SIZE 1, STYLE 2, CLASS 2 MANDATORY HOLDING POSITION SIGN FOR RUNWAY/RUNWAY INTERSECTION. CONNECT TO RUNWAY 3-21 LIGHTING CIRCUIT.			
R1-TGS8	RUNWAY 3 INTERSECTION WITH RUNWAY 18-36	18- 36			NEW SIGN TYPE: L-858R(L), SIZE 1, STYLE 2, CLASS 2 MANDATORY HOLDING POSITION SIGN FOR RUNWAY/RUNWAY INTERSECTION. CONNECT TO RUNWAY 3-21 LIGHTING CIRCUIT.			
R2-TGS1	RUNWAY 36 INTERSECTION WITH RUNWAY 3-21	3 - 21			NEW SIGN TYPE: L-858R, SIZE 1, STYLE 4, CLASS 2 MANDATORY HOLDING POSITION SIGN FOR RUNWAY/RUNWAY INTERSECTION.THIS IS AN UNLIT SIGN.			
R2-TGS2	RUNWAY 18 INTERSECTION WITH RUNWAY 21-3	21-3			NEW SIGN TYPE: L-858R, SIZE 1, STYLE 4, CLASS 2 MANDATORY HOLDING POSITION SIGN FOR RUNWAY/RUNWAY INTERSECTION. THIS IS AN UNLIT SIGN.			

NOTES:

- 1. THE PROPOSED LIGHTED RUNWAY/TAXI GUIDANCE SIGNS SHALL CONFORM TO ADVISORY CIRCULAR 150/5345-44 (CURRENT ISSUE IN EFFECT) AND BE FAA-APPROVED FOR TYPE L-858Y(L) DIRECTION, DESTINATION, AND BOUNDARY SIGNS (BLACK LEGEND ON YELLOW BACKGROUND): TYPE L-858R(L) MANDATORY INSTRUCTION SIGN (BLACK OUTLINE ON OUTSIDE EDGE OF WHITE LEGEND ON RED BACKGROUND); AND/OR TYPE L-858L(L) LOCATION SIGN (YELLOW LEGEND AND BORDER ON BLACK BACKGROUND).
- 2. THE PROPOSED UNLIGHTED TAXI GUIDANCE SIGNS SHALL CONFORM TO ADVISORY CIRCULAR 150/5345-44 (CURRENT ISSUE IN AFFECT) AND BE FAA-APPROVED FOR TYPE L-858 TAXIWAY AND RUNWAY SIGNS. THE SIGNS SHALL BE SIZE 1, 18-IN. SIGN FACE WITH A 12-IN. LEGEND; STYLE 4, UNLIGHTED SIGNS; MODE 2, TO WITHSTAND WIND LOADS OF 200 M.P.H., BASE-MOUNTED, AS SPECIFIED ON THE PLANS.
- 3. ALL SIGNS SHALL BE FURNISHED WITH TETHERS. TETHERS SHALL BE 3/16" STAINLESS STEEL AIRCRAFT CABLE WITH A FORMED EYE ON BOTH ENDS. THE TETHER EYE SHALL BE ATTACHED TO THE SIGN AND BASE BY BEING SANDWICHED BETWEEN TWO STAINLESS STEEL FENDER WASHERS, WITH A 1/2" MINIMUM STAINLESS STEEL BOLT. THE TETHER SHALL BE OF SUFFICIENT LENGTH TO HAVE A MINIMUM OF 6" OF SLACK WHEN ATTACHED BETWEEN THE SIGN AND THE SIGN BASE. THE TETHERS AND BONDING CONDUCTORS SHALL BE OF SUFFICIENT LENGTH TO ALLOW THE FRANGIBLE COUPLINGS TO OPERATE WITHOUT RESTRICTIONS AND TO ALLOW THE POWER CABLE TO DISCONNECT IF THE SIGN FALLS OVER, PROVIDE 3" ± 1/2" SLACK IN TETHER AND ALL TETHERS SHALL BE THE SAME LENGTH.
- ALL SIGNS SHALL BE ORIENTATED SUCH THAT THE LONGITUDINAL CENTERLINE OF THE SIGN IS PERPENDICULAR TO THE RESPECTIVE TAXIWAY/RUNWAY CENTERLINE, UNLESS NOTED OTHERWISE.
- ALL MANDATORY SIGNS (SIZE 1) SHALL BE LOCATED 15' OFF THE EDGE OF FULL STRENGTH PAVEMENT, (UNLESS DETAILED OTHERWISE) AND ALIGNED WITH THE FRONT EDGE OF THE FIRST YELLOW STRIPE (FURTHEST FROM THE RUNWAY) OF THE HOLD POSITION MARKING UNLESS SHOWN OTHERWISE FOR A RESPECTIVE SIGN. CONFIRM LOCATIONS WITH THE PROJECT ENGINEER.
- RUNWAY EXIT/TAXIWAY ENTRANCE SIGNS (TAXIWAY GUIDANCE SIGNS TO DEFINE THE THROAT OR ENTRANCE INTO THE INTERSECTING TAXIING ROUTE) OR RUNWAY EXIT/TAXIWAY ENTRANCE LIGHTS SHALL BE CONNECTED TO THE RESPECTIVE RUNWAY CIRCUIT TO BE ILLUMINATED WHEN THE RUNWAY EDGE LIGHTS ARE ON TO COMPLY WITH FAA AC 150/5340-18G, CHAPTER 1, PART 1.15 "SIGN OPERATION", AND/OR FAA AC 150/5340-30J PART
- HOLDING POSITION SIGNS FOR RUNWAYS SHALL BE CONNECTED TO THE RESPECTIVE RUNWAY SERIES CIRCUIT TO BE ILLUMINATED WHEN THE ASSOCIATED RUNWAY LIGHTS ARE ILLUMINATED TO COMPLY WITH FAA AC150/5340-18G, CHAPTER 1, PART 1.15 "SIGN
- 8. CONCRETE STEEL REINFORCEMENT SHALL BE TYPE ASTM A615 OR A706 GRADE 60 WELDED STEEL WIRE FABRIC SHALL CONFORM TO AASHTO M55 OR AASHTO M221. ALL REINFORCEMENT SHALL HAVE A 3" MINIMUM CONCRETE COVER, REINFORCEMENT MAY BE ADJUSTED TO MISS INTERFERENCES. CONCRETE SHALL CONFORM TO ITEM 610 CONCRETE FOR MISCELLANEOUS STRUCTURES.
- 9. SEE SPECIFICATION ITEM L-125 FOR ADDITIONAL REQUIREMENTS ON
- 10. CONTRACTOR SHALL TEST THE EARTH GROUND RESISTANCE FOR THE GROUND ROD AT EACH RUNWAY/TAXI GUIDANCE SIGN

TAXI GUIDANCE SIGN LEGEND



TYPE L-858L(L) LOCATION SIGN -YELLOW LEGEND AND BORDER ON A BLACK BACKGROUND



TYPE L-858R(L) MANDATORY INSTRUCTION SIGN - BLACK OUTLINE ON OUTSIDE EDGE OF WHITE LEGEND ON A RED BACKGROUND



TYPE L-858Y(L) DIRECTION, DESTINATION, AND BOUNDARY SIGN -BLACK LEGEND ON A YELLOW BACKGROUND



BLANK - BLACK BACKGROUND


www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839



SIGNED: 7/29/2025 EXPIRES: 11/30/2025

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD


NO.	DATE	DES	CRIPT	ION
NO.	DATE	DES	DWN	REV
ISSUE:	JULY 25	5, 2025	;	
PROJEC	CT NO: 2	3A103	8	

CAD FILE: E-641-SCHED.DWG DESIGN BY: KNI 4/26/2025 DRAWN BY: CWS 4/29/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

TAXI GUIDANCE SIGN SCHEDULE AND NOTES





Offices Nationwide

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA. ILLINOIS 62839



DATE

EXPIRES: 11/30/2025

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21


IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD


NO.	DATE	DES	CRIPT	NOI	
NO.	DATE	DES	DWN	REV	
ISSUE:	JULY 25	5, 2025	;		
PROJEC	CT NO: 2	3A103	8		
CAD FIL	CAD FILE: E-508-DETL.DWG				
DESIGN	BY: KN	L 4/26	6/2025		
DRAWN	BY: CW	S 4/29	/2025		

SHEET TITLE

LIGHTED TAXI GUIDANCE SIGN DETAILS

REVIEWED BY: KNL 6/24/2025





UNLIGHTED TAXI GUIDANCE SIGN NOTES

BASE-MOUNTED.

BORDER ON BLACK BACKGROUND).

THE PROPOSED UNLIGHTED TAXI GUIDANCE SIGNS SHALL CONFORM TO

FAA-APPROVED FOR TYPE L-858 TAXIWAY AND RUNWAY SIGNS. THE SIGNS SHALL BE SIZE 1, 18-IN. SIGN FACE WITH A 12-IN. LEGEND; STYLE 4, UNLIGHTED SIGNS; MODE 2, TO WITHSTAND WIND LOADS OF 200 M.P.H.,

ADVISORY CIRCULAR 150/5345-44 (CURRENT ISSUE IN FORCE) AND BE

 THE SIGNS SHALL READ AS DESCRIBED ON THE TAXI GUIDANCE SIGN SCHEDULE. THE PROPOSED TAXI GUIDANCE SIGNS WILL BE TYPE L-858-Y DIRECTION, DESTINATION, AND BOUNDARY SIGNS (BLACK LEGEND ON YELLOW BACKGROUND); TYPE L-858-R MANDATORY INSTRUCTION SIGN

(BLACK OUTLINE ON OUTSIDE EDGE OF WHITE LEGEND ON RED

4. NUMBER AND SPACING OF LEGS SHALL BE IN ACCORDANCE WITH THE

RESPECTIVE SIGN MANUFACTURER REQUIREMENTS.

BACKGROUND); AND TYPE L-858-L LOCATION SIGN (YELLOW LEGEND AND

3. THE CONCRETE USED IN THE CONSTRUCTION OF THESE ITEMS SHALL BE IN ACCORDANCE WITH ITEM 610 CONCRETE FOR MISCELLANEOUS

5. REINFORCING STEEL/WIRE MESH USED IN THE SIGN FOUNDATION SHALL BE PRODUCED FROM 100 PERCENT DOMESTIC STEEL TO COMPLY WITH THE ILLINOIS "STEEL PRODUCTS PROCUREMENT ACT" AND THE AIRPORT IMPROVEMENT PROGRAM BUY AMERICAN PREFERENCE REQUIREMENTS.

UNLIGHTED SIGN DETAILS

(NOT TO SCALE)

HANSON Engineering | Planning | Allied Service


Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed
Professional Service Corporation
#184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839



ATE LICE GNED: 7/29/2025 EXP

LICENSE /2025 EXPIRES: 11/30/20

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

	NO.	DATE	DES	CRIPT	ION
	NO.	DATE	DES	DWN	REV
	ISSUE:	JULY 25	5, 2025	5	
i	PROJEC	CT NO: 2	3A103	8	
	CAD FIL	E: E-509-D	ETL.DWG	3	

CAD FILE: E-509-DETL.DWG
DESIGN BY: KNL 4/26/2025

DRAWN BY: CWS 4/29/2025 REVIEWED BY: KNL 6/24/2025


SHEET TITLE

UNLIGHTED TAXI GUIDANCE SIGN DETAILS WITH LOOP CIRCUIT AND FOR SPLICES IN HOMERUNS TO EXISTING CABLES

HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE. HEAT SHRINKABLE TUBING SHALL EXTEND FROM THE CABLE TO AT LEAST AN INCH PAST THE COMPLETED CONNECTION. FIELD PRINTABLE, DOUBLE SIDED, CORROSION RESISTANT, COLOR ADDITIONAL ADHESIVE L-823 RECEPTACLE END-CODED. REFLECTIVE CABLE TAG COMPOUND FILLER c===5 AFTER SHRINKING -L-823 PLUG END WRAP WITH AT LEAST ONE LAYER OF RUBBER OR FACTORY MOLDED SYNTHETIC RUBBER TAPE AND ONE LAYER OF TRANSFORMER LEADS PLASTIC TAPE ONE-HALF LAPPED EXTENDED AT LEAST 1-1/2 INCHES ON EACH SIDE OF JOINT HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE. HEAT SHRINKABLE TUBING SHALL EXTEND FROM THE CABLE TO AT LEAST AN INCH PAST THE COMPLETED CONNECTION. AFTER SHRINKING L-823 PLUG END-TYPE C ADDITIONAL ADHESIVE FOR SPLICES AT COMPOUND FILLER **RUNWAY AND TAXIWAY** LIGHTS AND TAXI SIGNS —I -823 RECEPTACLE END.

> NOTES: INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY MATCH THE OUTSIDE DIAMETER OF CABLE.

> > CABLE SPLICES "NOT TO SCALE"




LOW VOLTAGE UNDERGROUND TAP SPLICE

FOR TAP SPLICES IN LOW VOLTAGE (600V) CABLE SPLICES SHALL BE RATED AND LISTED SUITABLE FOR DIRECT BURIAL LOCATIONS. FOR SPLICES UP TO #2 AWG CONDUCTOR, SPLICES SHALL BE WYE RESIN TYPE POWER CABLE TAP SPLICE KIT SUITABLE FOR THE RESPECTIVE CABLES AND RESPECTIVE APPLICATION.

NOTES:

- SPLICE DETAILS ARE PROVIDED FOR NEW WORK AND TO ASSIST IN REPAIRS OF ACCIDENTAL OR UNEXPECTED INTERRUPTIONS AND/OR CUTS TO AIRFIELD LIGHTING CARLES
- 2. KEEP ON HAND A MINIMUM OF 10 SETS OF SPLICE KITS FOR L-823 CONNECTORS AND A MINIMUM OF 10 SETS OF TYPE A LOW VOLTAGE SPLICE KITS TO ACCOMMODATE REPAIRS.
- 3. EVERY AIRFIELD LIGHTING CABLE SPLICER SHALL BE QUALIFIED IN MAKING CABLE SPLICES AND TERMINATIONS ON CABLES RATED AT AND/OR ABOVE 5 000 VOLTS AC TO COMPLY WITH THE REQUIREMENTS OF FAA AC. 150/5370-10H ITEM L-108.
- INSIDE DIAMETER OF RESPECTIVE CABLE CONNECTOR SHALL PROPERLY MATCH OUTSIDE DIAMETER OF CABLE.
- WHEN PREPARING CABLE FOR SPLICES. THE CONTRACTOR SHALL USE A CABLE STRIPPER/PENCILLER WHENEVER CABLE CONNECTIONS ARE MADE.
- WRAP ALL PRIMARY AND SECONDARY POWER CONNECTIONS WITH SUFFICIENT LAYERS OF HIGH VOLTAGE ELECTRICAL INSULATING TAPE (RUBBER SPLICING TAPE SUITABLE FOR PRIMARY ELECTRICAL INSULATION FOR SPLICING CABLE FROM 600 VOLTS TO 69,000 VOLTS) AND COVER WITH VINYL ELECTRICAL TAPE (ALL-WEATHER VINYL INSULATING TAPE SUITABLE FOR PROTECTIVE JACKETING FOR HIGH-VOLTAGE CABLE SPLICES AND REPAIRS) FOR FULL VALUE OF CABLE INSULATION VOLTAGE. PER ILLINOIS STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS ITEM 108, ITEM 125, AND FAA AC 150/5370-10H ITEM L-108 AND L-125, HIGH VOLTAGE ELECTRICAL INSULATING TAPE SHALL BE 3M SCOTCH 130C LINERLESS RUBBER SPLICING TAPE (2 INCHES WIDE) OR APPROVED EQUIVALENT, AND VINYL ELECTRICAL TAPE SHALL BE 3M SCOTCH 88 (1.5 INCHES WIDE) OR APPROVED EQUIVALENT. TAPES MUST BE RATED SUITABLE FOR THE APPLICATION
- PROVIDE CABLE TAGS TO IDENTIFY THE RESPECTIVE CIRCUITS ALL POINTS OF ACCESS INCLUDING L-867 BASES, L-868 BASES, HANDHOLES, MANHOLES, JUNCTION BOXES, AND WIREWAYS.
- CONNECTION OF CONDUCTORS MUST BE MADE BY USING CRIMP CONNECTORS AND A CRIMPING TOOL APPROVED BY THE CONNECTOR/LUG MANUFACTURER. THE TOOL MUST PRODUCE A COMPLETE CRIMP BEFORE IT CAN BE REMOVED. FOR THE L-823 CONNECTORS, THE CRIMPING TOOL USED MUST BE LISTED BY THE L-823 KIT MANUFACTURER. MAKE THE NUMBER AND TYPE OF CRIMPS PER THE KIT MANUFACTURER'S INSTRUCTIONS.



- CONTRACTOR SHALL PROVIDE CABLE CIRCUIT IDENTIFICATION MARKERS ATTACHED TO BOTH SIDES
- CABLE IDENTIFICATION TAGS SHALL BE FIELD PRINTABLE, DOUBLE SIDE, CORROSION RESISTANT, COLOR CODED, REFLECTIVE CABLE TAGS SUITABLE FOR THE RESPECTIVE ENVIRONMENT.
- 3. THE CABLE SHALL THOROUGHLY BE CLEANED PRIOR TO THE INSTALLATION OF THE L-823
- 4. ATTACH EACH CABLE TIE ENOUGH TO HOLD IN PLACE WITHOUT COMPRESSING EDGE OF CABLE TAG INTO CONDUCTOR. TRIM OFF EXCESS CABLE TIE.
- 5. CABLE TAGS SHALL BE PROVIDED AT ALL POINTS OF ACCESS INCLUDING L-867 JUNCTION/SPLICE CANS, L-868 JUNCTION/SPLICE CANS, HANDHOLES. MANHOLES. JUNCTION BOXES. AND WIRFWAYS
- CABLE TAGS SHALL BE LABELED AS FOLLOWS FOR RESPECTIVE AIRFIELD LIGHTING CIRCUITS, RUNWAY 3-21 LIGHTING: RWY 3-21 TAXIWAY A, A1 LIGHTING: TWY A

CABLE TAG DETAIL "NOT TO SCALE"

www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA. ILLINOIS 62839

COVERING ELECTRICAL DESIGN LIGHTFOOT 062-047643

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIBENT DE ISSUE: JULY 25, 2025 PROJECT NO: 23A1038


CAD FILE: E-502-DETL.DWG

DESIGN BY: KNI 3/31/2025 DRAWN BY: CWS 4/4/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

AIRFIELD LIGHTING CABLE SPLICE **DETAILS**



NOTES:

1. DIMENSIONS FOR COVERAGE AND SEPARATION BETWEEN DUCTS ARE MINIMUM.

"NOT TO SCALE"

- 2. TRENCHES WITH MORE THAN TWO DUCTS OR CABLE IN UNIT DUCTS SHALL BE INCREASED 3" IN WIDTH PLUS DIAMETER OF RESPECTIVE DUCT FOR EACH ADDITIONAL CONDUIT, DUCT, OR CABLE IN UNIT DUCT; IF SPECIFIED ON PLANS TWO PARALLEL TRENCHES MAY BE
- DEPTH OF TRENCHES SHALL BE AS SHOWN ABOVE UNLESS OTHERWISE SPECIFIED ON THE PLANS. MINIMUM COVER REQUIREMENTS FOR CABLES AND DUCTS AT AIRPORT RUNWAYS AND ADJACENT AREAS WHERE TRESPASSING IS PROHIBITED IS 18 INCHES PER NEC 300.5. AND 300 50. MINIMUM COVER REQUIREMENTS FOR DUCTS CONTAINING NAVAID FEEDER CIRCUITS SHALL BE 24". MINIMUM COVER REQUIREMENTS FOR DUCTS LOCATED BELOW PAVEMENT OR ROADWAYS IS 30". MINIMUM COVER REQUIREMENTS FOR DUCTS LOCATED IN AREAS SUBJECT TO FARMING IS 42". MINIMUM COVER FOR DUCTS CONTAINING SECONDARY ELECTRIC SERVICE CONDUCTORS SHALL BE 36" OR AS REQUIRED BY THE SERVING ELECTRIC UTILITY COMPANY. ADJUST/INCREASE BURIAL DEPTHS TO ACCOMMODATE SITE CONDITIONS, DRAINAGE AND/OR OBSTRUCTIONS, COVER IS DEFINED AS THE SHORTEST DISTANCE IN INCHES MEASURED BETWEEN A POINT ON THE TOP SURFACE OF ANY DIRECT-BURIED CONDUCTOR, CABLE, CONDUIT, OR OTHER RACEWAY AND THE TOP SURFACE OF FINISHED GRADE, CONCRETE OR SIMILAR COVER.
- HIGH-VOLTAGE CIRCUIT WIRING (AIRFIELD LIGHTING 5000 VOLT SERIES CIRCUITS AND/OR OTHER CIRCUITS RATED ABOVE 600 VOLTS) AND LOW-VOLTAGE CIRCUIT WIRING (RATED 600 VOLTS AND BELOW) SHALL MAINTAIN SEPARATION FROM EACH OTHER. HIGH-VOLTAGE WIRING AND LOW-VOLTAGE WIRING SHALL NOT BE INSTALLED IN THE SAME WIREWAY, CONDUIT, DUCT, RACEWAY, HANDHOLE, OR JUNCTION BOX. CORRECTIVE WORK WILL BE REQUIRED TO SEPARATE HIGH VOLTAGE SERIES CIRCUIT CONDUCTORS FROM LOW VOLTAGE CONDUCTORS WHERE THEY ARE INSTALLED IN THE SAME RACEWAY
- 5. SERVICE CONDUCTORS SHALL NOT BE INSTALLED IN THE SAME RACEWAY, CONDUIT, DUCT, OR HANDHOLE WITH FEEDER CIRCUITS, BRANCH CIRCUITS OR CONTROL CIRCUITS.
- COMMUNICATION CIRCUITS SHALL NOT BE INSTALLED IN THE SAME RACEWAY, CONDUIT, DUCT, OR HANDHOLE WITH POWER CIRCUITS.
- HOME RUN CABLES FOR A RESPECTIVE CIRCUIT SHALL BE INSTALLED IN THE SAME RACEWAY OR DUCT
- COORDINATE DUCT INTERFACE TO MANHOLES AND HANDHOLES. FIELD CUT OPENINGS FOR CONDUITS AND DUCTS TO INTERFACE TO MANHOLES AND/OR HANDHOLES. CUT WALL OF RESPECTIVE HANDHOLE OR MANHOLE WITH A TOOL DESIGNED FOR MATERIAL TO BE CUT. SIZE HOLES FOR RESPECTIVE DUCTS, CONDUITS, AND TERMINATION FITTINGS AND SEAL AROUND PENETRATIONS. ALL CORING, INTERFACE, CUTTING, AND SEALING WILL BE CONSIDERED INCIDENTAL TO THE RESPECTIVE DUCT INSTALLATION AND/OR RESPECTIVE HANDHOLE/MANHOLE INSTALLATION. PROVIDE BUSHINGS OR BELLS AT CONDUIT TERMINATIONS IN ELECTRICAL HANDHOLES OR MANHOLES.
- 9. ALL DISTURBED SURFACES SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST IS INCIDENTAL TO TRENCH.
- 10. ALL ELECTRICAL EQUIPMENT AND MATERIALS SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 - NATIONAL ELECTRICAL CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES LAWS ORDINANCES AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING. INTERTEK TESTING SERVICES VERIFICATION/ETL LISTING (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT BE PERMITTED.

- 11. CONTRACTOR SHALL COORDINATE WORK AND ANY POWER OUTAGES AND/OR SHUT DOWN OF SYSTEMS WITH THE RESPECTIVE FACILITY OWNER PERSONNEL AND THE AIRPORT MANAGER/DIRECTOR, ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT), WHERE THE FACILITY IS NOT EQUIPPED WITH LOCKOUT/TAGOUT FOLIPMENT THE RESPECTIVE PERSONNEL WILL BE RESPONSIBLE FOR PROVIDING THE APPROPRIATE LOCKOUT/TAGOUT EQUIPMENT. FAILURE TO SHUT DOWN AND LOCKOUT THE CIRCUIT(S) PRESENTS A DANGEROUS HAZARD FOR PERSONNEL WORKING ON THIS
- 12. THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO ACCURACY. COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION PHONE; 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.
- 13. ADJUSTMENTS TO DUCT BANK ROUTES MIGHT BE REQUIRED TO ACCOMMODATE EXISTING SITE CONDITIONS AND UNDERGROUND LINES AND UTILITIES. CONTRACTOR SHALL FIELD VERIFY EXISTING SITE CONDITIONS. CONTRACTOR SHALL COORDINATE DUCT ROUTE ADJUSTMENTS WITH THE RESIDENT PROJECT REPRESENTATIVE AND THE AIRPORT
- 14. CONTRACTOR SHALL LOCATE AND MARK ALL EXISTING CABLES, LINES, OR UTILITIES WITHIN 10 FT OF PROPOSED EXCAVATING/TRENCHING AREA. ANY CABLES, LINES, AND UTILITIES FOUND INTERFERING WITH PROPOSED EXCAVATION OR CABLE/TRENCHING SHALL BE HAND DUG AND EXPOSED. ANY DAMAGED CABLES OR OTHER UTILITIES SHALL BE IMMEDIATELY REPAIRED TO THE SATISFACTION OF THE RESPECTIVE OWNER'S REPRESENTATIVE AT THE CONTRACTOR'S EXPENSE. THE RESIDENT ENGINEER/RESIDENT TECHNICIAN AND OWNER SHALL BE NOTIFIED IMMEDIATELY IF ANY CABLES OR OTHER UTILITIES ARE DAMAGED.

- 15. PAYMENT FOR LOCATING AND MARKING UNDERGROUND UTILITIES AND CABLES WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE RESPECTIVE
- 16. THE CONTRACTOR WILL DETERMINE IF THERE IS A CONFLICT BETWEEN THE INSTALLATION OF THE PROPOSED ELECTRICAL DUCTS AND ANY EXISTING UTILITIES. THE CONTRACTOR WILL MAKE ALL NECESSARY ADJUSTMENTS IN DEPTH OF INSTALLATION TO AVOID ANY AND ALL PROPOSED UNDERGROUND IMPROVEMENTS
- 17. CONDUITS FOR DIRECT BURIAL OR CONCRETE ENCASED DUCT BANK SHALL BE SCHEDULE 40 (MINIMUM) PVC CONDUIT, UL-LISTED, RATED FOR 90°C CABLE-CONFORMING TO NEMA STANDARD TC-2 AND UL 651, LISTED SUITABLE FOR UNDERGROUND USE EITHER DIRECT-BURIED OR ENCASED IN CONCRETE, OR SCHEDULE 40 (MINIMUM) HDPE CONDUIT UL LISTED, CONFORMING TO NEMA STANDARD TC-7 AND UL 651B AND LISTED SUITABLE FOR UNDERGROUND USE; EITHER DIRECT BURY OR ENCASED IN CONCRETE. HEAVIER WALL CONDUITS SHALL BE FURNISHED FOR RESPECTIVE APPLICATIONS WHERE DETAILED
- 18. CONDUITS FOR DIRECTIONAL BORING SHALL BE SCHEDULE 40 PVC CONDUIT OR SCHEDULE 80 PVC CONDUIT, UL-LISTED, RATED FOR 90°C CABLE-CONFORMING TO NEMA STANDARD TC-2 AND UL 651 AND SUITABLE FOR DIRECTIONAL BORING INSTALLATION, SCHEDULE 80 HDPE CONDUIT, UL-LISTED, CONFORMING TO NEMA STANDARD TC-7 AND UL 651B AND SUITABLE FOR DIRECTIONAL BORING INSTALLATION, OR WALL TYPE MINIMUM SDR 11 HDPE CONDUIT MANUFACTURED IN ACCORDANCE WITH ASTM D-3350 (SPECIFICATION OF POLYETHYLENE PLASTICS PIPE AND FITTINGS MATERIALS) AND ASTM F2160 (STANDARD SPECIFICATION FOR SOLID WALL, HIGH-DENSITY POLYETHYLENE CONDUIT BASED ON CONTROLLED OUTSIDE DIAMETER), AND SUITABLE FOR DIRECTIONAL BORING INSTALLATION. PER NEC 300.5 (K), RACEWAYS INSTALLED USING DIRECTIONAL BORING EQUIPMENT SHALL BE APPROVED FOR THE PURPOSE.
- 19. UNDERGROUND DUCTS INSTALLED BY DIRECTIONAL-BORING METHOD SHALL BE INSTALLED IN A MANNER THAT WILL NOT DAMAGE ANY EXISTING UNDERGROUND UTILITIES. AND SHALL NOT DISTURB OR DAMAGE THE RESPECTIVE PAVEMENT OR ROADWAY SURFACE. DUCTS SHALL BE DIRECTIONAL-BORED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION PLANS. THE DUCTS WILL BE BORED AT A MINIMUM DEPTH OF 42 IN. BELOW THE RESPECTIVE PAVEMENT IT IS BEING BORED UNDER
- 20. A PULL WIRE SHALL BE INSTALLED IN EACH CONDUIT OR DUCT TO BE LEFT VACANT.
- 21. CONTRACTOR SHALL COORDINATE DUCT MARKING WITH AIRPORT
- 22. ALL POWER AND CONTROL CABLES IN HANDHOLES, MANHOLES, AND JUNCTION BOXES SHALL BE TAGGED TO IDENTIFY THE RESPECTIVE CABLE. A MINIMUM OF TWO TAGS SHALL BE PROVIDED ON EACH CABLE IN A MANHOLE; ONE AT THE CABLE ENTRANCE AND ONE AT THE CABLE EXIT. CABLE TAGS SHALL BE STAMPED BRASS TAGS OR OTHER WEATHERPROOF/WATERPROOF CORROSION RESISTANT MATERIAL

www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA. ILLINOIS 62839



INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

	NO.	DATE	DES	CRIPT	ION
	NO.	DATE	DES	DWN	REV
	ISSUE:	JULY 25	5, 2025	;	
ı	PROJEC	CT NO: 2	3A103	8	

CAD FILE: E-503-DETL.DWG

DESIGN BY: KNI 3/31/2025 DRAWN BY: CWS 4/4/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE


CONDUIT TRENCH **DETAIL**

BID DOCUMENTS


SECTION VIEW

TURF SPLICE MARKERS

"NOT TO SCALE"




MARKER




SECTION VIEW

TURF DUCT MARKERS "NOT TO SCALE"



SECTION VIEW


TURF CABLE MARKERS "NOT TO SCALE"




BITUMINOUS PAVEMENT DUCT MARKERS

NOTE:

- TOP OF MARKER SHALL BE FLUSH WITH FINISHED PAVEMENT SURFACE. MARKER MAY BE INSTALLED IN A DRILLED HOLE AND SECURED WITH EPOXY GLUE
- 2. BRASS DUCT MARKERS ARE AVAILABLE FROM BERNTSEN INTERNATIONAL INC., P.O. BOX 8670, MADISON, WI. 53708-8670, PHONE: 1-877-959-8556, SURV-KAP, 3225 E. 47TH ST., TUCSON, AZ 85713, PHONE: (502)-622-6011, OR OTHER EQUIVALENT



DUCT MARKER DETAIL-PLAN "NOT TO SCALE"



UNDERGROUND ELECTRICAL DUCT

(NOT TO SCALE)

CABLE & DUCT MARKER NOTES:

- THE COST OF ALL TURF AND PAVEMENT DUCT MARKERS SHALL BE INCIDENTAL TO THE DUCT. THE COST OF ALL CABLE MARKERS SHALL BE INCIDENTAL TO THE
- BITUMINOUS PAVEMENT DUCT MARKER AND CONCRETE DUCT MARKER TO BE PROVIDED AT EACH END OF EACH DUCT AS SHOWN ON THE LOCATION PLAN. FOR CONCRETE PAVEMENT, THE LETTER "D" SHALL BE IMPRESSED IN THE PAVEMENT INSTEAD OF THE MARKER. THE LETTER SHALL BE INFORMED AS DESCRIBED IN NOTE 4.
- UNDERGROUND CABLE RUNS MUST BE IDENTIFIED BY CABLE MARKERS AT 200 FEET (61 M) MAXIMUM SPACING WITH AN ADDITIONAL MARKER AT EACH CHANGE OF DIRECTION OF THE CABLE RUN. CABLE MARKERS MUST BE INSTALLED ABOVE THE CABLE. CABLE MARKERS ARE NOT REQUIRED FOR CABLE RUNS BETWEEN RUNWAY/TAXIWAY EDGE LIGHTS.
- CONCRETE CABLE MARKERS AND DUCT MARKERS SHALL HAVE LETTERS 4" HIGH, 3" WIDE WITH WIDTH OF STROKE 1/2" AND 1/4" DEEP. ALL LETTERS, NUMBERS AND ARROWS TO BE IMPRESSED.
- EMPLOY THE FOLLOWING METHODS WHERE ADDITIONAL SPACE TO FIT THE LEGEND IS REQUIRED:
 - A. REDUCE LETTER SIZE TO 3" HIGH, 2" WIDE
 - B. INCREASE THE MARKER SIZE TO 30" X 30".
 - C. PROVIDE ADDITIONAL MARKERS PLACED SIDE BY SIDE
- TURF DUCT MARKERS ARE NOT REQUIRED AT PAVEMENT CROSSINGS WHERE DUCTS TERMINATE IN HANDHOLES, OR JUNCTION STRUCTURES.
- LOCATION OF ALL DIRECT EARTH BURIAL UNDERGROUND CABLE SPLICE/CONNECTIONS, EXCEPT THOSE AT ISOLATION TRANSFORMERS, MUST BE IDENTIFIED BY SPLICE MARKERS. SPLICE MARKERS MUST BE PLACED ABOVE THE SPLICE/CONNECTIONS. DIRECT EARTH BURIAL UNDERGROUND CABLE SPLICES SHALL BE AVOIDED WHERE POSSIBLE. CABLE SPLICES SHALL BE LOCATED IN SPLICE CANS, LIGHT BASES, HANDHOLES, MANHOLES, OR OTHER JUNCTION STRUCTURES UNLESS OTHERWISE APPROVED BY THE PROJECT ENGINEER OF RECORD
- THE CABLE AND SPLICE MARKERS MUST IDENTIFY THE CIRCUITS TO WHICH THE CABLES BELONG. FOR EXAMPLE: TWY A, TWY B.
- LOCATIONS OF ENDS OF ALL UNDERGROUND DUCTS MUST BE IDENTIFIED BY DUCT MARKERS

www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN



INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD


	NO.	DATE	DES	CRIPT	ION
	NO.	DATE	DES	DWN	REV
	ISSUE:	JULY 25	5, 2025	;	
i	PROJEC	CT NO: 2	3A103	8	
	CAD EII	E. E 604 D	ETI DWC		

DESIGN BY: KNI 3/31/2025 DRAWN BY: CWS 4/4/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

CABLE AND DUCT MARKER DETAILS "NOT TO SCALE"




HEAVY DUTY FRAME & LID SUITABLE FOR -40,000 LBS LOADING, NEENAH CAT. NO. R-6662-PP, EAST JORDAN IRON WORKS SMOOTH TROWEL CAT. NO. 8213, OR APPROVED EQUAL. FINISH, SLOPE TO HANDHOLF RATED SUITABLE FOR 40,000 LBS. LOADING. DUCT/CONDUIT \bigcirc PROVIDE CONDUIT 6" SAND CUSHION BUSHING OR BELL AT 6" SCHED 40 PVC DRAIN PIPE. TERMINATION IN FILL WITH PEA GRAVEL TO HANDHOLE (TYP.) ACCOMMODATE DRAINAGE

> **ELEVATION** "NOT TO SCALE"

HANDHOLE NOTES:

- LIDS FOR LOW VOLTAGE HANDHOLES (CONTAINING CIRCUITS RATED 600 VOLTS AND BELOW) SHALL BE LABELED "LOW VOLTAGE" OR "0V - 600V ELECTRIC". LIDS FOR HIGH VOLTAGE HANDHOLES CONTAINING AIRFIELD LIGHTING SERIES CIRCUIT WIRING SHALL BE LABELED "DANGER HIGH VOLTAGE KEEP OUT 5000 VOLTS" TO COMPLY WITH 2023 NEC ARTICLE 305.12 "WARNING SIGNS", NEC ARTICLE 314.30 "HANDHOLE ENCLOSURES" (D) "COVERS" AND NEC ARTICLE 314.72 (E) "SUITABLE COVERS". COORDINATE LETTERING WITH MFR. HANDHOLES PROVIDED WITH THE WRONG LIDS SHALL HÁVE THE LIDS REPLACED WITH THE CORRECT LIDS AT NO ADDITIONAL COST TO THE CONTRACT.
- 2. ELECTRICAL HANDHOLE, FRAME & LID SHALL BE CAPABLE OF WITHSTANDING MINIMUM 40,000 POUND LOADS.
- REINFORCEMENT SHALL BE #6 BARS AT 6" CENTERS BASE & WALLS EACH WAY.
- 4. CONCRETE SHALL BE 5000 PSI AT 28 DAYS.
- 5. HANDHOLES SHALL BE PRECAST. PRECAST MANUFACTURER MUST BE ON THE IDOT (ILLINOIS DEPARTMENT OF TRANSPORTATION) APPROVED LIST OF CERTIFIED PRECAST CONCRETE PRODUCERS.
- FRAMES AND LIDS (CASTINGS) SHALL BE MADE IN THE USA TO COMPLY WITH THE AIRPORT IMPROVEMENT PROGRAM BUY AMERICAN PRÈFERENCES REQUIREMENTS.
- 7. COORDINATE INSTALLATION OF HANDHOLES WITH RESPECTIVE FINISHED GRADE ELEVATION.
- ALL CORING, INTERFACE, AND LABOR ASSOCIATED WITH CONDUIT, DUCT, CABLE IN UNIT DUCT, AND/OR CABLE ENTRIES WILL BE CONSIDERED INCIDENTAL TO THE INSTALLATION OF THE HANDHOLE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 9. HANDHOLES WITH SIMILAR DIMENSIONS MEETING STRENGTH AND LOADING REQUIREMENTS WILL BE CONSIDERED.



SPLICE CAN/JUNCTION CAN DETAIL "NOT TO SCALE"

NOTES FOR SPLICE CAN/JUNCTION CAN DETAIL:

INCLUDE INTERNAL & EXTERNAL

GROUND LUGS (REQUIRED PER

- SPLICE CANS SHALL CONFORM TO THE REQUIREMENTS OF FAA AC 150/5345-42 (CURRENT ISSUES IN EFFECT), FOR TYPE L-867, CLASS IA, SIZE D, (16 IN. NOMINAL DIAMETER), AND 24 IN. DEEP AND/OR AS DETAILED ON THE PLANS. EACH SPLICE CAN SHALL INCLUDE INTERNAL AND EXTERNAL GROUND LUGS TO ACCOMMODATE THE RESPECTIVE APPLICATIONS. SPLICE CANS AND/OR JUNCTION CANS SHALL HAVE GALVANIZED STEEL COVERS, 3/8-INCH THICK (MINIMUM), WITH STAINLESS STEEL BOLTS.
- 2. FOR THE PURPOSE OF ENHANCING SAFETY, EACH BASE MUST HAVE INSTALLED, BY THE MANUFACTURER, AN INTERNAL AND EXTERNAL GROUND STRAP THAT IS AVAILABLE FOR THE PURPOSE OF ATTACHING A GROUND LUG THAT IS CONNECTED TO AN EARTH GROUND OR A SAFETY GROUND CONDUCTOR INSTALLED WITH THE RESPECTIVE CIRCUIT. FOR AIRPORT PROJECTS RECEIVING FEDERAL FUNDS THIS REQUIREMENT IS MANDATORY PER FAA AC 150/5345-42 (CURRENT ISSUES IN EFFECT).
- APPLY AN OXIDE-INHIBITING, ANTI-SEIZING COMPOUND TO ALL SCREWS, NUTS, AND ALL PLACES WHERE METAL COMES INTO CONTACT WITH METAL.
- THE CONCRETE USED IN THE CONSTRUCTION OF THE BASES FOR THE AIRFIELD LIGHTING CANS SHALL BE IN ACCORDANCE WITH ITEM 610 STRUCTURAL PORTLAND CEMENT CONCRETE.
- 5 LIDS FOR THE SPLICE CANS CONTAINING HIGH VOLTAGE AIRFIELD LIGHTING CABLES SHALL INCLUDE MINIMUM 1/2-INCH HIGH LETTERING LABELED "DANGER HIGH VOLTAGE KEEP OUT" TO COMPLY WITH NEC ARTICLE 300.45 "WARNING SIGNS" AND NEC ARTICLE 314.71(E) "SUITABLE COVERS". THIS WILL NEED TO BE COORDINATED WITH THE SPLICE CAN MANUFACTURER.
- 6. LIDS FOR THE SPLICE CANS CONTAINING LOW VOLTAGE CABLES (RATED 600 VOLTS AND BELOW) WILL BE ACCEPTABLE TO USE BLANK COVERS.

www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN



INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DESCRIPTION			
NO.	DATE	DES	DWN	REV	
ISSUE:	JULY 25	5, 2025	5		
PROJEC	PROJECT NO: 23A1038				
CAD FIL	E: E-505-D	ETL.DWG	;		
DESIGN	BY: KN	L 3/3	1/2025		

SHEET TITLE

HANDHOLE AND SPLICE CAN DETAILS

DRAWN BY: CWS 4/4/2025

REVIEWED BY: KNL 6/24/2025

 CONTRACTOR SHALL KEEP A COPY OF THE LATEST NEC IN FORCE ON SITE AT ALL TIMES DURING CONSTRUCTION FOR USE AS A REFERENCE.

3. CONTRACTOR SHALL COORDINATE WORK AND ANY POWER OUTAGES AND/OR SHUT DOWN OF SYSTEMS WITH THE RESPECTIVE FACILITY OWNER PERSONNEL AND THE AIRPORT MANAGER/DIRECTOR. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).

4. THE CONTRACTOR SHALL ASCERTAIN THAT ALL LIGHTING SYSTEM COMPONENTS FURNISHED BY HIM, INCLUDING FAA APPROVED EQUIPMENT, ARE COMPATIBLE IN ALL RESPECTS WITH EACH OTHER AND THE REMAINDER OF THE NEW/EXISTING SYSTEM. ANY NONCOMPATIBLE COMPONENTS FURNISHED BY THIS CONTRACTOR SHALL BE REPLACED BY HIM AT NO ADDITIONAL COST TO THE AIRPORT SPONSOR WITH A SIMILAR UNIT, APPROVED BY THE ENGINEER (DIFFERENT MODEL OR DIFFERENT MANUFACTURER) THAT IS COMPATIBLE WITH THE REMAINDER OF THE AIRPORT LIGHTING SYSTEM.

5. IN CASE THE CONTRACTOR ELECTS TO FURNISH AND INSTALL AIRPORT LIGHTING EQUIPMENT REQUIRING ADDITIONAL WIRING, TRANSFORMERS, ADAPTORS, MOUNTINGS, ETC., TO THOSE SHOWN ON THE DRAWINGS AND/OR LISTED IN THE SPECIFICATION, <u>ANY COST FOR THESE ITEMS SHALL BE INCIDENTAL TO THE</u> EQUIPMENT COST.

6. THE CONTRACTOR INSTALLED EQUIPMENT (INCLUDING FAA APPROVED) SHALL NOT GENERATE ANY ELECTROMAGNETIC INTEREFERENCE IN THE EXISTING AND/OR NEW COMMUNICATIONS, WEATHER, AIR NAVIGATION, AND AIR TRAFFIC CONTROL EQUIPMENT. ANY EQUIPMENT GENERATING SUCH INTERFERENCE SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST WITH THE EQUIPMENT MEETING THE APPLICABLE SPECIFICATIONS AND NOT GENERATING ANY INTERFERENCE.

 WHEN A SPECIFIC TYPE, STYLE, CLASS, ETC. OF FAA APPROVED EQUIPMENT IS SPECIFIED ONLY THAT TYPE, STYLE, CLASS, WILL BE ACCEPTABLE, EVEN THOUGH EQUIPMENT OF OTHER TYPES STYLES, CLASSES, ETC. MAY BE APPROVED.

8. ANY AND ALL INSTRUCTIONS FROM THE RESIDENT ENGINEER/RESIDENT TECHNICIAN TO THE CONTRACTOR REGARDING CHANGES IN OR DEVIATIONS FROM THE PLANS AND SPECIFICATIONS SHALL BE IN WRITING WITH COPIES SENT TO THE AIRPORT SPONSOR AND THE ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF AERONAUTICS. THE CONTRACTOR SHALL NOT ACCEPT ANY VERBAL INSTRUCTIONS FROM THE RESIDENT ENGINEER/RESIDENT TECHNICIAN REGARDING ANY CHANGES FROM THE PLANS AND SPECIFICATIONS.

9. A MINIMUM OF THREE COPIES OF THE INSTRUCTION BOOK SHALL BE SUPPLIED WITH EACH DIFFERENT TYPE OF EQUIPMENT. THE BOOKS DESCRIBING A MORE SOPHISTICATED TYPE OF EQUIPMENT, SUCH AS REGULATORS, PAPI, REIL, ETC. AS A MINIMUM SHALL CONTAIN THE FOLLOWING:

 A DETAILED DESCRIPTION OF THE OVERALL EQUIPMENT AND ITS INDIVIDUAL COMPONENTS.

B. THEORY OF OPERATION INCLUDING THE FUNCTION OF EACH COMPONENT.

C. INSTALLATION INSTRUCTION.

D. START-UP INSTRUCTIONS.

E. PREVENTATIVE MAINTENANCE REQUIREMENTS.

F. CHART FOR TROUBLE-SHOOTING.

G. COMPLETE POWER AND CONTROL DETAILED WIRING DIAGRAM(S), SHOWING EACH CONDUCTOR/CONNECTION/COMPONENT - "BLACK" BOXES ARE NOT ACCEPTABLE. THE DIAGRAM OF THE NARRATIVE SHALL SHOW VOLTAGE/CURRENTS/WAVE SHAPES AT STRATEGIC LOCATIONS TO BE USED WHEN CHECKING AND/OR TROUBLE-SHOOTING THE EQUIPMENT. WHEN THE EQUIPMENT HAS SEVERAL MODES OF OPERATION, SUCH AS SEVERAL BRIGHTNESS STEPS, THESE PARAMETERS SHALL BE INDICATED FOR ALL DIFFERENT MODES.

H. PARTS LIST WHICH WILL INCLUDE ALL MAJOR AND MINOR COMPONENTS SUCH AS RESISTORS, DIODES, ETC. IT SHALL INCLUDE A COMPLETE NOMENCLATURE OF EACH COMPONENT AND, IF APPLICABLE, THE NAME OF ITS MANUFACTURER AND THE CATALOG NUMBER.

I. SAFETY INSTRUCTIONS.

POWER AND CONTROL NOTES

PROVIDE LEGEND PLATES FOR ALL ELECTRICAL EQUIPMENT TO IDENTIFY FUNCTION, CIRCUIT VOLTAGE AND PHASE. WHERE THE EQUIPMENT CONTAINS FUSES, ALSO IDENTIFY THE FUSE OR FUSE LINK AMPERE RATING. WHERE THE EQUIPMENT DOES NOT HAVE SUFFICIENT AREA TO INSTALL LEGEND PLATES, THE LEGEND PLATES SHALL BE INSTALLED ON THE WALL NEXT TO THE UNIT. LEGEND PLATES SHALL BE WEATHERPROOF ENGRAVED PLASTIC OR PHENOLIC MATERIAL, 1/4" HIGH BLACK LETTERS ON A WHITE BACKGROUND UNLESS NOTED OTHERWISE. SECURE WITH WEATHERPROOF ADHESIVE AND MACHINE SCREWS. FURNISH ADDITIONAL LEGEND PLATES WHERE REQUIRED BY CODE, FOR ADDITIONAL EQUIPMENT, AS DETAILED HEREIN ON THE PLANS, AND AS NOTED IN THE SPECIAL PROVISION SPECIFICATIONS.

2. COLOR CODE ALL PHASE WIRING BY THE USE OF COLORED WIRE INSULATION AND/OR COLORED TAPE. WHERE TAPE IS USED, THE WIRE INSULATION SHALL BE BLACK. BLACK AND RED SHALL BE USED FOR PHASE CONDUCTORS ON 120/240VAC SINGLE-PHASE, THREE WIRE SYSTEMS AND BLACK, RED AND BLUE SHALL BE USED FOR PHASE CONDUCTORS ON 208/120VAC THREE-PHASE, FOUR WIRE SYSTEMS. NEUTRAL CONDUCTORS, SIZE NO. 6 AWG OR SMALLER, SHALL BE IDENTIFIED BY A CONTINUOUS WHITE OR NATURAL GRAY OUTER FINISH ALONG ITS ENTIRE LENGTH. NEUTRAL CONDUCTORS LARGER THAN NO. 6 AWG SHALL BE IDENTIFIED EITHER BY A CONTINUOUS WHITE OR NATURAL GRAY OUTER FINISH ALONG ITS ENTIRE LENGTH OR BY THE USE OF WHITE TAPE AT ITS TERMINATIONS AND INSIDE ACCESSIBLE WIREWAYS. INSULATED GROUND CONDUCTORS SHALL HAVE GREEN COLORED INSULATION FOR ALL CONDUCTOR SIZES (AWG OR KCMIL).

 ALL BRANCH CIRCUIT CONDUCTORS CONNECTED TO A PARTICULAR PHASE SHALL BE IDENTIFIED WITH THE SAME COLOR. THE COLOR CODING SHALL BE EXTENDED TO THE POINT OF UTILIZATION.

 IN CONTROL WIRING THE SAME COLOR SHALL BE USED THROUGHOUT THE SYSTEM FOR THE SAME FUNCTION, SUCH AS 10%, 30%, 100% BRIGHTNESS CONTROL. ETC.

 LOW VOLTAGE (600 V.) AND HIGH VOLTAGE (5000 V.) CONDUCTORS SHALL BE INSTALLED IN SEPARATE WIREWAYS.

6. NEATLY LACE WIRING IN DISTRIBUTION PANELS, WIREWAYS, SWITCHES AND

7. THE MINIMUM SIZE OF PULL/JUNCTION BOXES, REGARDLESS OF THE QUANTITY AND SIZE OF THE CONDUCTORS SHOWN, SHALL BE AS FOLLOWS:

A. IN STRAIGHT PULLS THE LENGTH OF THE BOX SHALL NOT BE LESS THAN EIGHT TIMES THE TRADE DIAMETER OF THE LARGER CONDUIT. THE TOTAL AREA (INCLUDING THE CONDUIT CROSS-SECTIONAL AREA) OF A BOX END SHALL BE AT LEAST 3 TIMES GREATER THAN THE TOTAL TRADE CROSS-SECTIONAL AREA OF THE CONDUITS TERMINATING AT THE END.

B. IN ANGLE PULLS OR 'U' PULLS THE DISTANCE BETWEEN EACH CONDUIT ENTRY INSIDE THE BOX AND THE OPPOSITE WALL OF THE BOX SHALL NOT BE LESS THAN SIX (6) TIMES THE TRADE DIAMETER OF THE LARGEST CONDUIT. THIS DISTANCE SHALL BE INCREASED FOR ADDITIONAL ENTRIES BY THE AMOUNT OF THE SUM OF THE DIAMETERS OF ALL OTHER CONDUIT ENTRIES ON THE SAME WALL AS THE BOX. THE DISTANCE BETWEEN CONDUIT ENTRIES ENCLOSING THE SAME CONDUCTOR SHALL NOT BE LESS THAN SIX TIMES THE TRADE DIAMETER OF THE LARGEST CONDUIT.

8. A RUN OF CONDUIT BETWEEN TERMINATIONS AT EQUIPMENT ENCLOSURES, SQUARE DUCTS AND PULL/JUNCTION BOXES, SHALL NOT CONTAIN MORE THAN THE EQUIVALENT OF FOUR QUARTER BENDS (360 DEGREES TOTAL), INCLUDING THOSE BENDS LOCATED IMMEDIATELY AT THE TERMINATIONS, CAST, CONDUIT TYPE OUTLETS SHALL NOT BE TREATED AS PULL/JUNCTION BOXES.

 EQUIPMENT CABINETS SHALL NOT BE USED AS PULL/JUNCTION BOXES. ONLY WIRING TERMINATING AT THE EQUIPMENT SHALL BE BROUGHT INTO THESE ENCLOSUBES.

10. SPLICES AND JUNCTION POINTS SHALL BE PERMITTED ONLY IN JUNCTION BOXES, DUCTS EQUIPPED WITH REMOVABLE COVERS, AND AT EASILY ACCESSIBLE LOCATIONS

11. CIRCUIT BREAKERS IN POWER DISTRIBUTION PANEL(S) SHALL BE THERMAL-MAGNETIC MOLDED CASE, PERMANENT TRIP WITH 100 AMPERE, MINIMUM FRAME.

12. DUAL LUGS SHALL BE USED WHERE TWO (2) WIRES, SIZE NO. 6 OR LARGER, ARE TO BE CONNECTED TO THE SAME TERMINAL.

13. ALL INTERIOR WALL MOUNTED EQUIPMENT ENCLOSURES SHALL BE MOUNTED ON HOT DIPPED GALVANIZED STEEL STRUT SUPPORT, OR STAINLESS STEEL STRUT SUPPORT, WITH CORROSION RESISTANT HARDWARE. PROVIDE ZINC RICH PAINT APPLIED TO FIELD CUTS OF GALVANIZED STEEL SUPPORT TO MINIMIZE THE POTENTIAL FOR CORROSION PER THE RESPECTIVE STRUT SUPPORT MANUFACTURER'S RECOMENTATIONS.

4. SUPPORT FOR EXTERIOR MOUNTED EQUIPMENT SHALL USE STAINLESS STEEL STRUT SUPPORT WITH STAINLESS STEEL HARDWARE.

5. CONDUITS FOR ELECTRIC SERVICE ENTRANCE AND FEEDERS SHALL BE AS DETAILED HEREIN ON THE PLANS. WHERE GALVANIZED RIGID STEEL CONDUIT IS SPECIFIED IT SHALL HAVE THREADED FITTINGS. SET SCREW TYPE FITTINGS WILL NOT BE ACCEPTABLE. CONDUITS FOR UNDERGROUND APPLICATIONS SHALL BE AS DETAILED HEREIN. CONDUITS FOR GROUNDING ELECTRODE CONDUCTORS OR INDIVIDUAL GROUNDING CONDUCTORS SHALL BE SCHEDULE 40 OR SCHEDULE 80 PVC.

16. PROVIDE LIQUID TIGHT FLEXIBLE METAL CONDUIT AT CONNECTIONS TO EQUIPMENT SUBJECT TO VIBRATION OR WHERE FLEXIBILITY IS REQUIRED. LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE U.L. LISTED TO MEET THE REQUIREMENTS OF NEC 350.6, SUITABLE FOR GROUNDING, SUNLIGHT RESISTANT, AND RESISTANT TO OIL, GASOLINE, AND GREASE. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO MOTORS, TRANSFORMERS, & CONSTANT CURRENT REGULATORS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.60. DO NOT INSTALL LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS NOT UL. LISTED. CONFIRM LIQUID-TIGHT FLEXIBLE METAL CONDUIT BEARS THE UL LABEL PRIOR TO INSTALLING IT.

17. UNLESS OTHERWISE SHOWN, ALL EXPOSED CONDUITS SHALL BE RUN PARALLEL TO OR AT RIGHT ANGLES WITH THE LINES OF THE STRUCTURE.

18. ALL STEEL CONDUITS, FITTINGS, NUTS, BOLTS, ETC. SHALL BE GALVANIZED.

 USE CONDUIT BUSHINGS AT EACH CONDUIT TERMINATION. WHERE NO. 4 AWG OR LARGER UNDERGROUND WIRE IS INSTALLED, USE INSULATED BUSHINGS.

20. USE DOUBLE LOCK NUTS AT EACH CONDUIT TERMINATION.

21. WRAP ALL PRIMARY AND SECONDARY POWER CONNECTIONS WITH SUFFICIENT LAYERS OF HIGH VOLTAGE ELECTRICAL INSULATING TAPE (RUBBER SPLICING TAPE SUITABLE FOR PRIMARY ELECTRICAL INSULATION FOR SPLICING CABLE FROM 600 VOLTS TO 69,000 VOLTS) AND COVER WITH VINYL ELECTRICAL TAPE (ALL-WEATHER VINYL INSULATING TAPE SUITABLE FOR PROTECTIVE JACKETING FOR HIGH-VOLTAGE CABLE SPLICES AND REPAIRS) FOR FULL VALUE OF CABLE INSULATION VOLTAGE. PER ILLINOIS STANDARD SPECIFICATIONS FOR CONSTRUCTION OF AIRPORTS ITEM 108, ITEM 125 AND FAA AC 150/5370-10H ITEM L-108, HIGH VOLTAGE ELECTRICAL INSULATING TAPE SHALL BE 3M SCOTCH 130C (2 INCHES WIDE) OR APPROVED EQUIVALENT, AND VINYL ELECTRICAL TAPE SHALL BE 3M SCOTCH 88 (1.5 INCHES WIDE) OR APPROVED EQUIVALENT. TAPES MUST BE RATED SUITABLE FOR THE APPLICATION.

22. UNLESS OTHERWISE NOTED, ALL SINGLE CONDUCTOR CONTROL WIRING SHALL BE NO. 12 AWG, COPPER MINIMUM.

23. THE FOLLOWING SHALL APPLY TO RELAY/CONTACTOR PANELS/ENCLOSURES:

A. FOR INTERIOR LOCATIONS ALL COMPONENTS SHALL BE MOUNTED IN NEMA 12 (DUST TIGHT) ENCLOSURE(S) WITH VERTICALLY HINGED COVERS. FOR EXTERIOR/OUTDOOR LOCATIONS ALL COMPONENTS SHALL BE MOUNTED IN NEMA 4X STAINLESS STEEL ENCLOSURE(S) WITH VERTICALLY HINGED COVERS. ALL CONDUIT ENTRIES INTO NEMA 4, 4X ENCLOSURES SHALL HAVE NEMA 4 HUBS LISTED SUITABLE FOR THE RESPECTIVE ENCLOSURE TO MAINTAIN THE NEMA 4, 4X RATING OF THE ENCLOSURE.

B. THE ENCLOSURE(S) SHALL HAVE AMPLE SPACE FOR THE CIRCUIT COMPONENTS, TERMINAL BLOCKS AND INCOMING AND INTERNAL WIRING.

2. ALL CONTROL CONDUCTOR TERMINATIONS SHALL BE OF THE OPEN-EYE CONNECTOR/SCREW TYPE. SOLDERED CLOSED-EYE TERMINATIONS, OR TERMINATIONS WITHOUT CONNECTORS ARE NOT ACCEPTABLE.

D. WHEN THE ENCLOSURE COVER IS OPENED, ALL CIRCUIT COMPONENTS, WIRING AND TERMINALS SHALL BE EXPOSED AND ACCESSIBLE WITHOUT REMOVAL OF ANY PANELS, COVERS, ETC., EXCEPT THOSE COVERING HIGH VOLTAGE COMPONENTS.

E. ACCESS TO, OR REMOVAL OF A CIRCUIT COMPONENT OR TERMINAL BLOCK WILL NOT REQUIRE THE REMOVAL OF ANY OTHER CIRCUIT COMPONENT OR TERMINAL BLOCK

. EACH CIRCUIT COMPONENT SHALL BE CLEARLY IDENTIFIED INDICATING ITS CORRESPONDING NUMBER SHOWN ON THE DRAWINGS AND ITS FUNCTION.

G. A COMPLETE WIRING DIAGRAM SHALL BE MOUNTED ON THE INSIDE OF THE COVER. THE DIAGRAM SHALL REPRESENT EACH CONDUCTOR BY A SEPARATE LINE.

H. THE DIAGRAM SHALL IDENTIFY EACH CIRCUIT COMPONENT AN NUMBERING AND COLOR OF EACH TERMINAL CONDUCTOR AND TERMINAL.

I. ALL WIRING SHALL BE NEATLY TRAINED AND LACED.

J. MINIMUM WIRE SIZE SHALL BE NO. 12 AWG.

THE ABOVE GENERAL NOTES & POWER AND CONTROL NOTES
ARE BASED ON DEPT. OF TRANSPORTATION FAA GREAT LAKES REGION
ELECTRICAL NOTES SUBMITTED BY AL GRIGAITIS, DATE: 2/11/1987 AND HAVE
BEEN UPDATED BY KEVIN LIGHTFOOT TO ACCOMMODATE CODE CHANGES, FAA
ADVISORY CIRCULAR CHANGES, AND OTHER RESPECTIVE APPLICATIONS.

BID DOCUMENTS

HANSON Engineering | Planning | Alled Services

Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN

KEVIN N. LICHTFOOT 062-047643

DATE LICENSE SIGNED: 7/29/2025 EXPIRES: 11/30/203

INSTALL MEDIUM
INTENSITY RUNWAY
LIGHTS ON RUNWAY
3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO	NO.	DATE	DES	CRIPT	ION
	INO.	DATE	DES	DWN	REV
	ISSUE:	JULY 25	5, 2025	j	
				-	

PROJECT NO: 23A1038
CAD FILE: E-002-NOTES.DWG

DESIGN BY: KNL 3/31/2025 DRAWN BY: CWS 4/4/2025 REVIEWED BY: KNL 6/24/2025

SHEET TITLE

ELECTRICAL NOTES SHEET 1

AIRFIELD LIGHTING NOTES

- UNLESS OTHERWISE NOTED, ALL UNDERGROUND AIRFIELD LIGHTING SERIES CIRCUIT CONDUCTORS WHETHER DEB OR IN DUCT/CONDUIT SHALL BE FAA APPROVED 5000 VOLT L-824 TYPE. ALL UNDERGROUND FIELD POWER LOW VOLTAGE (600 VOLT & BELOW) CIRCUIT CONDUCTORS WHETHER DEB OR IN DUCT/CONDUIT SHALL BE UL LISTED 600 VOLT, TYPE XLP-USE-2 COPPER CONDUCTORS. CONDUCTOR SIZES SHALL BE AS SPECIFIED HEREIN
- NO COMPONENTS OF PRIMARY CIRCUIT SUCH AS CABLE, CONNECTORS AND TRANSFORMERS SHALL BE BROUGHT ABOVE GROUND AT EDGE LIGHTS, SIGNS, REIL, PAPI, ETC.
- B. THERE SHALL BE NO EXPOSED POWER/CONTROL CABLES BETWEEN THE POINT WHERE THEY LEAVE THE UNDERGROUND (DEB OR L-867 BASES) AND WHERE THEY ENTER THE EQUIPMENT (SUCH AS TAXIWAY SIGNS, PAPI, REIL, ETC.) ENCLOSURES. THESE CABLES SHALL BE ENCLOSED IN RIGID CONDUIT OR IN FLEXIBLE, WATERTIGHT CONDUIT WITH BREAKABLE COUPLING(S) AT THE GRADE OR THE HOUSING COVER, AS SHOWN IN APPLICABLE DETAILS.
- 4. THE JOINTS OF THE L-823 PRIMARY CONNECTORS SHALL BE WRAPPED WITH AT LEAST ONE LAYER OF RUBBER OR SYNTHETIC RUBBER TAPE AND ONE LAYER OF PLASTIC TAPE, ONE-HALF LAPPED, EXTENDING AT LEAST 1-1/2 INCHES ON EACH SIDE OF THE JOINT, AS SHOWN ON AIRFIELD LIGHTING CABLE SPLICE DETAILS.
- THE CABLE ENTRANCE INTO THE FIELD-ATTACHED L-823 CONNECTORS SHALL BE ENCLOSED BY A HEAT-SHRINKABLE TUBING WITH CONTINUOUS INTERNAL ADHESIVE, AS SHOWN ON AIRFIELD LIGHTING CABLE SPLICE DETAILS.
- L-823 TYPE II, TWO-CONDUCTOR SECONDARY CONNECTORS SHALL BE CLASS 'A' (FACTORY MOLDED).
- THERE SHALL BE NO SPLICES IN THE SECONDARY CABLE(S) WITHIN THE STEMS OF A RUNWAY/TAXIWAY EDGE/THRESHOLD LIGHTING FIXTURE AND THE WIREWAYS LEADING TO TAXIWAY SIGNS AND PAPI/REIL EQUIPMENT.
- ELECTRICAL INSULATING GREASE SHALL BE APPLIED WITHIN THE L-823, SECONDARY, TWO
 CONDUCTOR CONNECTORS TO PREVENT WATER ENTRANCE. THESE CONNECTORS SHALL
 NOT BE TAPED.
- DEB ISOLATION TRANSFORMERS SHALL BE BURIED AT A DEPTH OF TEN (10") INCHES ON A LINE CROSSING THE LIGHT AND PERPENDICULAR TO THE RUNWAY/TAXIWAY CENTERLINE AT A LOCATION TWELVE (12") INCHES FROM THE LIGHT OPPOSITE FROM THE BLINIMAY/TAXIWAY
- 10. A SLACK OF THREE (3') FEET, MINIMUM, PLUS DEPTH OF BASE CAN (IF APPLICABLE), SHALL BE PROVIDED IN THE PRIMARY CABLE AT EACH TRANSFORMER/CONNECTOR TERMINATION. AT STAKE-MOUNTED LIGHTS, THE SLACK SHALL BE LOOSELY COILED IMMEDIATELY BELOW THE ISOLATION TRANSFORMER. THERE SHALL BE NO ADDITIONAL PAYMENT FOR CABLE SLACK AND THEREFORE THE QUANTITY OF PROPOSED CABLE SLACK HAS NOT BEEN INCLUDED IN THE RESPECTIVE CABLE PAY ITEMS.
- 11. DIRECTION OF PRIMARY CABLES SHALL BE IDENTIFIED BY COLOR CODING AS FOLLOWS: WHEN FACING LIGHT WITH BACK TO PAVEMENT, CABLE TO THE LEFT IS CODED RED AND CABLE TO RIGHT IS CODED BLUE. THIS APPLIES TO STAKE MOUNTED LIGHTS AND BASE MOUNTED LIGHTS WHERE THE BASE HAS ONLY ONE ENTRANCE.
- 12. L-867 BASES SHALL BE SIZE B, 24" DEEP, CLASS I, UNLESS OTHERWISE NOTED.
- BASE MOUNTED BREAKABLE COUPLINGS SHALL NOT HAVE WEEP HOLES TO THE OUTSIDE. PLUGGED UP HOLES SHALL NOT BE ACCEPTABLE. IT SHALL BE A 1/4" DIAMETER, MINIMUM, OR EQUIVALENT OPENING FOR DRAINAGE FROM THE SPACE AROUND THE SECONDARY CONNECTOR INTO THE L-867 BASE.
- 14. THE ELEVATION OF THE BREAKABLE COUPLING GROOVE SHALL NOT EXCEED 1-1/2" ABOVE THE EDGE OF THE COVER IN CASE OF BASE MOUNTED COUPLINGS, OR THE TOP OF THE STAKE IN CASE OF STAKE MOUNTED COUPLINGS.
- 15. WHERE THE BREAKABLE COUPLING IS NOT AN INTEGRAL PART OF THE LIGHT FIXTURE STEM OR MOUNTING LEG, A BEAD OF SILICON SEAL SHALL BE APPLIED COMPLETELY AROUND LIGHT STEM OR WIREWAY AT BREAKABLE COUPLING TO PROVIDE A WATERTIGHT SEAL.
- 16. TOPS OF THE STAKES SUPPORTING LIGHT FIXTURES SHALL BE FLUSH WITH THE SURROUNDING GRADE.
- 17. PLASTIC LIGHTING FIXTURE COMPONENTS, SUCH AS LAMP HEADS, STEMS, BREAKABLE COUPLINGS, BASE COVERS, BRACKETS, STAKES, SHALL NOT BE ACCEPTABLE.
- 18. THE TOLERANCE FOR THE HEIGHT OF RUNWAY/TAXIWAY EDGE LIGHTS SHALL BE: ONE (1) INCH. IN CASE OF STAKE MOUNTED LIGHTS, THE SPECIFIED LIGHTING FIXTURE HEIGHT SHALL BE MEASURED BETWEEN THE TOP OF THE STAKE AND THE TOP OF THE LENS. IN CASE OF BASE MOUNTED LIGHTS, THE SPECIFIED LIGHTING FIXTURE HEIGHT SHALL BE MEASURED BETWEEN THE TOP OF THE BASE FLANGE AND THE TOP OF THE LENS, THUS INCLUDING THE BASE COVER, THE FRANGIBLE COUPLING, THE STEM, THE LAMP HOUSING AND THE LENS.
- 19. THE TOLERANCE FOR THE LATERAL SPACING (LIGHT LANE TO RUNWAY/TAXIWAY CENTERLINE) OF RUNWAY/TAXIWAY EDGE LIGHTS SHALL BE ONE (1) INCH. THIS ALSO APPLIES AT INTERSECTIONS TO LATERAL SPACING BETWEEN LIGHTS OF A RUNWAY/TAXIWAY AND THE INTERSECTING RUNWAY/TAXIWAY.

- 20. ENTRANCES INTO L-867 BASES SHALL HAVE CONDUIT COUPLINGS OR REDUCERS TO INTERFACE UNIT DUCT/CONDUIT TO L-867 BASE HUBS, OR SHALL BE SEALED WITH HEAT SHRINK
- GALVANIZED/PAINTED EQUIPMENT/COMPONENT SURFACES SHALL NOT BE DAMAGED BY DRILLING, FILING, ETC. DRAIN HOLES IN METAL TRANSFORMER HOUSINGS SHALL BE MADE BEFORE GALVANIZING.
- 22. EDGE LIGHT NUMBERING TAGS SHALL BE FACING THE PAVEMENT.
- CABLE/SPLICE/DUCT MARKERS SHALL BE PRECAST CONCRETE OF THE SIZE SHOWN.
 LETTERS/NUMBERS/ARROWS FOR THE LEGEND TO BE IMPRESSED INTO THE TOPS OF THE
 MARKERS SHALL BE PRE-ASSEMBLED AND SECURED IN THE MOLD BEFORE THE
 CONCRETE IS POURED. LEGEND INSCRIBED BY HAND IN WET CONCRETE SHALL NOT BE
 ACCEPTABLE.
- 24. ALL UNDERGROUND CABLE RUNS SHALL BE IDENTIFIED BY CABLE MARKERS AT 200 FEET MAXIMUM SPACING, WITH AN ADDITIONAL MARKER AT EACH CHANGE OF DIRECTION OF THE CABLE RUN. CABLE MARKERS SHALL BE INSTALLED IMMEDIATELY ABOVE THE CABLES
- 25. THERE SHALL BE NO SPLICES BETWEEN THE ISOLATION TRANSFORMERS. L-823 CONNECTORS ARE ALLOWED AT TRANSFORMER CONNECTIONS ONLY, UNLESS OTHERWISE SHOWN
- 26. APPLY AN OXIDE INHIBITING, ANTI-SEIZING COMPOUND TO ALL SCREWS, NUTS AND BREAKAGE COUPLING THREADS.
- 27. LOCATIONS OF ENDS OF ALL UNDERGROUND DUCTS SHALL BE IDENTIFIED BY DUCT
- 28. WHERE A PARALLEL, CONSTANT VOLTAGE PAPI SYSTEM IS PROVIDED, THE "T" SPLICES SHALL BE OF THE CAST TYPE.
- CONCRETE USED FOR SLABS, FOOTINGS, BACKFILL AROUND TRANSFORMER HOUSINGS, MARKINGS, ETC. SHALL BE 3500 PSI (MINIMUM) AT 14 DAYS, IN ACCORDANCE WITH ITEM 610 STRUCTURAL PORTI AND CEMENT CONCRETE
- 30. ALL POWER AND CONTROL CABLES IN MAN/HAND HOLES SHALL BE TAGGED. USE EMBOSSED COPPER STRIPS TO BE ATTACHED AT BOTH ENDS TO THE CABLE BY THE USE OF PLASTIC STRAPS. MINIMUM OF TWO TAGS SHALL BE PROVIDED ON EACH CABLE IN A MAN/HAND HOLE-ONE AT THE CABLE ENTRANCE AND ONE AT THE CABLE EXIT.
- THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER. ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO ACCURACY COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER CONTROL AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVE GROUND UTILITIES.
- 22. WHEN PREPARING CABLE FOR SPLICES, THE CONTRACTOR SHALL USE A CABLE STRIPPER/PENCILLER WHENEVER CABLE CONNECTIONS ARE MADE.
- 33. THE ABOVE AIRFIELD LIGHTING NOTES ARE BASED ON DEPT. OF TRANSPORTATION FAA GREAT LAKES REGION ELECTRICAL NOTES SUBMITTED BY AL GRIGAITIS, DATE: 2/11/1987 AND HAVE BEEN UPDATED BY KEVIN LIGHTFOOT TO ACCOMMODATE CODE CHANGES, FAA ADVISORY CIRCULAR CHANGES, AND OTHER RESPECTIVE APPLICATIONS.

GROUNDING NOTES FOR AIRFIELD LIGHTING

- GROUNDING FOR RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS SHALL BE AS DETAILED ON THE PLANS AND AS SPECIFIED HEREIN A GROUND ROD MUST BE INSTALLED AT EACH LIGHT FIXTURE. TAXI GUIDANCE SIGN AND L-867/L-868 BASE. THE PURPOSE OF THE LIGHT BASE GROUND IS TO PROVIDE A DEGREE OF PROTECTION FOR MAINTENANCE PERSONNEL FROM POSSIBLE CONTACT WITH AN ENERGIZED LIGHT BASE OR MOUNTING STAKE THAT MAY RESULT FROM A SHORTED POWER CABLE OR ISOLATION TRANSFORMER. A LIGHT BASE GROUND SHALL BE INSTALLED AT EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS. A LIGHT BASE GROUND SHALL ALSO BE INSTALLED AT EACH STAKE MOUNTED LIGHT FIXTURE. A LIGHT BASE GROUND SHALL BE INSTALLED AND CONNECTED TO THE METAL FRAME OF EACH TAXI GUIDANCE SIGN AS DETAILED ON THE PLANS AND IN ACCORDANCE WITH THE RESPECTIVE TAXI GUIDANCE SIGN MANUFACTURER RECOMMENDATIONS. THE LIGHT BASE GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR BONDED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE AND A 3/4-INCH DIAMETER BY 10-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD. CONNECTIONS TO GROUND LUGS ON THE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE SHALL BE WITH A UL LISTED GROUNDING CONNECTOR. CONNECTIONS TO LIGHT BASES MAY ALSO BE MADE WITH A UL 467 LISTED PIPE CLAMP CONNECTED TO THE GRSC NIPPLE EXTENDING FROM A THREADED LIGHT BASE HUB. CONNECTIONS TO GROUND RODS SHALL BE MADE WITH EXOTHERMIC WELD TYPE CONNECTORS, CADWELD BY PENTAIR ERICO PRODUCTS, INC., THERMOWELD BY CONTINENTAL INDUSTRIES, INC., ULTRAWELD BY HARGER, OR APPROVED EQUAL. EXOTHERMIC WELD CONNECTIONS SHALL BE INSTALLED IN CONFORMANCE WITH THE RESPECTIVE MANUFACTURER'S DIRECTIONS USING MOLDS AS REQUIRED FOR EACH RESPECTIVE APPLICATION. BOLTED CONNECTIONS WILL NOT BE PERMITTED AT GROUND RODS. TOP OF GROUND RODS SHALL BE BURIED 12 INCHES MINIMUM BELOW GRADE, UNLESS SPECIFIED OTHERWISE HEREIN, FOR RESPECTIVE APPLICATIONS.
- PER THE REQUIREMENTS OF FAA AC 150/5340-30J DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS, CHAPTER 12, PART 12.6 "LIGHT FIXTURE BONDING" IT NOTES THE FOLLOWING: BOND THE LIGHT FIXTURE TO THE LIGHT BASE INTERNAL GROUND LUG VIA A NO. 6 AWG STRANDED COPPER WIRE RATED 600 VOLTS WITH GREEN XHHW, THWN-2, OR OTHER SUITABLE INSULATION, BARE STRANDED CONDUCTOR OR A BRAIDED GROUND STRAP OF EQUIVALENT CURRENT RATING. THE BONDING CONDUCTOR LENGTH MUST BE SUFFICIENT TO ALLOW THE REMOVAL OF THE LIGHT FIXTURE FROM THE LIGHT BASE FOR ROUTINE MAINTENANCE. SEE THE LIGHT FIXTURE MANUFACTURER'S INSTRUCTIONS FOR PROPER METHODS OF ATTACHING A BONDING WIRE TO THE FIXTURE.
- STEEL USED TO MANUFACTURE GROUND RODS SHALL BE 100 PERCENT DOMESTIC STEEL.
- CLEAN ALL METAL SURFACES BEFORE MAKING GROUND CONNECTIONS.
 METALLIC SURFACES TO BE JOINED SHALL BE PREPARED BY THE REMOVAL OF
 ALL NON-CONDUCTIVE MATERIAL PER 2020 NATIONAL ELECTRICAL CODE
 ARTICLE 250-12.
- THE RESISTANCE TO GROUND OF THE RESPECTIVE MOUNTING STAKE OR LIGHT BASE (WITH GROUND ROD CONNECTED) MUST BE 25 OHMS OR LESS.
- 6. FOR EACH AIRFIELD LIGHT FIXTURE, TAXI GUIDANCE SIGN, DISTANCE REMAINING SIGN, JUNCTION STRUCTURE/L-867 BASE/L-868 BASE, OR OTHER AIRFIELD LIGHT FIXTURE, THE CONTRACTOR SHALL TEST THE MADE ELECTRODE GROUND SYSTEM WITH AN INSTRUMENT SPECIFICALLY DESIGNED FOR TESTING GROUNDING SYSTEMS. TEST RESULTS SHALL BE RECORDED FOR EACH AIRFIELD LIGHT FIXTURE AND EACH TAXI GUIDANCE SIGN INSTALLATION. IF GROUND RESISTANCE EXCEEDS 25 OHMS, LONGER GROUND RODS OR ADDITIONAL GROUND RODS MIGHT BE REQUIRED. IF GROUND RESISTANCE EXCEEDS 25 OHMS CONTACT THE PROJECT ENGINEER FOR FURTHER DIRECTION. ALSO REFER TO EOR-062-047643 FOR ADDITIONAL INFORMATION ON GROUNDING REQUIREMENTS WHERE APPLICABLE. COPIES OF THE GROUND SYSTEM TEST RESULTS SHALL BE FURNISHED TO THE RESIDENT ENGINEER/RESIDENT TECHNICIAN AND THE PROJECT ENGINEER OF RECORD: KEVIN LIGHTFOOT.
- 7. SAFETY OF PERSONNEL IS THE PRIORITY. PROTECTION OF EQUIPMENT IS SECONDARY. PLEASE BE AWARE THAT GROUNDING DOES NOT GUARANTEE YOU WILL NOT RECEIVE A SHOCK, BE INJURED, OR KILLED FROM DEFECTIVE OR DAMAGED EQUIPMENT OR MATERIALS. PROPER GROUNDING WILL HOWEVER SIGNIFICANTLY REDUCE THE POSSIBILITY OF SHOCK, INJURY, OR DEATH. PLEASE FOCUS ON SAFETY OF PERSONNEL AT ALL TIMES



Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed
Professional Service Corporation
#184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN

WEVEN N.

LIGHTFOOT

062-047643

OF ILLUMBER

OF ILLUMB

TE LICENS

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DESCRIPTION		
NO.	DATE	DES	DWN	REV
SSUE: JULY 25, 2025				
PROJECT NO: 23A1038				

SHEET TITLE


ELECTRICAL NOTES SHEET 2

CAD FILE: E-003-NOTES.DWG

DESIGN BY: KNI 3/31/2025


REVIEWED BY: KNL 6/24/2025

DRAWN BY: CWS 4/4/2025



DETAIL NOTES

- 1. KNOWLEDGEABLE AND QUALIFIED PERSONNEL SHALL PERFORM EXOTHERMIC WELD CONNECTIONS TO ENSURE GOOD, SAFE, & RELIABLE CONNECTIONS. ALL BELOW GRADE CONNECTIONS TO GROUND RODS & GROUND RING CONDUCTORS SHALL BE EXOTHERMIC WELD TYPE CONNECTIONS UNLESS OTHERWISE APPROVED BY THE PROJECT ENGINEER OF RECORD: KEVIN LIGHTFOOT. EXOTHERMIC WELDS SHALL BE CADWELD AS MANUFACTURED BY PENTAIR ERICO PRODUCTS, ULTRAWELD AS MANUFACTURED BY HARGER LIGHTNING PROTECTION & GROUNDING EQUIPMENT, OR THERMOWELD AS MANUFACTURED BY CONTINENTAL INDUSTRIES OR APPROVED EQUAL. VERIFY PROPER SIZES, MOLDS, TYPES, AND REQUIREMENTS FOR THE RESPECTIVE APPLICATION WITH THE MANUFACTURER, AND INSTALL PER THEIR DIRECTIONS.
- 2. INTERIOR APPLICATIONS MIGHT NEED SMOKELESS EXOTHERMIC WELD WHERE ELECTRONIC EQUIPMENT IS LOCATED WITHIN THE RESPECTIVE WORK AREA.
- 3. ALL APPLICATIONS TO GALVANIZED STEEL OR PAINTED STEEL, SHALL REMOVE GALVANIZING AND/OR PAINT & CLEAN THE SURFACE TO EXPOSE BARE STEEL BEFORE MAKING EXOTHERMIC WELD CONNECTION.
- 4. THE EXOTHERMIC WELD DETAILS SHOWN ARE FOR A FEW COMMON APPLICATIONS. CONTACT THE RESPECTIVE EXOTHERMIC WELD MANUFACTURER FOR DETAILS AND INFORMATION ON OTHER APPLICATIONS.
- 5. FOR APPLICATIONS USING STAINLESS STEEL GROUND RODS CONTACT THE EXOTHERMIC WELD MANUFACTURER TO DETERMINE AND CONFIRM APPROPRIATE SIZE MOLDS AND MATERIALS FOR THE RESPECTIVE APPLICATION. PLEASE BE AWARE THAT AN EXOTHERMIC WELD KIT SUITABLE FOR A 3/4-INCH DIA x 10-FEET LONG COPPERCLAD-STEEL GROUND ROD WILL NOT BE SUITABLE FOR A 3/4-INCH DIA x 10-FEET LONG STAINLESS STEEL GROUND ROD. 3/4-INCH NOMINAL DIAMETER COPPERCLAD-STEEL GROUND RODS TYPICALLY HAVE A SMALLER ACTUAL DIAMETER THAN 3/4-INCH NOMINAL DIAMETER STAINLESS STEEL GROUND RODS AND THIS WILL AFFECT EXOTHERMIC WELD TYPE CONNECTIONS.



NOTES:

- 1. THE GROUND ROD COMPRESSION CONNECTOR DETAIL ABOVE APPLIES TO #2 AWG MINIMUM COPPER GROUNDING ELECTRODE CONDUCTORS.
- 2. THE EARTH GROUND RESISTANCE FOR EQUIPMENT SHALL BE ACCORDING TO THE APPLICABLE CODE REQUIREMENTS AND IN NO CASE MORE THAN 25 OHMS FOR AIRFIELD LIGHTING AND NO MORE THAN 10 OHMS FOR THE AIRPORT ELECTRICAL VAULT. TESTS SHALL BE MADE TO ESTABLISH THAT THE PROPER VALUE HAS BEEN OBTAINED. WHERE REQUIRED MAXIMUM GROUND RESISTANCE LEVELS CANNOT BE ACHIEVED AFTER TESTING NOTIFY THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT FOR FURTHER DIRECTIONS.
- BEFORE CRIMPING, BOTH CONNECTOR ELEMENTS CAN BE TURNED ON ROD DIAMETER 'D' TO ANY DESIRED POSITION.
- 4. CONFIRM CRIMPING TOOLS WITH RESPECTIVE CONNECTOR MANUFACTURER AND FOLLOW THEIR DIRECTIONS.

GROUND ROD COMPRESSION CONNECTOR DETAIL



Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed
Professional Service Corporation
#184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN



ATE LICE GNED: 7/29/2025 EXP

INSTALL MEDIUM
INTENSITY RUNWAY
LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

	NO.	DATE	DES	CRIPT	ION
	NO.	DATE	DES	DWN	REV
ISSUE: JULY 25, 2025					
į	PROJECT NO: 23A1038				

CAD FILE: E-506-DETL.DWG
DESIGN BY: KNL 05/19/2025

DESIGN BY: KNL 05/19/2025
DRAWN BY: AJC 05/19/2025
REVIEWED BY: KNL 6/24/2025


SHEET TITLE

DEVICE TO BE BONDED OR GROUND BUS BAR.

2 HOLE LONG BARREL COMPRESSION LUG TABLE (OR APPROVED EQUAL)				
WIRE SIZE	BURNDY CAT. NO.	THOMAS & BETTS CAT. NO.	PENN-UNION CAT. NO.	HARGER CAT. NO.
#8 AWG STRANDED	YA8C-2TC38	256-30695-1157	BBLU-8D-2TC38	(CONTACT MFR)
#6 AWG SOLID	YA8C-2TC38 OR YGA6C-2TC38E2G1	(CONTACT MFR)	(CONTACT MFR)	(CONTACT MFR)
#6 AWG STRANDED	YA6C-2TC38	256-30695-1158	BBLU-6D-2TC38	GECLB62C
#4 AWG STRANDED	YA4C-2TC38	256-30695-1159	BBLU-4D-2TC38	GECLB42C
#2 AWG STRANDED	YA2C-2TC38	256-30695-1160	BBLU-2D-2TC38	GECLB22C
#2 AWG SOLID	YA3C-2TC38	256-30695-1160	BBLU-3D-2TC38	GECLB22CS
#1/0 AWG STRANDED	YA25-2TC38	256-30695-1162	BBLU-1/0D-2TC38	GECLB1/02C
#2/0 AWG STRANDED	YA26-2TC38	256-30695-1116	BBLU-2/0D-2TC38	GECLB2/02C
#3/0 AWG STRANDED	YA27-2TC38	54816BE	BBLU-3/0D-2TC38	(CONTACT MFR)
#4/0 AWG STRANDED	YA28-2TC38	256-30695-1117	BBLU-4/0D-2TC38	GECLB4/02C
250 KCMIL	YA29-2TC38	256-30695-1245	BBLU-025D-2TC38	GECLB2502C
350 KCMIL	YA31-2TC38	256-30695-1118	BBLU-035D-2TC38	(CONTACT MFR)
500 KCMIL	YA34-2TC38	256-30695-1119	BBLU-050D-2TC38	GECLB5002C
750 KCMIL	YA39-2TC38	256-30695-1222	BBLU-075D-2TC38	GECLB7502C

NOTES

- 1. IT IS IMPORTANT TO HAVE GOOD SECURE GROUND CONNECTIONS THAT WILL WITHSTAND WEATHER CONDITIONS AND MAINTAIN CONTINUITY TO GROUND. OFTEN WEATHER CONDITIONS CAN AFFECT GROUNDING CONNECTIONS THAT RESULT IN LOOSE CONNECTIONS AND UNSAFE CONDITIONS. A TWO-HOLE BOLTED CONNECTOR WILL TYPICALLY MAINTAIN A BETTER AND MORE SECURE CONNECTION THAN A ONE-HOLE BOLTED CONNECTOR. ONE HOLE BOLTED CONNECTORS HAVE BEEN OBSERVED ON PAST PROJECTS TO HAVE LOOSENED AND LOST CONTINUITY OVER A SHORT PERIOD OF A FEW MONTHS OR LESS WHERE SUBJECTED TO WEATHER AND TEMPERATURE FLUCTUATIONS AND THEREFORE WILL NOT BE PERMITTED ON THIS PROJECT.
- 2. SAFETY OF PERSONNEL IS THE PRIORITY. PROTECTION OF EQUIPMENT IS SECONDARY. PLEASE BE AWARE THAT GROUNDING DOES NOT GUARANTEE YOU WILL NOT RECEIVE A SHOCK, BE INJURED, OR KILLED FROM DEFECTIVE OR DAMAGED EQUIPMENT OR MATERIALS. PROPER GROUNDING WILL HOWEVER SIGNIFICANTLY REDUCE THE POSSIBILITY OF SHOCK, INJURY, OR DEATH. PLEASE FOCUS ON SAFETY OF PERSONNEL AT ALL TIMES
- 3. THE GROUND WIRE CONNECTIONS TO EQUIPMENT LOCATED ABOVE GRADE, SHALL BE WITH 2 HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE DEVICE WITH 3/8-INCH STAINLESS STEEL BOLTS, NUTS, AND WASHERS OR WITH THE RESPECTIVE EQUIPT MANUFACTURER'S LUG OR TERMINAL WHERE APPLICABLE. THIS ALSO APPLIES TO CONNECTIONS TO GROUND BUS BARS.
- 4. HIGH VOLTAGE CIRCUITS OVER 1000 VOLTS CODE UPDATE. PER 2023 NEC ARTICLE 250, PART X. "GROUNDING OF SYSTEMS AND CIRCUITS OF OVER 1000 VOLTS," 250.190 "GROUNDING OF EQUIPMENT", PART (C) (1) "GENERAL" IT NOTES "EQUIPMENT GROUNDING CONDUCTORS THAT ARE NOT AN INTEGRAL PART OF A CABLE ASSEMBLY SHALL NOT BE SMALLER THAN 6 AWG COPPER OR 4 AWG ALUMINUM OR COPPER-CLAD ALUMINUM". GROUND WIRE TO BE USED WITH 6.6 AMP OR 20 AMP SERIES CIRCUITS SHALL BE #6 AWG COPPER CONDUCTOR. THIS APPLIES TO EQUIPMENT GROUND WIRES RUN WITH OUTPUT WIRING FROM CONSTANT CURRENT REGULATORS, THE ASSOCIATED SERIES CIRCUIT CUTOUT DISCONNECTS AND THEIR ENCLOSURES, AND ASSOCIATED HIGH VOLTAGE RACEWAYS AND JUNCTION BOXES CONTAINING AIRFIELD LIGHTING SERIES CIRCUITS.
- 5. EACH CONNECTION SHALL BE COATED WITH A CORROSION PREVENTATIVE COMPOUND (SANCHEM INC. NO-OX-ID "A-SPECIAL", BURNDY PENETROX E, OR APPROVED EQUAL) BEFORE JOINING. ALL COPPER BUS BARS SHALL BE CLEANED PRIOR TO MAKING CONNECTIONS TO REMOVE SURFACE OXIDATION. CLEAN SURFACES, OF RESPECTIVE DEVICES TO BE BONDED, TO BARE METAL, PER NEC 250-12.



- DOUBLE HOLE LUG WASHER SUITABLE AND SIZED FOR THE APPLICATION FOR USE WITH 2-HOLE TONGUE COMPRESSION LUGS; HARGER PART NO. BLW6S, LAUNCH 3 DIRECT PART NO. L3-LUGWASH-EA, ADVANCE TOWER COMPONENTS, INC. PART NO. AT-GW381, BONDWASHER SKU: BW381SS1, OR APPROVED EQUAL.

GROUNDING TWO HOLE LUG FLAT WASHER DETAIL

TIGHTENING TORQUE TABLE			
BOLT DIAMETER	SILICONE BRONZE GALVANIZED OR STAINLESS STEEL		
	Ft-Lbs.	Inch-Lbs	
5/16-18	15	180	
3/18-16	20	240	
1/2-13	40	480	
5/8-11	55	660	
3/4-10	80	960	

TABLE ABOVE SHOWS THE RECOMMENDED TIGHTENING TORQUES FOR SILICON BRONZE, STAINLESS STEEL AND GALVANIZED STEEL HARDWARE. THIS TABLE REPRESENTS TORQUES PRESENTLY RECOMMENDED BY NEMA-CC1-1984 SPECIFICATION. FOR SPECIFIC EQUIPMENT CONFIRM TIGHTENING TORQUES WITH RESPECTIVE MANUFACTURERS.

TIGHTENING TORQUE TABLE



Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN



ATE LICI

LICENSE 1/2025 EXPIRES: 11/30/20

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD


	l I				
	NO.	DATE	DES	CRIPT	ION
	NO.	DATE	DES	DWN	REV
į	SSUE:	JULY 25	5, 2025	,	
i	PROJECT NO: 23A1038				

PROJECT NO: 23A1038
CAD FILE: E-510-DETL.DWG

DESIGN BY: KNL 05/19/2025 DRAWN BY: AJC 05/19/2025

DRAWN BY: AJC 05/19/2025 REVIEWED BY: KNL 6/24/2025


SHEET TITLE





NOTES

- 1. 2020/2023 NEC ARTICLE 250.64 "GROUNDING ELECTRODE CONDUCTOR INSTALLATION", PART (E) "RACEWAYS AND ENCLOSURES FOR GROUNDING ELECTRODE CONDUCTORS", PARAGRAPH 1 "GENERAL" NOTES THE FOLLOW: "FERROUS METAL RACEWAYS, ENCLOSURES, AND CABLE ARMOR FOR GROUNDING ELECTRODE CONDUCTORS SHALL BE ELECTRICALLY CONTINUOUS FROM THE POINT OF ATTACHMENT TO CABINETS OR EQUIPMENT TO THE GROUNDING ELECTRODE AND SHALL BE SECURELY FASTENED TO THE GROUND CLAMP OR FITTING. FERROUS METAL RACEWAYS, ENCLOSURES, AND CABLE ARMOR SHALL BE BONDED AT EACH END OF THE RACEWAY OR ENCLOSURE TO THE GROUNDING ELECTRODE OR GROUNDING ELECTRODE CONDUCTOR TO CREATE AN ELECTRICALLY PARALLEL PATH. NONFERROUS METAL RACEWAYS, ENCLOSURES, AND CABLE ARMOR SHALL NOT BE REQUIRED TO BE ELECTRICALLY CONTINUOUS."
- AVOID INSTALLING GROUNDING ELECTRODE CONDUCTORS IN FERROUS METAL CONDUIT UNLESS REQUIRED BY THE AUTHORITY
 HAVING JURISDICTION OR RESPECTIVE CODES IN FORCE. FOR EXAMPLE: THE CITY OF CHICAGO ELECTRICAL CODE HAS HISTORICALLY
 PROHIBITED THE USE OF PVC CONDUIT INSIDE BUILDINGS AND THEREFORE GROUNDING ELECTRODE CONDUCTORS ARE OFTEN
 REQUIRED TO BE IN METAL CONDUIT.
- B. IF LOCAL CODES DICTATE THAT INDIVIDUAL GROUNDING CONDUCTORS MUST BE RUN IN METAL CONDUIT OR RACEWAY, THEN THE CONDUIT OR RACEWAY MUST BE BONDED AT EACH END OF THE RUN WITH A BONDING JUMPER SIZED EQUAL TO THE INDIVIDUAL GROUNDING CONDUCTOR OR AS REQUIRED BY 2023 NEC 250-102 AND/OR 2023 NEC 250.64(E). NOTE THIS DOES NOT APPLY TO AC EQUIPMENT GROUNDING CONDUCTORS RUN WITH AC CIRCUITS. CONFIRM REQUIREMENTS WITH AUTHORITY HAVING JURISDICTION.



GROUNDING ELECTRODE CONDUCTOR INSTALLED IN FERROUS METAL CONDUIT



- 1. EFFECTIVE WITH 2020 NEC ARTICLE 250.64 "GROUNDING ELECTRODE CONDUCTOR INSTALLATION", WHERE A GROUNDING ELECTRODE CONDUCTOR #6 AWG OR LARGER IS EXPOSED TO PHYSICAL DAMAGE IT SHALL BE PROTECTED IN RIGID METAL CONDUIT (RMC), INTERMEDIATE METAL CONDUIT (IMC), SCHEDULE 80 RIGID POLYVINYL CHLORIDE CONDUIT (PVC), REINFORCED THERMOSETTING RESIN CONDUIT TYPE XW (RTRC-XW), ELECTRICAL METALLIC TUBING (EMT), OR CABLE ARMOR. SCHED 40 PVC CONDUIT IS NO LONGER ADEQUATE. AVOID METAL CONDUIT UNLESS REQUIRED BY THE AUTHORITY HAVING JURISDICTION. SEE DETAILS FOR ADDITIONAL BONDING REQUIREMENTS WHERE A GROUNDING ELECTRODE CONDUCTOR IS INSTALLED IN METAL CONDUIT.
- 2. NOTE THAT INDIVIDUAL GROUNDING ELECTRODE CONDUCTORS SHALL NOT BE INSTALLED IN METAL CONDUIT UNLESS REQUIRED BY THE AUTHORITY HAVING JURISDICTION. INSTALL GROUNDING ELECTRODE CONDUCTORS IN SCHED 80 PVC CONDUIT AS REQUIRED IN FOUNDATIONS, FOR PROTECTION, WHERE ENTERING ENCLOSURES, ETC. WHERE PLASTIC CONDUIT IS USED FOR INDIVIDUAL GROUND WIRES, DO NOT COMPLETELY ENCIRCLE THE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. WHERE METAL CLAMPS ARE INSTALLED USE NYLON BOLTS, NUTS, WASHERS, & SPACERS TO INTERRUPT A COMPLETE METALLIC PATH FROM ENCIRCLING THE CONDUIT. THIS IS REQUIRED TO AVOID GIRDLING OF GROUND CONDUCTORS. GIRDLING OF A GROUND CONDUCTOR IS THE RESULT OF PLACING THE CONDUCTOR IN A RING OF MAGNETIC MATERIAL. THIS RING COULD BE A METALLIC CONDUIT, U-BOLT OR STRUT SUPPORT PIPE CLAMP, OR OTHER SUPPORT HARDWARE. THE RESULT OF GIRDLING GROUND CONDUCTORS SIGNIFICANTLY INCREASES THE INDUCTIVE IMPEDANCE OF THE GROUND CONDUCTOR. INDUCTIVE AND CAPACITIVE IMPEDANCE IS A TYPE OF RESISTANCE THAT OPPOSES THE FLOW OF ALTERNATING CURRENT. ANY INCREASES IN THE IMPEDANCE OF A GROUND CONDUCTOR REDUCES ITS ABILITY TO EFFECTIVELY MITIGATE RADIO FREQUENCY NOISE IN THE GROUND SYSTEM. THE CONDITION WHERE A GROUND CONDUCTOR IS GIRDLED DURING A LIGHTNING STRIKE RESULTS IN PHENOMENA KNOWN AS SURGE IMPEDANCE LOADING. SURGE IMPEDANCE LOADING. SURGE IMPEDANCE LOADING IS A RESULT OF VOLTAGE AND CURRENT REACHING 500,000 VOLTS AND 10,000 AMPS FOR A SHORT DURATION. GIRDLING FURTHER INCREASES THE IMPEDANCE AT LIGHTNING FREQUENCIES OF 100 KILOHERTZ TO 100 MEGAHERTZ. AT THESE POWER AND FREQUENCY LEVELS ANY INCREASE IN THE IMPEDANCE OF THE GROUND CONDUCTOR MUST BE CONTROLLED. DURING LIGHTNING DISCHARGE CONDITIONS A LOW INDUCTIVE IMPEDANCE PATH. IS MORE IMPORTANT THAN A LOW DC RESISTANCE PATH.
- DIRECT CONNECTIONS BETWEEN DEVICE OR EQUIPMENT TO BE BONDED AND THE GROUNDING ELECTRODE SYSTEM SHALL BE PROVIDED. AVOID SPLICING OF GROUNDING ELECTRODE CONDUCTORS.

HANSON Engineering | Planning | Allied Services


Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839



DATE LIC

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIPTION
DES DWN REV


ISSUE: JULY 25, 2025
PROJECT NO: 2341038

PROJECT NO: 23A1038
CAD FILE: E-511-DETL.DWG

DESIGN BY: KNL 05/19/2025 DRAWN BY: AJC 05/19/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE




PIPE GROUNDING CLAMP TABLE (OR APPROVED EQUAL)				
HUBBELL CAT. NO.	PIPE SIZE			
GAR3902TC	GAR3902TC	1/2" - 1"		
GAR3903TC	GAR3903TC	1 1/4" - 2"		
GAR3904TC	GAR3904TC	2 1/2" - 3 1/2"		
GAR3905TC	GAR3905TC	4" - 5"		
GAR3906TC	GAR3906TC	6"		
GAR3907TC	GAR3907TC	8"		
GAR3908TC	GAR3908TC	10"		
GAR3909TC	GAR3909TC	12"		


NOTES

- METAL WATER PIPE TO BE USED AS A GROUNDING ELECTRODE SHALL MEET THE REQUIREMENTS OF 2023 NEC 250.52 "GROUNDING ELECTRODES", (A)(1) "METAL UNDERGROUND WATER PIPE" WHICH NOTES THE FOLLOWING:

 A METAL UNDERGROUND WATER PIPE IN DIRECT CONTACT WITH THE EARTH FOR 3.0 m (10 ft) OR MORE (INCLUDING ANY METAL WELL CASING BONDED TO THE PIPE) AND ELECTRICALLY CONTINUOUS (OR MADE ELECTRICALLY CONTINUOUS BY BONDING AROUND INSULATING JOINTS OR INSULATING PIPE) TO THE POINTS OF CONNECTION OF THE GROUNDING ELECTRODE CONDUCTOR AND THE BONDING CONDUCTOR(S) OR JUMPER(S), IF INSTALLED.
- 2. PROVIDE PIPE GROUNDING CLAMPS AT BOTH SIDES OF WATER METER WITH #2 AWG (MINIMUM) COPPER BONDING JUMPER ACROSS THE METER.
- 3. FOR DAMP OR WET LOCATIONS USE PIPE CLAMPS WITH ALL BRONZE HARDWARE.

WATER SERVICE PIPE GROUNDING DETAIL





PIPE GROUNDING CLAMP TABLE (OR APPROVED EQUAL)		
BURNDY CAT. NO.	THOMAS & BETTS CAT. NO.	PIPE SIZE
GAR3902-BU	3902BU	1/2" - 1"
GAR3903-BU	3903BU	1 1/4" - 2"
GAR3904-BU	3904BU	2 1/2" - 3 1/2"
GAR3905-BU	3905BU	4" - 5"
GAR3906-BU	3906BU	6"

NOTES

- EACH PIPE GROUNDING CLAMP SHALL HAVE BRONZE HARDWARE, BE CORROSION RESISTANT, SUITABLE FOR DIRECT BURIAL IN EARTH OR CONCRETE, & UL 467 LISTED.
- 2. FOR APPLICATIONS SUBJECT TO ADDITIONAL CORROSION, PROVIDE PIPE GROUNDING CLAMPS WITH TINNED COATED BRONZE HARDWARE
- 3. HARGER CPC AND APC SERIES PIPE GROUNDING CLAMPS PROPERLY SIZED FOR THE RESPECTIVE PIPE AND GROUND WIRE ARE ALSO ACCEPTABLE.
- PENN-UNION TYPE "GPL" SERIES PIPE GROUNDING CLAMPS PROPERLY SIZED FOR THE RESPECTIVE PIPE AND GROUND WIRE ARE ALSO ACCEPTABLE.

PIPE/CONDUIT GROUNDING CLAMP DETAIL



Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN



DATE LICENSE SIGNED: 7/29/2025 EXPIRES: 11/30/20

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DES	CRIPT	ION	
INO.	DATE	DES	DWN	REV	
ISSUE: JULY 25, 2025					
PROJECT NO: 23A1038					

CAD FILE: E-512-DETLDWG
DESIGN BY: KNL 05/19/2025

DESIGN BY: KNL 05/19/2025
DRAWN BY: AJC 05/19/2025
REVIEWED BY: KNL 6/24/2025

SHEET TITLE

Professional Service Corporation #184-001084

Illinois Licensed

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN




DATE

9/2025 EXPIRES: 11/3

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD




PROJECT NO: 23A1038
CAD FILE: E-507-DETL.DWG

DESIGN BY: KNL 3/31/2025 DRAWN BY: CWS 4/4/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

GROUND RESISTANCE TESTING DETAILS




NOTES

- 1. CONTRACTOR SHALL TEST AND RECORD THE RESISTANCE FOR EACH MADE ELECTRODE GROUND ROD/GROUND FIELD/GROUND RING WITH AN INSTRUMENT SPECIFICALLY DESIGNED FOR TESTING GROUNDING ELECTRODE SYSTEMS. IF GROUND RESISTANCE EXCEEDS 25 OHMS, CONTACT THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT FOR FURTHER DIRECTIONS. COPIES OF GROUND ROD TEST RESULTS SHALL BE FURNISHED TO THE RESIDENT ENGINEER/RESIDENT TECHNICIAN, AND THE PROJECT ENGINEER OF RECORD.
- 2. FOR EACH AIRFIELD LIGHT FIXTURE, TAXI GUIDANCE SIGN, SPLICE CAN AND NAVAID THE CONTRACTOR SHALL TEST THE MADE ELECTRODE GROUND SYSTEM WITH AN INSTRUMENT SPECIFICALLY DESIGNED FOR TESTING GROUND SYSTEMS. TEST RESULTS SHALL BE RECORDED FOR EACH AIRFIELD LIGHT FIXTURE, TAXI GUIDANCE SIGN, AND NAVAIDS INSTALLATION. IF GROUND RESISTANCE EXCEEDS 25 OHMS, CONTACT THE PROJECT ENGINEER OF RECORD FOR FURTHER DIRECTIONS. ALSO REFER TO EOR-062-047643 FOR ADDITIONAL INFORMATION ON GROUNDING REQUIREMENTS WHERE APPLICABLE. COPIES OF THE GROUND SYSTEM TEST RESULTS SHALL BE FURNISHED TO THE RESIDENT ENGINEER / RESIDENT TECHNICIAN, AND THE PROJECT ENGINEER OF RECORD.
- 3. GROUND RESISTANCE TEST SHALL BE CONDUCTED IN ACCORDANCE WITH THE RESPECTIVE GROUND ELECTRODE RESISTANCE TESTING EQUIPMENT MANUFACTURER'S INSTRUCTIONS.
- 4. RECORD SITE CONDITIONS DURING TESTS.
- "FALL OF POTENTIAL" TYPE GROUND ELECTRODE RESISTANCE TESTER IS RECOMMENDED FOR TESTING INDIVIDUAL STAND ALONE GROUND RODS.

- FURNISH AND INSTALL GROUND RODS AS DETAILED HEREIN. GROUND RODS FOR AIRFIELD LIGHTING LIGHT BASE GROUNDS FOR (RUNWAY LIGHTING, TAXIWAY LIGHTING, TAXI GUIDANCE SIGNS, & DISTANCE REMAINING SIGNS) SHALL BE MINIMUM 3/4-IN. DIAMETER BY 10-FT LONG, UL-LISTED COPPER CLAD WITH 10-MIL MINIMUM COPPER COATING. GROUND RODS FOR COUNTERPOISE/LIGHTNING PROTECTION SYSTEM ON THE AIRFIELD SHALL BE MINIMUM 3/4-IN. DIAMETER BY 10-FT. LONG UL-LISTED COPPER CLAD WITH 10-MIL MINIMUM COPPER COATING, GROUND RODS SHALL BE SPACED OR AS DETAILED ON THE RESPECTIVE PLANS, AND IN NO CASE SPACED LESS THAN ONE ROD LENGTH APART. ALL CONNECTIONS TO GROUND RODS AND THE GROUND RING SHALL BE MADE WITH EXOTHERMIC WELD TYPE CONNECTORS, CADWELD BY PENTAIR ERICO PRODUCTS, THERMOWELD BY CONTINENTAL INDUSTRIES, ULTRAWELD BY HARGER, OR APPROVED EQUAL. EXOTHERMIC WELD CONNECTIONS SHALL BE INSTALLED IN CONFORMANCE WITH THE RESPECTIVE MANUFACTURER'S DIRECTIONS USING MOLDS AS REQUIRED FOR EACH RESPECTIVE APPLICATION. BOLTED CONNECTIONS WILL NOT BE PERMITTED AT GROUND RODS OR AT BURIED GROUNDING ELECTRODE CONDUCTORS
- CONTRACTOR SHALL TEST EACH MADE ELECTRODE GROUND ROD/GROUND FIELD/GROUND RING WITH AN INSTRUMENT SPECIFICALLY DESIGNED FOR TESTING GROUND FIELD SYSTEMS. IF GROUND RESISTANCE EXCEEDS 25 OHMS, CONTACT THE PROJECT ENGINEER OF RECORD FOR FURTHER DIRECTIONS. ALSO REFER TO EOR-47643 FOR ADDITIONAL INFORMATION ON GROUNDING REQUIREMENTS, WHERE APPLICABLE. COPIES OF GROUND ROD TEST RESULTS SHALL BE FURNISHED TO THE RESIDENT PROJECT REPRESENTATIVE. AND THE PROJECT ENGINEER OF RECORD.
- ALL PRODUCTS ASSOCIATED WITH THE GROUNDING SYSTEM SHALL BE UL-LISTED AND
- ALL BOLTED OR MECHANICAL CONNECTIONS SHALL BE COATED WITH A CORROSION PREVENTIVE COMPOUND BEFORE JOINING, SANCHEM INC. "NO-OX-ID "A-SPECIAL" COMPOUND, BURNDY PENETROX E, OR APPROVED EQUAL
- METALLIC SURFACES TO BE JOINED SHALL BE PREPARED BY THE REMOVAL OF ALL NON-CONDUCTIVE MATERIAL, PER 2023 NATIONAL ELECTRICAL CODE ARTICLE 250-12. ALL COPPER BUS BARS MUST BE CLEANED PRIOR TO MAKING CONNECTIONS TO REMOVE SURFACE OXIDATION.
- METALLIC RACEWAY FITTINGS SHALL BE MADE UP TIGHT TO PROVIDE A PERMANENT LOW IMPEDANCE PATH FOR ALL CIRCUITS. METAL CONDUIT TERMINATIONS IN ENCLOSURES SHALL BE BONDED TO THE ENCLOSURE WITH UL-LISTED FITTINGS SUITABLE FOR GROUNDING. PROVIDE GROUNDING BUSHINGS WITH BONDING JUMPERS FOR ALL METAL CONDUITS ENTERING SERVICE EQUIPMENT (METER BASE, CT CABINET, MAIN SERVICE BREAKER ENCLOSURE, ETC.). PROVIDE GROUNDING BUSHINGS WITH BONDING JUMPERS FOR ALL METAL CONDUITS ENTERING AN ENCLOSURE THROUGH CONCENTRIC OR ECCENTRIC KNOCKOUTS THAT ARE PUNCHED OR OTHERWISE FORMED SO AS TO IMPAIR THE ELECTRICAL CONNECTION TO GROUND. STANDARD LOCKNUTS OR BUSHINGS SHALL NOT BE THE SOLE MEANS FOR BONDING WHERE A CONDUIT ENTERS AN ENCLOSURE THROUGH A CONCENTRIC OR ECCENTRIC KNOCKOUT
- ALL CONNECTIONS, LOCATED ABOVE GRADE, BETWEEN THE DIFFERENT TYPES OF GROUNDING CONDUCTORS SHALL BE MADE USING UL-LISTED DOUBLE COMPRESSION CRIMP TYPE CONNECTORS OR UL-LISTED BOLTED GROUND CONNECTORS. FOR GROUND CONNECTIONS TO ENCLOSURES, CASES AND FRAMES OF ELECTRICAL EQUIPMENT NOT SUPPLIED WITH GROUND LUGS THE CONTRACTOR SHALL DRILL REQUIRED HOLES FOR MOUNTING A BOLTED GROUND CONNECTOR. ALL BOLTED GROUND CONNECTORS SHALL BE BURNDY, THOMAS AND BETTS, OR EQUAL. TIGHTEN CONNECTIONS TO COMPLY WITH TIGHTENING TORQUES IN UL STANDARD 486A TO ASSURE PERMANENT AND EFFECTIVE GROUNDING
- ALL METAL FOLIPMENT ENCLOSURES CONDUITS CABINETS BOXES RECEPTACLES MOTORS, ETC. SHALL BE BONDED TO THE RESPECTIVE GROUNDING SYSTEM.
- PROVIDE ALL BOXES FOR PROPOSED OUTLETS, SWITCHES, CIRCUIT BREAKERS, ETC. WITH GROUNDING SCREWS. PROVIDE ALL PANELBOARD, SWITCHGEAR, ETC., ENCLOSURES WITH GROUNDING BARS WITH INDIVIDUAL SCREWS, LUGS, CLAMPS, ETC., FOR EACH OF THE GROUNDING CONDUCTORS THAT ENTER THEIR RESPECTIVE
- EACH NEW FEEDER CIRCUIT AND/OR BRANCH CIRCUIT SHALL INCLUDE AN EQUIPMENT GROUND WIRE. METAL RACEWAY OR CONDUIT SHALL NOT MEET THIS REQUIREMENT. THE EQUIPMENT GROUND WIRE FROM EQUIPMENT SHALL NOT BE SMALLER THAN ALLOWED BY 2023 NEC TABLE 250-122 "MINIMUM SIZE CONDUCTORS OR GROUNDING RACEWAY AND EQUIPMENT." WHEN CONDUCTORS ARE ADJUSTED IN SIZE TO COMPENSATE FOR VOLTAGE DROP, EQUIPMENT-GROUNDING CONDUCTORS SHALL BE ADJUSTED PROPORTIONATELY ACCORDING TO CIRCULAR MIL AREA. ALL EQUIPMENT GROUND WIRES SHALL BE COPPER. EITHER BARE OR INSULATED GREEN IN COLOR. WHERE THE EQUIPMENT GROUNDING CONDUCTORS ARE INSULATED, THEY SHALL BE IDENTIFIED BY THE COLOR GREEN, AND SHALL BE THE SAME INSULATION TYPE AS THE

- ALL EXTERIOR METAL CONDUIT, WHERE NOT ELECTRICALLY CONTINUOUS BECAUSE OF MANHOLES, HANDHOLES, NON-METALLIC JUNCTION BOXES, ETC., SHALL BE BONDED TO ALL OTHER METAL CONDUIT IN THE RESPECTIVE DUCT RUN, AND AT EACH END, WITH A COPPER-BONDING JUMPER SIZED IN CONFORMANCE WITH 2023 NEC 250-102. WHERE METAL CONDUITS TERMINATE IN AN ENCLOSURE (SUCH AS A MOTOR CONTROL CENTER, SWITCHBOARD, ETC) WHERE THERE IS NOT ELECTRICAL CONTINUITY WITH THE CONDUIT AND THE RESPECTIVE ENCLOSURE, PROVIDE A BONDING JUMPER FROM THE RESPECTIVE ENCLOSURE GROUND BUS TO THE CONDUIT SIZED PER 2023 NEC 250-102.
- 12. IT IS THE INTENT OF THIS SPECIFICATION THAT ALL MOTOR FRAMES, PUMP BASES ELECTRICAL EQUIPMENT ENCLOSURES, PANEL HOUSINGS, CONDUITS, BOXES, ETC. HAVE A CONTINUOUS COPPER WIRE GROUND CONNECTION AND SHALL BE POSITIVELY BONDED TO THE RESPECTIVE GROUNDING SYSTEM. CONDUIT CONNECTORS WILL NOT BE CONSIDERED AS ADEQUATE GROUNDING.
- PROVIDE A POSITIVE GROUND BOND FOR ALL OUTLET BOXES, ELECTRICAL EQUIPMENT ENCLOSURES, GROUNDING RECEPTACLES, TOGGLE SWITCHES, ETC. INSTALL A GROUNDING CONDUCTOR IN ALL WIRE AND CABLE RACEWAYS. GROUND CONDUCTOR TO HAVE 600-VOLT INSULATION AND BE IDENTIFIED BY A CONTINUOUS GREEN COLOR COATING. THEY SHALL BE USED SOLELY FOR GROUNDING PURPOSES AND BE ENTIRELY SEPARATE FROM WHITE GROUNDED NEUTRAL CONDUCTOR. EXCEPT AT SUPPLY SIDE OF SERVICE DISCONNECTING MEANS, WHERE GROUNDING AND NEUTRAL SYSTEMS ARE TO BE CONNECTED TO SERVICE GROUND.
- EACH AND ALL GROUNDED CASED AND METAL PARTS ASSOCIATED WITH ELECTRICAL EQUIPMENT SHALL BE TESTED FOR CONTINUITY OF CONNECTION WITH GROUND BUS SYSTEM BY CONTRACTOR IN PRESENCE OF OWNER'S REPRESENTATIVE
- ALL CONNECTIONS BETWEEN THE DIFFERENT TYPES OF GROUNDING CONDUCTORS ABOVE GRADE SHALL BE MADE USING BOLTED GROUND CONNECTORS. GROUND LUGS SHALL BE PROVIDED IN ALL ENCLOSURES AND WIRING TERMINATION JUNCTION BOXES. EQUIPMENT GROUNDS AND GROUNDING CONDUCTOR SHALL BE CONNECTED TO THESE GROUND LUGS. FOR GROUND CONNECTIONS TO ENCLOSURES, CASES AND FRAMES OF ELECTRICAL EQUIPMENT NOT SUPPLIED WITH GROUND LUGS THE CONTRACTOR SHALL DRILL REQUIRED HOLES FOR MOUNTING A BOLTED GROUND CONNECTOR. ALL BOLTED GROUND CONNECTORS SHALL BE BURNDY, OR EQUAL.
- BOND ALL NONCURRENT-CARRYING PARTS OF METAL EQUIPMENT TO GROUND SYSTEM.
- BUILDING STRUCTURAL STEEL SYSTEM SHALL BE BONDED TO ELECTRICAL GROUND
- INSTALL GROUNDING ELECTRODE CONDUCTORS, LIGHTNING PROTECTION DOWN CONDUCTORS AND SEPARATE GROUND CONDUCTORS IN SCHEDULE 80 PVC CONDUIT OR EXPOSED WHERE ACCEPTABLE TO LOCAL CODES. WHERE GROUNDING ELECTRODE CONDUCTORS, LIGHTNING PROTECTION DOWN CONDUCTORS OR INDIVIDUAL GROUND CONDUCTORS ARE RUN IN PVC CONDUIT, $\underline{\text{DO NOT}}$ COMPLETELY ENCIRCLE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. USE NON-METALLIC REINFORCED FIBERGLASS STRUT SUPPORT. WHERE METAL CONDUIT CLAMPS ARE INSTALLED, USE NYLON BOLTS, NUTS, WASHERS AND SPACERS TO INTERRUPT A COMPLETE METALLIC PATH FROM ENCIRCLING THE CONDUIT. THIS IS REQUIRED TO AVOID GIRDLING OF GROUND CONDUCTORS.
- IF LOCAL CODES DICTATE THAT INDIVIDUAL GROUNDING CONDUCTORS MUST BE RUN IN METAL CONDUIT OR RACEWAY, THEN THE CONDUIT OR RACEWAY MUST BE BONDED AT EACH END OF THE RUN WITH A BONDING JUMPER SIZED EQUAL TO THE INDIVIDUAL GROUNDING CONDUCTOR OR AS REQUIRED BY 2023 NEC 250-102 AND/OR 2023 NEC 250.64(E). NOTE THIS DOES NOT APPLY TO AC EQUIPMENT GROUNDING CONDUCTORS RUN WITH AC CIRCUITS. CONFIRM REQUIREMENTS WITH AUTHORITY HAVING
- GROUNDING WORK AFFECTING OPERATIONS AT A FACILITY SHALL BE COORDINATED WITH THE OWNER'S DESIGNATED REPRESENTATIVE(S) AND TO MINIMIZE DOWNTIME TO EXISTING SYSTEMS. THE RESPECTIVE PERSONNEL SHALL COORDINATE WORK AND ANY POWER OUTAGES WITH THE OWNER'S DESIGNATED REPRESENTATIVE(S). ANY SHUTDOWN OF EXISTING SYSTEMS SHALL BE SCHEDULED WITH AND APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO SHUT DOWN. ALL POWER SYSTEMS (AC OR DC) SHALL HAVE PROVISIONS TO LOCKOUT AND TAGOUT ANY CIRCUIT TO HELP ENSURE THE CIRCUIT IS SAFE TO WORK ON FOR PROTECTION OF PERSONNEL. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY AND HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT). WHERE A FACILITY DOES NOT HAVE LOCKOUT/TAGOUT KITS THE RESPECTIVE PERSONNEL SHALL PROVIDE ADEQUATE QUANTITIES OF LOCKOUT/TAGOUT KITS SUITABLE FOR USE WITH THE RESPECTIVE EQUIPMENT. WHERE EXISTING ELECTRICAL EQUIPMENT DOES NOT HAVE FEATURES FOR LOCKOUT/TAGOUT THE RESPECTIVE PERSONNEL WILL BE RESPONSIBLE FOR PROVIDING THE APPROPRIATE LOCKOUT/TAGOUT EQUIPMENT AND MEASURES TO COMPLY WITH OSHA LOCKOUT/TAGOUT REQUIREMENTS. ALL PADLOCKS FOR USE WITH LOCKOUT/TAGOUT PROCEDURES SHALL HAVE A DIFFERENT KEY PROVIDE LOCKOUT HASPS TO ACCOMMODATE MULTIPLE PADLOCKS WHERE MULTIPLE PEOPLE ARE WORKING ON THE SAME SYSTEM. INCLUDE LOCKOUT TAGS FOR EACH PIECE OF EQUIPMENT REQUIRING SERVICING AND SHUTDOWN. COMPLIANCE WITH LOCKOUT/TAGOUT PROCEDURES AND ALL OTHER SAFETY PROCEDURES AND REQUIREMENTS ARE THE RESPONSIBILITY OF THE RESPECTIVE PERSONNEL WORKING
- NEVER REMOVE, ALTER, OR ATTEMPT TO REPAIR CONDUCTORS OR CONDUIT SYSTEMS PROVIDING GROUNDING OR ELECTRICAL BONDING FOR ANY ELECTRICAL EQUIPMENT UNTIL ALL POWER IS REMOVED FROM EQUIPMENT. WARN ALL PERSONNEL OF THE UNGROUNDED CONDITION OF THE EQUIPMENT. DISPLAY APPROPRIATE WARNING SIGNS, SUCH AS DANGER TAGS, TO WARN PERSONNEL OF THE POSSIBLE HAZARDS.

- GROUNDING WORK AND MODIFICATIONS SHALL NOT BE PERFORMED DURING A THUNDERSTORM OR WHEN A THUNDERSTORM IS PREDICTED IN THE AREA.
- PER NFPA 70E STANDARD FOR ELECTRICAL SAFETY IN THE WORKPLACE IT DEFINES ELECTRICALLY SAFE WORK CONDITION AS "A STATE IN WHICH AN ELECTRICAL CONDUCTOR OR CIRCUIT PART HAS BEEN DISCONNECTED FROM ENERGIZED PARTS LOCKED/TAGGED IN ACCORDANCE WITH ESTABLISHED STANDARDS, TESTED TO VERIFY THE ABSENCE OF VOLTAGE, AND, IF NECESSARY, TEMPORARILY GROUNDED FOR PERSONNEL PROTECTION." PRIOR TO CONDUCTING TESTS OR WORKING ON EQUIPMENT, VERIFY EQUIPMENT ENCLOSURES AND FRAMES HAVE A GOOD AND SECURE GROUND CONNECTION. FAILURE TO PROPERLY GROUND THIS EQUIPMENT PRESENTS A DANGEROUS HAZARD FOR PERSONNEL WORKING ON THIS SYSTEM.
- WHERE A CONFLICT IS DETERMINED WITH RESPECT TO GROUNDING REQUIREMENTS PER MANUFACTURER INSTALLATION INSTRUCTIONS, NEC, AND/OR THE CONTRACT DOCUMENTS, CONTACT THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT FOR
- GROUND RODS SHALL BE PRODUCED FROM 100 PERCENT DOMESTIC STEEL TO COMPLY WITH THE AIRPORT IMPROVEMENT PROGRAM BUY AMERICAN PREFERENCES
 REQUIREMENT. THE BUY AMERICAN PREFERENCE REQUIREMENTS ESTABLISHED WITHIN 49 USC 50101 REQUIRE THAT ALL STEEL AND MANUFACTURED GOODS USED ON AIP PROJECTS MUST BE PRODUCED IN THE UNITED STATES



NOTES

- THE GROUNDING SYSTEM HAS BEEN DESIGNED BASED ON EXISTING CONDITIONS AT THE AIRPORT. GROUND RODS SHALL BE AS SPECIFIED ON THE PLANS AND
- THE RESISTANCE TO GROUND OF THE AIRFIELD LIGHTING GROUNDING SYSTEM SHALL NOT EXCEED 25 OHMS. WHERE TESTING RESULTS INDICATE 25 OHMS CANNOT BE ACHIEVED, CONTACT THE ENGINEER OF RECORD, KEVIN LIGHTFOOT, FOR FURTHER DIRECTIONS
- COST OF GROUND RODS IS INCIDENTAL TO THE ASSOCIATED ITEMS REQUIRING GROUNDING UNLESS OTHERWISE SPECIFIED.
- GROUND RODS SHALL BE SPACED AS DETAILED ON THE PLANS AND SHALL NOT BE SPACED LESS THAN ONE ROD LENGTH APART.
- TOP OF GROUND RODS SHALL BE 12" MINIMUM BELOW GRADE UNLESS DETAILED
- GROUND RODS FOR SPLICE CANS AND AIRFIELD LIGHTING SHALL BE A MINIMUM 3/4-INCH DIAMETER BY 10-FT LONG UL LISTED COPPER CLAD.

NOT TO SCALE

BID DOCUMENTS



Offices Nationwide www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839

COVERING ELECTRICAL DESIGN LIGHTFOOT 062-047643

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

ı		1			
l					
Ī					
l					
Ī					
l					
Ī					
L					
Ī					
l					
ľ	NO.	DATE	DES	CRIPT	101
l	NO.	DATE	DES	DWN	RE
į	ISSUE: JULY 25, 2025				
Ē	PROJECT NO: 23A1038				

CAD FILE: E-004-NOTES.DWG

DESIGN BY: KNI 3/31/2025 DRAWN BY: CWS 4/4/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

GROUNDING NOTES

ELEC1	FRICAL LEGEND - ONE-LINE DIAGRAM
—	CABLE TERMINATOR/LUG
***	TRANSFORMER
_\	DISCONNECT SWITCH
-	FUSIBLE DISCONNECT SWITCH
	CIRCUIT BREAKER
\ \-\	THERMAL MAGNETIC CIRCUIT BREAKER
	FUSE
	TRANSIENT VOLTAGE SURGE SUPPRESSOR OR SURGE PROTECTOR DEVICE
=	GROUND - GROUND ROD, GROUNDING ELECTRODE, OR AT EARTH POTENTIAL
¤	INDICATING LIGHT
M	MOTOR
#	LOAD, MOTOR, # = HORSEPOWER
0	ELECTRIC UTILITY METER BASE
0	JUNCTION BOX WITH SPLICE
xxx	EQUIPMENT, XXX = DEVICE DESCRIPTION
GND	GROUND BUS OR TERMINAL
S/N	NEUTRAL BUS
#	PANELBOARD WITH MAIN LUGS
	PANELBOARD WITH MAIN BREAKER
₩□≫ #	FUSE PANEL WITH MAIN FUSE PULLOUT
+	DUPLEX RECEPTACLE 120V SINGLE PHASE GROUNDING TYPE
	CONTROL STATION
N EM	TRANSFER SWITCH
G	ENGINE GENERATOR SET

	ECTRICAL LEGEND - SCHEMATIC		
⊣⊢	NORMALLY OPEN (N.O.) CONTACT		
	NORMALLY CLOSED (N.C.) CONTACT		
S*	STARTER COIL, * = STARTER NUMBER		
-}/-	OVERLOAD RELAY CONTACT		
©R*	CONTROL RELAY, * = CONTROL RELAY NUMBER		
R*	RELAY, * = RELAY NUMBER		
%	TOGGLE SWITCH / 2 POSITION SWITCH		
OFF AUTO	2-POSITION SELECTOR SWITCH		
HAND TAUTO NOO OOO OOO OOO	3-POSITION SELECTOR SWITCH (H-O-A SHOWN)		
¹ -7°	N.O. THERMAL SWITCH		
Ţ	N.C. THERMAL SWITCH		
<u></u>	2 POLE DISCONNECT SWITCH		
	3 POLE DISCONNECT SWITCH		
*	PHOTOCELL		
	TERMINAL BLOCK, * = TERMINAL NUMBER		
	DEVICE TERMINAL, * = DEVICE TERMINAL NUMBER		
	INTERNAL PANEL WIRING		
	FIELD WIRING		
	FUSE		
GND	GROUND BUS OR TERMINAL		
[S/N]	NEUTRAL BUS		
- <u>+</u>	GROUND, GROUND ROD, GROUND BUS		
0 0	INDUSTRIAL CONTROL RELAY OR LIGHTING CONTACTOR		
 	TYPE S1 CUTOUT HANDLE REMOVED (MFRD BY CROUSE-HINDS, MANAIRCO, AND OTHERS)		
 	TYPE S1 CUTOUT HANDLE INSERTED (MFRD BY CROUSE-HINDS, MANAIRCO, AND OTHERS)		
3 3	TYPE SCO CUTOUT (MFRD BY ADB)		
**	TYPE ALSC AIRFIELD LIGHTING SAFETY CUTOUT (MFRD BY ADB)		
* *			

L-830 SERIES ISOLATION TRANSFORMER

	ELECTRICAL ABBREVIATIONS
A.F.F.	ABOVE FINISHED FLOOR
A, AMP	AMPERES
ATS	AUTOMATIC TRANSFER SWITCH
AWG	AMERICAN WIRE GAUGE
BKR	BREAKER
С	CONDUIT
СВ	CIRCUIT BREAKER
CKT	CIRCUIT
CR	CONTROL RELAY
CU	COPPER
DPDT	DOUBLE POLE DOUBLE THROW
DPST	DOUBLE POLE SINGLE THROW
EM	EMERGENCY
EMT	ELECTRICAL METALLIC TUBING
ENCL	ENCLOSURE
EOR	ENGINEER OF RECORD
EP	EXPLOSION PROOF
ES	EMERGENCY STOP
ETL	INTERTEK - ELECTRICAL TESTING LABS
ETM	ELAPSE TIME METER
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GFI	GROUND FAULT INTERRUPTER
GND	GROUND
GRSC	GALVANIZED RIGID STEEL CONDUIT
HOA	HAND OFF AUTOMATIC
HP	HORSEPOWER
J	JUNCTION BOX
KVA	KILOVOLT AMPERE(S)
KNL	KEVIN NEIL LIGHTFOOT
KW	KILOWATTS
LC	LIGHTING CONTACTOR
LED	LIGHT EMITTING DIODE
LTFMC	LIQUID TIGHT FLEXIBLE METAL CONDUIT (UL LISTED)
LTG	LIGHTING
LHTNG	LIGHTING
LP	LIGHTING PANEL
MAX	MAXIMUM
MCB	MAIN CIRCUIT BREAKER
МСМ	THOUSAND CIRCULAR MIL
MDP	MAIN DISTRIBUTION PANEL
MFR	MANUFACTURER
MH	METAL HALIDE
MIN	MINIMUM
MLO	MAIN LUGS ONLY
NEC	NATIONAL ELECTRICAL CODE (NFPA 70)
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OHE	OVERHEAD ELECTRIC
OHL	

ELECT	FRICAL ABBREVIATIONS (CONTINUED)
РВ	PULL BOX
PC	PHOTO CELL
PDB	POWER DISTRIBUTION BLOCK
PNL	PANEL
RCPT	RECEPTACLE
R	RELAY
S	STARTER
SPD	SURGE PROTECTION DEVICE
SPST	SINGLE POLE SINGLE THROW
TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSOR
TYP	TYPICAL
UG	UNDERGROUND
UGE	UNDERGROUND ELECTRIC
UL	UNDERWRITER'S LABORATORIES
V	VOLTS
W/	WITH
W/O	WITHOUT
WP	WEATHER PROOF
XFER	TRANSFER
XFMR	TRANSFORMER
-	DASH, HYPHEN, OR MINUS SIGN
xxx	LETTERS AND / OR NUMBERS (TO BE DETERMINED)
AIRPOR	F EQUIPMENT/FACILITY ABBREVIATIONS
ASOS	AUTOMATED SURFACE OBSERVING SYSTEM
ATCT	AIR TRAFFIC CONTROL TOWER

AIRPOR ³	T EQUIPMENT/FACILITY ABBREVIATIONS
ASOS	AUTOMATED SURFACE OBSERVING SYSTEM
ATCT	AIR TRAFFIC CONTROL TOWER
AWOS	AUTOMATED WEATHER OBSERVING SYSTEM
CCR	CONSTANT CURRENT REGULATOR
DME	DISTANCE MEASURING EQUIPMENT
FAR	FEDERAL AVIATION REGULATION
GS	GLIDE SLOPE FACILITY
HIRL	HIGH INTENSITY RUNWAY LIGHT
ILS	INSTRUMENT LANDING SYSTEM
IM	INNER MARKER
LIR	LOW IMPACT-RESISTANT
LOC	LOCALIZER FACILITY
MALS	MEDIUM INTENSITY APPROACH LIGHTING SYSTEM
MALSR	MEDIUM INTENSITY APPROACH LIGHTING SYSTEM WITH RUNWAY ALIGNMENT INDICATING LIGHTS
MIRL	MEDIUM INTENSITY RUNWAY LIGHT
MITL	MEDIUM INTENSITY TAXIWAY LIGHT
NDB	NON-DIRECTIONAL BEACON
PAPI	PRECISION APPROACH PATH INDICATOR
PLASI	PULSE LIGHT APPROACH SLOPE INDICATOR
RAIL	RUNWAY ALIGNMENT INDICATING LIGHTS
REIL	RUNWAY END IDENTIFIER LIGHT
RVR	RUNWAY VISUAL RANGE
VADI	VISUAL APPROACH DESCENT INDICATOR
VASI	VISUAL APPROACH SLOPE INDICATOR
VOR	VERY HIGH FREQUENCY OMNIDIRECTIONAL RANGE FACILITY

WC

WIND CONE

NOTES:

- ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 - NATIONAL ELECTRICAL CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES, AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, INTERTEK TESTING SERVICES VERIFICATION/ETL LISTING (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT BE PERMITTED.
- 2. KEEP A COPY OF THE LATEST NEC IN FORCE ON SITE AT ALL TIMES DURING/CONSTRUCTION FOR USE AS A REFERENCE.
- NEW WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW ILS DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
- 4 LITEMO DENOTES LIQUID TIGHT FLEXIBLE METAL CONDUIT UI LISTED SUNLIGHT RESISTANT & SUITABLE FOR GROUNDING LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE U.L. LISTED TO MEET THE REQUIREMENTS OF NEC 350.6. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO CCR'S & TRANSFORMERS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.60. EXTERNAL BONDING JUMPERS USED WITH CCR INSTALLATIONS SHALL BE #6 AWG COPPER (MINIMUM). DO NOT INSTALL LTFMC THAT IS NOT UL LISTED. CONFIRM LTFMC BEARS THE UL LABEL PRIOR TO INSTALLATION.
- 5. INSULATED CONDUCTORS SHALL COLOR CODE PHASE AND NEUTRAL CONDUCTOR INSULATION FOR NO. 6 AWG OR SMALLER. PROVIDE COLORED INSULATION OR COLORED MARKING TAPE FOR PHASE AND NEUTRAL CONDUCTORS FOR NO. 4 AWG AND LARGER. INSULATED GROUND CONDUCTORS SHALL HAVE GREEN COLORED INSULATION FOR ALL CONDUCTOR AWG AND/OR KCMIL TO COMPLY WITH NEC 250.119. NEUTRAL CONDUCTORS SHALL HAVE WHITE COLORED INSULATION FOR NO. 6 AWG AND SMALLER TO MEET THE REQUIREMENTS OF NEC 200.6. STANDARD COLORS FOR POWER WIRING AND BRANCH CIRCUITS SHALL BE AS FOLLOWS:

120/240 VAC, 1 PHASE, 3 WIRE

(ORIGINATING FROM 240/120V 3 PH, 4W DELTA)

PHASE C BI UF NFUTRAL WHITE GREEN GROUND

- SEE RESPECTIVE SITE PLANS FOR SITE LEGEND INFORMATION.
- 7. ENCLOSURES RATED NEMA 4. 4X SHALL HAVE WATERTIGHT HUBS AT CONDUIT ENTRANCES UL LISTED NEMA 4, 4X FOR THE RESPECTIVE ENCLOSURE, TO MAINTAIN THE NEMA 4, 4X
- 8. ONLY QUALIFIED ELECTRICAL CONTRACTORS SHALL PERFORM ELECTRICAL WORK ON THIS PROJECT. NEC DEFINES A QUALIFIED PERSON AS "ONE WHO HAS SKILLS AND KNOWLEDGE RELATED TO THE CONSTRUCTION AND OPERATION OF THE ELECTRICAL EQUIPMENT AND INSTALLATIONS AND HAS RECEIVED SAFETY TRAINING TO RECOGNIZE AND AVOID THE HAZARDS INVOLVED."
- RESPECTIVE POWER SOURCES FOR EACH PANEL EQUIPMENT, AIRFIELD LIGHT, SIGN, NAVAID, OR OTHER DEVICE SHALL BE VERIFIED PRIOR TO WORKING ON, RELOCATING. REMOVING. DISCONNECTING. AND/OR INSTALLING THE RESPECTIVE DEVICES. SHUT OFF, LOCKOUT AND TAGOUT FOR PROTECTION OF PERSONNEL.
- 10. HIGH VOLTAGE CIRCUITS (AIRFIELD LIGHTING 5000 VOLT SERIES CIRCUITS AND OTHER CIRCUITS RATED ABOVE 600 VOLTS) AND LOW VOLTAGE CIRCUITS (RATED 600 VOLTS AND BELOW) SHALL NOT BE INSTALLED IN THE SAME WIREWAY CONDUIT, DUCT, RACEWAY, JUNCTION STRUCTURE OR HANDHOLE.

BID DOCUMENTS



www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA. ILLINOIS 62839

COVERING ELECTRICAL DESIGN LIGHTFOOT 062-047643

SIGNED: 7/29/2025 EXPIRES: 11/30/2025

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO.	DATE	DESCRIPTION						
NO.	DATE	DES	DWN	REV				
SSUE: JULY 25, 2025								
PROJECT NO: 23A1038								
CAD EILE: E.005 I CND DWG								

DESIGN BY: KNI 3/31/2025 DRAWN BY: CWS 4/4/2025 REVIEWED BY: KNL 6/24/2025

SHEET TITLE

ELECTRICAL LEGEND AND ABBREVIATIONS

SET IS MAIN FEEDER FOR VAULT, SECOND SET IS FOR LIGHTS AND RECEPTACLES AT VAULT.

EXIST. RADIO RELAY INTERFACE PANEL WITH PHOTOCELL BYPASS SWITCH FOR AIRFIELD LIGHTING

EXIST. ELECTRIC WALL HEATER EH-1, 2000 WATT, 240 VAC, 1 PHASE, MARLEY ENGINEERED PRODUCTS

EXIST. ELECTRIC WALL HEATER EH-2 3000 WATT, 240 VAC, 1 PHASE, MARLEY ENGINEERED PRODUCTS


EXIST. 60 AMP, 240 VAC, 2P DOUBLE THROW NOT FUSIBLE SAFETY SWITCH FOR RUNWAY CCR'S.

EXIST. VAULT MAIN DISTRIBUTION PANELBOARD

3 EXIST. AC SURGE PROTECTIVE DEVICE.

EXIST. L-854 RADIO CONTROL UNIT

4 EXIST. LIGHTING CONTACTOR PANEL



GENERAL NOTES

- CONTRACTOR SHALL COORDINATE WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS WITH THE AIRPORT DIRECTOR/MANAGER AND THE RESIDENT PROJECT REPRESENTATIVE, AND SHUT DOWN OF EXISTING SYSTEMS SHALL BE SCHEDULED WITH AND APPROVED BY THE AIRPORT MANAGER PRIOR TO SHUTDOWN. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT), FAILURE TO SHUT DOWN AND LOCKOUT THE RESPECTIVE CIRCUIT(S) PRESENTS A DANGEROUS HAZARD FOR PERSONNEL WORKING ON THE SYSTEM.
- 2. THE RESPECTIVE PERSONNEL PERFORMING AIRFIELD LIGHTING WORK, VAULT WORK, AND/OR TESTS SHALL BE FAMILIAR WITH AND QUALIFIED TO WORK ON 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS. CONSTANT CURRENT REGULATORS, AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT ONLY QUALIFIED ELECTRICAL CONTRACTORS SHALL PERFORM ELECTRICAL WORK ON THIS PROJECT. NEC DEFINES A QUALIFIED PERSON AS FOLLOWS; "ONE WHO HAS SKILLS AND KNOWLEDGE RELATED TO THE CONSTRUCTION AND OPERATION OF THE ELECTRICAL EQUIPMENT AND INSTALLATIONS AND HAS RECEIVED SAFETY TRAINING TO RECOGNIZE AND AVOID THE HAZARDS
- 3. CONTRACTOR SHALL EXAMINE THE SITE TO CONFIRM AND FIELD VERIFY EXISTING SITE CONDITIONS.
- 4. CONTRACTOR SHALL COMPLY WITH THE APPLICABLE REQUIREMENTS OF NFPA 70E - STANDARD FOR ELECTRICAL SAFETY IN THE WORKPLACE.
- 5. EACH ACTIVE CCR SERVING THE RESPECTIVE WORK AREAS OF THE PROJECT. SHALL BE TESTED FOR PROPER OPERATION BEFORE REMOVAL WORK MODIFICATIONS, ADDITIONS AND/OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING CIRCUITS AND AGAIN AFTER THE AIRFIELD LIGHTING REPLACEMENTS AND VAULT ADDITIONS HAVE BEEN COMPLETED. CONTRACTOR SHALL TEST AND RECORD THE INPUT CURRENT AND OUTPUT CURRENT FOR EACH CONSTANT CURRENT REGULATOR IN THE AUTOMATIC AND MANUAL MODES OF OPERATION, CONTRACTOR SHALL REPORT CONCERNS AND/OR DEFICIENCIES TO THE PROJECT ENGINEER OF RECORD

www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839



SIGNED: 7/29/2025 EXPIRES: 11/30/2025

INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

DESCRIPTION NO. DATE DES DWN REV ISSUE: JULY 25, 2025

PROJECT NO: 23A1038 CAD FILE: E-103-PLN.DWG

DESIGN BY: KNI 4/28/2025 DRAWN BY: CWS 4/29/2025 REVIEWED BY: KNL 6/24/2025

SHEET TITLE

AIRPORT VAULT **EQUIPMENT PLAN**

EXIST. 2-3" PVC COATED GRSC WITH PVC COATED GRSC ELBOWS FROM HIGH VOLTAGE WIREWAY TO HIGH VOLTAGE HANDHOLE.

EXIST. 3-3" PVC COATED GRSC WITH PVC COATED GRSC ELBOWS AT VAULT FROM LOW VOLTAGE WIREWAY TO LOW VOLTAGE MANHOLE #1.

EXIST. DRY CHEMICAL ABC FIRE EXTINGUISHER.

EXIST. UL RATED, 10 POUND CARBON DIOXIDE FIRE EXTINGUISHER

24 EXIST. HALOTRON FIRE EXTINGUISHER.

EXIST. 2-3" PVC COATED GRSC WITH PVC COATED GRSC ELBOWS FROM NEMA 4X SS PULL BOX TO LOW VOLTAGE MANHOLE #2.

2 SETS OF EXISTING ELECTRIC POWER FEEDER CONDUCTORS IN GRSC FROM SERVICE PANELBOARD. ONE 10 EXIST. EXHAUST FAN EF-1, 2000 CFM (MINIMUM) AT .25" STATIC PRESSURE WITH 1/3 HP (MINIMUM), 115 VAC MOTOR, ; CARNES MODEL LWBK20M1A1CP20F

[11] EXIST. INTAKE LOUVER L-1, 24" WIDE BY 48" HIGH INTAKE LOUVER WITH STAINLESS INSECT SCREEN.

EXIST. 6" BY 6" LOW VOLTAGE WIREWAY

EXIST. 6" BY 6" HIGH VOLTAGE WIREWAY.

EXIST. RUNWAY 3-21 CONSTANT CURRENT REGULATOR. OUTPUT SERIES CIRCUIT WIRING TO BE REMOVED AND REPLACED FROM EACH CCR TO CUTOUTS AND ON TO RUNWAY 3-21 LIGHTING SERIES CIRCUIT

EXIST. BACKUP CONSTANT CURRENT REGULATOR FOR RUNWAY 3-21. OUTPUT SERIES CIRCUIT WIRING TO BE REMOVED AND REPLACED FROM EACH CCR TO CUTOUTS AND ON TO RUNWAY 3-21 LIGHTING SERIES

EXIST. TAXIWAY CONSTANT CURRENT REGULATOR.

17 EXIST. ENTRANCE PAD/STEP.

EXIST. TRANSFER PAIR SERIES PLUG CUTOUTS (TYPE S-1) FOR RUNWAY LIGHTING WITH EXIST ENCLOSURE. OUTPUT SERIES CIRCUIT WIRING TO BE REMOVED AND REPLACED FROM EACH CCR TO CUTOUTS AND ON TO RUNWAY 3-21 LIGHTING SERIES CIRCUIT HOMERUN.

EXIST. SERIES PLUG CUTOUT (TYPE S-1) FOR TAXIWAY LIGHTING WITH EXISTING ENCLOSURE

BID DOCUMENTS



www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA. ILLINOIS 62839

COVERING ELECTRICAL DESIGN LIGHTFOOT 062-047643

INSTALL MEDIUM

INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD


DESCRIPTION NO. DATE DES DWN REV ISSUE: JULY 25, 2025 PROJECT NO: 23A1038 CAD FILE: E-601.DWG DESIGN BY: KNI 4/28/2025

DRAWN BY: CWS 4/29/2025

REVIEWED BY: KNL 6/24/2025

SHEET TITLE

EXISTING ONE-LINE DIAGRAM FOR VAULT AND AIRFIELD



NOTES

- KEEP ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS COORDINATED WITH THE AIRPORT MANAGER/DIRECTOR AND RESIDENT PROJECT REPRESENTATIVE. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT). WHERE THE FACILITY IS NOT EQUIPPED WITH LOCKOUT/TAGOUT EQUIPMENT THE RESPECTIVE PERSONNEL WILL BE RESPONSIBLE FOR PROVIDING THE APPROPRIATE LOCKOUT/TAGOUT EQUIPMENT. WHERE EXISTING ELECTRICAL EQUIPMENT DOES NOT HAVE FEATURES FOR LOCKOUT/TAGOUT THE RESPECTIVE PERSONNEL WILL BE RESPONSIBLE FOR PROVIDING THE APPROPRIATE LOCKOUT/TAGOUT EQUIPMENT AND MEASURES TO ENSURE THE COMPLIANCE WITH OSHA LOCKOUT/TAGOUT PROCEDURES. FAILURE TO SHUT DOWN AND LOCKOUT THE CIRCUIT PRESENTS A DANGEROUS HAZARD FOR PERSONNEL WORKING ON THE SYSTEM. COMPLIANCE WITH LOCKOUT/TAGOUT PROCEDURES AND ALL OTHER SAFETY PROCEDURES AND REQUIREMENTS ARE THE RESPONSIBILITY OF EACH INDIVIDUAL, THE CONTRACTOR, THE RESPECTIVE MAINTENANCE PERSONNEL, AND ANY OTHER PERSONNEL WORKING ON THE EQUIPMENT OR ELECTRICAL SYSTEM.
- EXAMINE THE SITE TO CONFIRM AND FIELD VERIFY EXISTING SITE CONDITIONS.
- VERIFY RESPECTIVE CIRCUITS AND POWER SOURCES FOR RESPECTIVE SYSTEMS PRIOR TO REMOVING, DISCONNECTING, WORKING ON, RELOCATING, RECONNECTING, AND/OR INSTALLING THE RESPECTIVE AIRFIELD LIGHTING, TAXI SIGN, NAVAID, VAULT EQUIPMENT OR OTHER DEVICES. THE CONTRACTOR WILL NEED TO EXERCISE CAUTION WHEN WORKING IN THE VALUET AND ON THE AIRFIELD. CONTRACTOR SHALL REPORT ANY VARIATIONS DEFICIENCIES, AND/OR APPARENT SAFETY CONCERNS TO THE PROJECT ENGINEER OF RECORD AND THE RESIDENT PROJECT REPRESENTATIVE. CONTRACTOR SHALL FOLLOW LOCKOUT/TAGOUT PROCEDURES TO COMPLY WITH OSHA REQUIREMENTS.

- IDENTIFY EACH RESPECTIVE CIRCUIT PRIOR TO PERFORMING WORK ON THAT CIRCUIT. CONTRACTOR SHALL ARRANGE TO SHUTOFF, DISCONNECT, AND LOCKOUT/TAGOUT CIRCUITS WHEN WORKING ON THE RESPECTIVE AIRFIELD LIGHTING SYSTEMS FOR SAFETY OF PERSONNEL
- NEVER REMOVE OR INSERT A CUTOUT WITH THE CIRCUIT ENERGIZED. SHUTOFF CIRCUITS PRIOR TO PULLING OR INSERTING A SERIES PLUG CUTOUT.
- THE RESPECTIVE PERSONNEL PERFORMING AIRFIELD LIGHTING WORK, VAULT WORK AND/OR TESTS SHALL BE FAMILIAR WITH, AND QUALIFIED TO WORK ON, 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS CONSTANT CURRENT REGULATORS AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT, NEC DEFINES A QUALIFIED PERSON AS "ONE WHO HAS SKILLS AND KNOWLEDGE RELATED TO THE CONSTRUCTION AND OPERATION OF THE ELECTRICAL EQUIPMENT AND INSTALLATIONS AND HAS RECEIVED SAFETY TRAINING TO RECOGNIZE AND AVOID THE HAZARDS INVOLVED."
- EXERCISE CAUTION, PRACTICE SAFETY, AND DISCONNECT THE SERIES CIRCUITS FROM THE RESPECTIVE CONSTANT CURRENT REGULATORS, AS APPLICABLE WHEN PERFORMING WORK ON THE AIRFIELD LIGHTING OR WORK THAT MIGHT AFFECT THE AIRFIELD LIGHTING CONTRACTOR SHALL MAKE NECESSARY ARRANGEMENTS TO DISCONNECT POWER AND LOCKOUT CIRCUITS FOR PROTECTION OF PERSONNEL
- OVERSEE AND CONDUCT TESTS FOR AREAS OF WORK WHERE THE RESPECTIVE CIRCUITS MIGHT BE AFFECTED. MEGGER TEST AND RECORD EXISTING SERIES CIRCUITS (WITH A CABLE INSULATION TESTER) PRIOR TO CABLE WORK OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING SYSTEMS, AND AGAIN AFTER AIRFIELD LIGHTING MODIFICATIONS ADDITIONS LIPGRADES AND/OR OTHER WORK HAS BEEN COMPLETED PROVIDE 5KV INSULATION TESTER FOR 5.000 VOLT SERIES CIRCUIT CABLES, ALSO TEST AND RECORD SERIES CIRCUIT LOOP RESISTANCE WITH AN OHMMETER. PROVIDE COPY OF TEST RESULTS TO THE ENGINEER OF RECORD (EOR) WITHIN 5 DAYS OF CONDUCTING

- RESPECTIVE CCR'S SHALL BE TESTED FOR PROPER OPERATION BEFORE REMOVAL WORK, MODIFICATIONS, ADDITIONS AND/OR ANY AIRFIELD WORK THAT MIGHT AFFECT LIGHTING CIRCUITS AND AGAIN AFTER THE AIRFIELD WORK AND ADDITIONS HAVE BEEN COMPLETED CONTRACTOR SHALL TEST AND RECORD THE INPUT CURRENT AND OUTPUT CURRENT FOR EACH CONSTANT CURRENT REGULATOR IN THE AUTOMATIC AND MANUAL MODES OF OPERATION. PROVIDE A TRUE RMS AMMETER FOR CURRENT MEASUREMENTS. CONTRACTOR SHALL REPORT CONCERNS AND/OR DEFICIENCIES TOT HE RESIDENT PROJECT REPRESENTATIVE AND THE ENGINEER OF RECORD (EOR). WRITTEN TEST RESULTS SHALL BE PROVIDED TO THE RESIDENT PROJECT REPRESENTATIVE AND THE ENGINEER OF RECORD (EOR). CABLE AND CCR TESTING WILL BE CONSIDERED INCIDENTAL TO ITEM AR800931 ELECTRICAL MODIFICATIONS PER LUMP SUM
- MAINTAIN SEPARATION OF HIGH VOLTAGE WIRING (AIRFIELD LIGHTING 5000 VOLT SERIES CIRCUITS FROM LOW VOLTAGE WIRING (RATED 1000 VOLTS AC AND BELOW) TO COMPLY WITH 2023 NEC 300.3(C)(2). HIGH VOLTAGE AND LOW VOLTAGE WIRING SHALL NOT BE INSTALLED IN THE SAME RACEWAY, CONDUIT, WIREWAY, PULL BOX, SPLICE CAN,
- LOW VOLTAGE WIRING SHALL ENTER THE RESPECTIVE CCR AT THE LOW VOLTAGE SECTION, HIGH VOLTAGE WIRING SHALL ENTER THE RESPECTIVE CCR AT THE HIGH
- EXISTING RUNWAY 3-21 CCR'S AND CUTOUTS SHALL HAVE THE EXISTING OUTPUT SERIES CIRCUIT WIRING REMOVED AND REPLACED WITH NEW #8AWG FAA L-824, 5000V CONDUCTORS. THIS WILL BE PAID FOR UNDER ITEM AR109410 "VAULT WIRING" PER LUMP
- ADD LEGEND PLATE TO EACH CCR LABELED "NOTICE CCR HAS SEPARATE 120V CONTROL POWER SOURCE".

BID DOCUMENTS




www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**

1 AIRPORT ROAD FLORA, ILLINOIS 62839



INSTALL MEDIUM INTENSITY RUNWAY LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIPTION DES DWN REV ISSUE: JULY 25, 2025 PROJECT NO: 23A1038							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
NO. DATE DES DWN REV							
SSUE: JULY 25, 2025	NO.	DATE	DESCRIPTION				
			DES	DWN	REV		
PROJECT NO: 23A1038	ISSUE: JULY 25, 2025						

CAD FILE: E-602.DWG

DESIGN BY: KNI 4/28/2025 DRAWN BY: CWS 4/29/2025 REVIEWED BY: KNL 6/24/2025

SHEET TITLE

ELECTRICAL ONE-LINE DIAGRAM FOR VAULT

5 CLICKS 7 CLICKS THE RUNWAY 3-21 PLASI CIRCUITS ARE CONTROLLED IN THE

3 CLICKS - ON 5 CLICKS - REMAIN ON 7 CLICKS - REMAIN ON

THE RADIO OVERRIDE SWITCH ACTIVATES L-854 RADIO CONTROL 24 HOURS PER DAY IN THE "RADIO ON" POSITION. THE PHOTOCELL WILL ACTIVATE RADIO CONTROL IN THE "PHOTOCELL ACTIVATE RADIO"

AUTOMATIC MODE BY THE L-854 RADIO CONTROL UNIT IN THE

FOLLOWING MANNER. CONFIRM CONTROL WITH AIRPORT MANAGER.

- IN THE AUTOMATIC MODE OF OPERATION THE AIRPORT ROTATING BEACON SHALL BE ACTIVATED BY THE PHOTOCELL OR PHOTOCELL BYPASS SWITCH.
- "N" DESIGNATES NEUTRAL CONNECTION OR NEUTRAL CONDUTOR.




www.hanson-inc.com

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL **AIRPORT**


1 AIRPORT ROAD FLORA, ILLINOIS 62839



INSTALL MEDIUM

INTENSITY RUNWAY LIGHTS ON RUNWAY 3/21

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD





PROJECT NO: 23A1038 CAD FILE: E-603.DWG

DESIGN BY: KNI 4/28/2025 DRAWN BY: CWS 4/29/2025 REVIEWED BY: KNL 6/24/2025

SHEET TITLE

AIRFIELD LIGHTING CONTROL WIRING **SCHEMATIC**






CABLE INSULATION RESISTANCE TEST (MEGGER TEST) NOTES

- PRIOR TO BEGINNING EXCAVATIONS, AIRFIELD LIGHTING MODIFICATIONS, CABLE INSTALLATION, AND/OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING CIRCUITS, ALL EXISTING SERIES CIRCUIT LIGHTING CABLES SHALL BE MEGGER TESTED WITH AN INSULATION RESISTANCE TESTER AND RECORDED AT THE RESPECTIVE AIRPORT ELECTRICAL VAULT. COORDINATE TESTING WITH THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT. PROJECT ENGINEER OF RECORD SHALL BE ON SITE TO OBSERVE TEST.
- AFTER AIRFIELD LIGHTING MODIFICATIONS, ADDITIONS, UPGRADES, AND/OR OTHER
 WORK AND ADDITIONS HAVE BEEN COMPLETED ALL EXISTING SERIES CIRCUIT LIGHTING
 CABLES SHALL BE MEGGER TESTED WITH AN INSULATION RESISTANCE TESTER AND
 RECORDED AT THE RESPECTIVE AIRPORT ELECTRICAL VAULT. COORDINATE TESTING
 WITH THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT. PROJECT ENGINEER OF
 RECORD SHALL BE ON SITE TO OBSERVE TEST.
- 3. THE CONTRACTOR IS RESPONSIBLE TO EMPLOY THE SERVICES OF PERSONNEL QUALIFIED, FAMILIAR WITH, AND TRAINED TO PERFORM THE RESPECTIVE TESTS, AND QUALIFIED TO WORK ON 5000 VOLT AIRFIELD LIGHTING SERIES CIRCUITS, CONSTANT CURRENT REGULATORS, AND ASSOCIATED AIRPORT ELECTRICAL VAULT EQUIPMENT.
- 4. INSULATION RESISTANCE TESTING EQUIPMENT FOR USE WITH 5,000 VOLT SERIES CIRCUIT CABLES SHALL USE AN INSULATION RESISTANCE TESTER CAPABLE OF TESTING THE CABLES AT 5,000 VOLTS. OLDER SERIES CIRCUIT CABLES AND/OR CABLES IN POOR CONDITION MAY REQUIRE THE TEST VOLTAGE TO BE PERFORMED AT A VOLTAGE LOWER THAN 5,000 VOLTS (EXAMPLE 1,000 VOLTS, 500 VOLTS, OR LESS THAN 500 VOLTS). THE RESPECTIVE TEST VOLTAGE SHALL BE RECORDED FOR EACH CABLE INSULATION RESISTANCE TEST RESULT.
- INSULATION RESISTANCE TESTING EQUIPMENT FOR USE WITH 600 VOLT RATED CABLES SHALL USE A 500 VOLT INSULATION RESISTANCE TESTER. THE RESPECTIVE TEST VOLTAGE SHALL BE RECORDED FOR EACH CABLE INSULATION RESISTANCE TEST RESULT.
- 6. IT IS RECOMMENDED TO USE THE SAME INSULATION RESISTANCE TEST EQUIPMENT THROUGHOUT THE PROJECT TO ENSURE RELIABLE COMPARATIVE READINGS AT THE BEGINNING OF THE PROJECT AND AT THE COMPLETION OF THE PROJECT.

- 7. DISCONNECT THE AIRFIELD LIGHTING SERIES CIRCUIT CABLES FROM THE CONSTANT CURRENT REGULATOR WHEN PERFORMING CABLE INSULATION RESISTANCE TESTS (MEGGER TESTS). TEST THE CABLES THAT GO TO THE AIRFIELD FOR THE RESPECTIVE AIRFIELD LIGHTING SERIES CIRCUIT. CONNECT THE CABLE INSULATION RESISTANCE TESTER TO ONE OF THE AIRFIELD LIGHTING SERIES CIRCUIT CABLES AND TO A GOOD GROUND IN THE AIRPORT ELECTRICAL VAULT SUCH AS THE AIRPORT VAULT GROUND BUS. CONDUCT THE CABLE INSULATION RESISTANCE TEST ON EACH RESPECTIVE CABLE FOR NOT LESS THAN 90 SECONDS. RECORD THE TEST RESULTS AT THE END OF THE TIME DURATION FOR THE TEST.
- 8. FAA ADVISORY CIRCULAR 150/5340-26C MAINTENANCE OF AIRPORT VISUAL AID FACILITIES PROVIDES GUIDANCE ON INSULATION RESISTANCE TESTS. ALSO REFER TO THE USER MANUAL FOR THE RESPECTIVE CABLE INSULATION RESISTANCE TESTER. REASONABLY NEW SERIES CIRCUIT CABLES AND TRANSFORMERS WITH GOOD CONNECTIONS SHOULD READ 500 MEGA-OHMS TO 1,000 MEGA-OHMS OR HIGHER. THE READINGS SHOULD DECREASE WITH AGE. THE RESISTANCE VALUE DECLINES OVER THE SERVICE LIFE OF THE CIRCUIT; A 10-20 PERCENT DECLINE PER YEAR MAY BE CONSIDERED NORMAL. A YEARLY DECLINE OF 50 PERCENT (4 PERCENT MONTHLY) OR GREATER INDICATES THE EXISTENCE OF A PROBLEM, SUCH AS A HIGH RESISTANCE GROUND, SERIOUS DETERIORATION OF THE CIRCUIT INSULATION, LIGHTNING DAMAGE, BAD CONNECTIONS, BAD SPLICES, CABLE INSULATION DAMAGE, OR OTHER FAILURE. FAA ADVISORY CIRCULAR 150/5340-26C NOTES "GENERALLY SPEAKING, ANY CIRCUIT THAT MEASURES LESS THAN 1 MEGOHM IS CERTAINLY DESTINED FOR RAPID FAILURE." AIRFIELD LIGHTING SERIES CIRCUITS WITH CABLE INSULATION READINGS OF LESS THAN 1 MEGOHM ARE NOT UNCOMMON FOR OLDER CIRCUITS THAT ARE 20 YEARS OR MORE OF AGE.
- BASED ON INFORMATION IN FAA AC NO. 150/5340-26C MAINTENANCE OF AIRPORT VISUAL AID FACILITIES, THE CABLE INSULATION RESISTANCE VALUE INEVITABLY DECLINES OVER THE SERVICE LIFE OF THE CIRCUIT; A 10-20 PERCENT DECLINE PER YEAR MAY BE CONSIDERED NORMAL. IN THE EVENT THAT THE CABLE INSULATION RESISTANCE READINGS HAVE DECLINED MORE THAN 2 PERCENT PER MONTH IT MIGHT INDICATE CABLE DAMAGE DUE TO LIGHTNING OR DAMAGE AS A RESULT OF CONTRACTOR OPERATIONS. WHERE THE CABLE INSULATION RESISTANCE READINGS HAVE DECLINED MORE THAN 2 PERCENT PER MONTH OVER THE PROJECT CONSTRUCTION DURATION AS A RESULT OF CONTRACTOR OPERATIONS, CONTRACTOR WILL NEED TO INVESTIGATE, ADDRESS. AND REPAIR THE RESPECTIVE CABLE CIRCUITS.



MEASURE RESISTANCE OF SERIES CIRCUIT LOOP.

NOT TO SCALE

SERIES CIRCUIT LOOP RESISTANCE MEASUREMENT NOTES

- PRIOR TO BEGINNING EXCAVATIONS, AIRFIELD LIGHTING MODIFICATIONS, CABLE INSTALLATION, AND/OR ANY OTHER WORK THAT MIGHT POSSIBLY AFFECT AIRFIELD LIGHTING CIRCUITS, THE RESPECTIVE SERIES CIRCUIT CABLE LOOPS SHALL HAVE THE RESISTANCE MEASURED WITH AN OHMMETER AND RECORDED FOR EACH CIRCUIT AT THE VAULT. COORDINATE TESTING WITH THE PROJECT ENGINEER OF RECORD; KEVIN LIGHTFOOT. PROJECT ENGINEER OF RECORD SHALL BE ON SITE TO OBSERVE TEST.
- AFTER AIRFIELD LIGHTING MODIFICATIONS, ADDITIONS, UPGRADES, AND/OR
 OTHER WORK AND ADDITIONS HAVE BEEN COMPLETED THE RESPECTIVE
 SERIES CIRCUIT CABLE LOOPS SHALL HAVE THE RESISTANCE MEASURED
 WITH AN OHMMETER AND RECORDED FOR EACH CIRCUIT AT THE VAULT.
 COORDINATE TESTING WITH THE PROJECT ENGINEER OF RECORD; KEVIN
 LIGHTFOOT. PROJECT ENGINEER OF RECORD SHALL BE ON SITE TO OBSERVE
 TEST
- ALL EXISTING SERIES CIRCUIT CABLE LOOPS SHALL HAVE THE RESISTANCE MEASURED WITH AN OHMMETER AND RECORDED FOR EACH CIRCUIT AT THE VAULT. THE RESISTANCE OF THE SERIES CIRCUIT LOOP WITH CONNECTIONS USING #8 AWG COPPER CONDUCTOR SHOULD BE APPROXIMATELY 0.8 TO 1 OHM PER THOUSAND FEET OF CABLE LENGTH. THE RESISTANCE OF THE SERIES CIRCUIT LOOP WITH CONNECTIONS USING #6 AWG COPPER CONDUCTOR SHOULD BE APPROXIMATELY 0.5 TO 0.7 OHM PER THOUSAND FEET OF CABLE LENGTH. THE NUMBER OF SERIES CIRCUIT TRANSFORMERS AND CONNECTIONS WILL AFFECT THE OVERALL RESISTANCE OF THE SERIES CIRCUIT LOOP AND THEREFORE THE MEASUREMENTS MIGHT BE SLIGHTLY HIGHER THAN THE CALCULATED RESISTANCE FOR THE RESPECTIVE LENGTH OF CABLE




Offices Nationwide

Hanson Professional Services Inc. 1525 S. 6th Street Springfield, IL 62568 phone: 217-788-2450 fax: 217-788-2503

Illinois Licensed Professional Service Corporation #184-001084

FLORA MUNICIPAL AIRPORT

1 AIRPORT ROAD FLORA, ILLINOIS 62839



DATE

SIGNED: 7/29/2025 EXPIRES: 11/30/2025
INSTALL MEDIUM
INTENSITY RUNWAY
LIGHTS ON RUNWAY

IDA No: FOA-5137 SBG No: 3-17-SBGP-TBD

NO. DATE DESCRIPTION
DES DWN REV
ISSUE: JULY 25, 2025
PROJECT NO: 23A1038
CAD FILE: E-604 DWG

SHEET TITLE

SERIES CIRCUIT CABLE TESTING DETAILS

DESIGN BY: KNI 4/28/2025

DRAWN BY: CWS 4/29/2025

REVIEWED BY: KNL 6/24/2025