


URBAN

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
20200100	EARTH EXCAVATION	CU YD	346	346					
20800150	TRENCH BACKFILL	CU YD	62	62					
21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	43	43					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	32	32					
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	1,177	1,177					
31200110	STABILIZED SUBBASE 6"	SO YD	43	43					
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20					
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	22	22					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	1,068	1,068					
42001300	PROTECTIVE COAT	SO YD	1,593	1,593					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	79	79					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	720	720					
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SO FT	1,818	1,818					
42400800	DETECTABLE WARNINGS	SO FT	164	164					
44000100	PAVEMENT REMOVAL	SO YD	1,099	1,099					
44000300	CURB REMOVAL	FOOT	67	67					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	570	570					
44000600	SIDEWALK REMOVAL	SO FT	2,538	2,538					
44001980	CONCRETE BARRIER REMOVAL	FOOT	15	15					
44003100	MEDIAN REMOVAL	SO FT	830	830					
44004250	PAVED SHOULDER REMOVAL	SO YD	43	43					
48300820	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SO YD	43	43					
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1				
50102400	CONCRETE REMOVAL	CU YD	309		309				
50157300	PROTECTIVE SHIELD	SO YD	2,652		2,652				

- DENOTES SPECIALTY ITEM
- DENOTES CHICAGO DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION

75

FILES 5/22/2013 3:21:27 PM

 2501 W. Higgins Road, Suite 200 Chicago, Illinois 60631 773-355-0012	USER NAME - J485	DESIGNED - JSO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	63rd STREET BRIDGE REPLACEMENT - COOK COUNTY SUMMARY OF QUANTITIES			F.A.I. RTE. 94	SECTION 1920-B	COUNTY COOK	TOTAL SHEETS 137	SHEET NO. 5	
	PLOT SCALE - 1/8" = 1'-0"	CHECKED - TNS	REVISED -		SCALE: 1"=80'	SHEET 1	OF 8 SHEETS	STA. TO STA.	CONTRACT NO. 60J15				
	PLOT DATE - 5/22/2013	DATE - 03-15-2013	REVISED -		ILLINOIS FED. AID PROJECT								