

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0011	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	270	270					
• 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	237			237			
" • X0370121	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	518			518			
" • X0370122	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL (CDOT)	FOOT	634			634			
" • X0370123	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	140			140			
" • X0370124	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL (CDOT)	FOOT	3,010						3,010
" • X0370125	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	952			952			
• 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	221			221			
• 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	12			12			
• 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	6			6			
• 81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24"x24"x10"	EACH	2			2			
" • X0370126	UNIT DUCT, 600 V, 3-1/2" NO. 2, 1/2" NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE (CDOT)	FOOT	102			102			
" • X0370127	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10 (CDOT)	FOOT	2,786			2,786			
" • X0370128	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4 (CDOT)	FOOT	932			932			
" • X0370129	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2 (CDOT)	FOOT	2,500			2,500			
• 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5,982			5,982			
" • X0370140	REMOVE EXISTING STREET LIGHTING EQUIPMENT (CDOT)	L SUM	1			1			
" • X0370120	RACK, SECONDARY-AERIAL, 2-WIRE (CDOT)	EACH	1			1			
" • X0370131	REMOVE CONDUIT ATTACHED TO STRUCTURE (CDOT)	FOOT	2,083			2,083			
" • X0370132	MAINTENANCE OF STREET LIGHTING SYSTEM (CDOT)	L SUM	1			1			
" • X0370003	CABLE IN CONDUIT, TRIPLEX, 2-1/2" NO. 6, 1/2" NO. 8 (CDOT)	FOOT	2,692			2,692			
" • X0370133	PAINT EXISTING STREET LIGHT/TRAFFIC EQUIPMENT COMPLETE (CDOT)	EACH	1			1			
" • X0370134	JUNCTION BOX, POLE OR POST MOUNTED (CDOT)	EACH	2				1	1	
X2011000	TEMPORARY FENCE (SPECIAL)	FOOT	453		453				

• DENOTES SPECIALTY ITEM  
 • DENOTES CHICAGO DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION

24

5/22/2013 1:27:28 PM  
 GR@EF  
 8501 W. Higgins Road, Suite 200  
 Chicago, Illinois 60631  
 (773) 399-0112

USER NAME - J485 DESIGNED - JSO DRAWN - HJM CHECKED - TNS PLOT DATE - 5/22/2013	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>63rd STREET BRIDGE REPLACEMENT - COOK COUNTY</b> <b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 94 SECTION 1920-B COUNTY COOK TOTAL SHEETS 137 SHEET NO. 78 CONTRACT NO. 60J15
SCALE: NTS=60' SHEET 5 OF 8 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT	