



MATCHLINE 63RD ST. STA. 22+00

- NOTES:
1. ANY DISTURBED LANDSCAPING WITHIN THE PLANTER BOX AREAS SHALL BE REPLACED IN KIND. THIS WORK SHALL BE PAID FOR AS LANDSCAPING (SPECIAL).
 2. ALL 8-INCH P.C.C. SIDEWALK SHALL BE HIGH EARLY STRENGTH P.C.C.
 3. FOR ADA CURB RAMP DETAILS, SEE SHEETS 120-123.
 4. LONGITUDINAL CONSTRUCTION JOINT, DRILL AND GROUT NO. 8 DEFORMED EPOXY TIE BARS 30" LONG AT 24" C-C SHALL BE INCLUDED IN THE COST OF THE PCC SHOULDER.

LEGEND

- PAVEMENT REMOVAL
AGGREGATE SUBGRADE IMPROVEMENT, 12"
PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)
- MEDIAN REMOVAL
HOT-MIX ASPHALT MEDIAN SURFACE, 4 INCH
- SIDEWALK REMOVAL
PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH
(HIGH EARLY STRENGTH)
DETECTABLE WARNINGS
- SIDEWALK REMOVAL
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH
- TOPSOIL FURNISH AND PLACE, 4"
LANDSCAPING, SPECIAL
- COMBINATION CURB AND GUTTER REMOVAL
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12
- (A) CONCRETE BARRIER REMOVAL
CONCRETE BARRIER TRANSITION
BARRIER BASE
- (B) MODIFY CONCRETE BARRIER AND RETAINING WALL
(REMOVAL AND REPLACEMENT)
- PAVED SHOULDER REMOVAL (DAN RYAN) SEE NOTE 4
PORTLAND CEMENT CONCRETE SHOULDERS, 14"
STABILIZED SUB BASE 6"
SUB BASE GRANULAR MATERIAL, TYPE B-24"
GEOTECHNICAL FABRIC FOR GROUND STABILIZATION

MATCHLINE 63RD ST. STA. 22+00

WENTWORTH AVE

FILE NAME *	USER NAME * #USER#	DESIGNED - KMM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	RESTORATION PLAN			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - LV	REVISED -		63RD ST & YALE AVE, 63RD ST & WENTWORTH AVE			94	1920-B	COOK	137	118
PLDT SCALE * #SCALE#		CHECKED - JDH	REVISED -		SCALE: 1"=20'			SHEET NO. OF SHEETS		STA. TO STA.		
PLDT DATE * #DATE#		DATE - 02-22-2012	REVISED -		CONTRACT NO. 60J15			ILLINOIS FED. AID PROJECT				