

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	S.N.	S.N.	0005 ROADWAY
				045-0035	045-0036	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	315	123	179	13
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	135	55	80	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	605	246	359	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	320	160	160	
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	129			129
50102400	CONCRETE REMOVAL	CU YD	29.0	12.9	16.1	
50104650	SLOPE WALL REMOVAL	SO YD	319	215	104	
50157300	PROTECTIVE SHIELD	SO YD	898	383	515	
50300100	FLOOR DRAINS	EACH	24	12	12	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	29.2	13.0	16.2	
50300260	BRIDGE DECK GROOVING	SO YD	1741	720	1021	
50300300	PROTECTIVE COAT	SO YD	424	205	219	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	13570	11270	2300	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2620	1120	1500	
50800515	BAR SPLICERS	EACH	48	24	24	
51100100	SLOPE WALL 4 INCH	SO YD	319	213	106	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	166	70	96	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	30	12	18	
52100520	ANCHOR BOLTS, 1"	EACH	60	24	36	
63301235	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	48	24	24	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6			6
67100100	MOBILIZATION	L SUM	1			1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2			2
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2			2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6			6
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6			6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4			4
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4213			4213
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1650.0			1650.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1288			1288
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3			3
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4			4
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1			1
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1			1
72000300	SIGN PANEL - TYPE 3	SO FT	94.5	94.5		

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	S.N.	S.N.	0005 ROADWAY
				045-0035	045-0036	
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	13.5	13.5		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	77			77
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,847			10,847
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	155			155
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	6,007			6,007
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	395			395
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	162			162
78200530	BARRIER WALL MARKERS, TYPE C	EACH	264			264
78300100	PAVEMENT MARKING REMOVAL	SO FT	8,134			8,134
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	162			162
X0326766	CLEAN & RESEAL RELIEF JOINT	FOOT	136	54	82	
X4400110	TEMPORARY PAVEMENT REMOVAL	SO YD	129			129
X6060082	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (SPECIAL)	FOOT	320	160	160	
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1			1
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1			1
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	14,404			14,404
X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	6367			6367
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	146			146
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SO YD	19	9	10	
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	30	12	18	
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	9570	9570		
Z0001905	STRUCTURAL STEEL REPAIR	POUND	10610	4790	5820	
Z0003600	BEAM STRAIGHTENING	L SUM	1	0.3	0.7	
Z0006020	BRIDGE DECK LATEX CONCRETE OVERLAY 3/2"	SO YD	1807	755	1052	
Z0012152	BRIDGE DECK SCARIFICATION 3/2"	SO YD	1807	755	1052	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	702	273	429	
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	77		77	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	54	24	30	
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	280			280
Z0062456	TEMPORARY PAVEMENT	SO YD	129			129
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	0.5	0.5	
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1		

• DENOTES SPECIALTY ITEM

Rev. 9-10-13



USER NAME - #USER#	DESIGNED - SEW	REVISED -
PLOT SCALE - #SCALE#	DRAWN - SEW	REVISED -
PLOT DATE - #DATE#	CHECKED - ST	REVISED -
	DATE - 11/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES US ROUTE 30 / IL 56 OVER IL 47		F.A.P. RTE. 573	SECTION 61 HB-1-7	COUNTY KANE	TOTAL SHEETS 48	SHEET NO. 3
SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			