

**INDEX OF SHEETS**

- 1 COVER SHEET
- 2 INDEX OF SHEETS
- 3 LOCATION MAP
- 4-8 SUMMARY OF QUANTITIES
- 9-14 DISTRICT 1 STANDARD TRAFFIC SIGNAL DESIGN DETAILS

PAGE	TS#	INTERSECTION NAME
15	TS 3890	79TH ST @ ROBERTS RD
16	TS 12760	79TH ST @ 78TH AVE
17	TS 12755	79TH ST @ OKETO AVE
18	TS 2165	IL 43/HARLEM AVE @ 71ST ST
19	TS 2170	IL 43/HARLEM AVE @ 75TH ST
20	TS 2345	IL 43/HARLEM AVE @ 77TH ST
21	TS 2175	IL 43/HARLEM AVE @ 79TH ST
22	TS 2180	IL 43/HARLEM AVE @ 83RD ST
23	TS 2340	IL 43/HARLEM AVE @ 84TH ST
24	TS 2185	IL 43/HARLEM AVE @ 87TH ST
25	TS 2190	IL 43/HARLEM AVE @ 88TH/SOUTHFIELD SHOPPING CENTER DR
26	TS 2195	IL 43/HARLEM AVE @ 90TH ST/CAMBRIDGE DR
27	TS 2335	IL 43/HARLEM AVE @ 92ND PL/STANFORD DR
28	TS 12530	IL 43/HARLEM AVE @ 100TH PL
29	TS 3885	79TH ST @ NARRAGANSETT AVE
30	TS 3880	79TH ST @ CENTRAL AVE
31	TS 2451	IL 50/CICERO AVE @ BURBANK STATION/77TH ST
32	TS 2470	IL 50/CICERO AVE @ 79TH ST
33	TS 2525	IL 50/CICERO AVE @ 80TH AVE
34	TS 2475	IL 50/CICERO AVE @ 83RD ST
35	TS 3835	55TH ST/ARCHER AVE @ CENTER AVE/LAWDALE AVE
36	TS 3555	IL 171/ARCHER AVE @ 55TH ST/ARCHER AVE
37	TS 20525	IL 171/ARCHER AVE @ 57TH ST/BULLDOG DR
38	TS 3557	IL 171/ARCHER AVE @ 59TH ST
39	TS 3545	IL 171/ARCHER AVE @ 63RD ST
40	TS 2155	63RD ST @ 63RD ST CUT OFF
41	TS 2150	IL 43/HARLEM AVE @ 63RD ST
42	TS 2145	IL 43/HARLEM AVE @ 60TH ST
43	TS 2140	IL 43/HARLEM AVE @ 57TH ST
44	TS 2260	IL 43/HARLEM AVE @ 55TH ST/ARCHER AVE
45	TS 15	IL 43/HARLEM AVE @ I-55 STEVENSON EXPY/SOUTH RAMP EB
46	TS 5	IL 43/HARLEM AVE @ I-55 STEVENSON EXPY/NORTH RAMP WB
47	TS 11640	US 12-US 20/95TH ST @ KEAN AVE
48	TS 11760	US 12-US 20/95TH ST @ 76TH AVE
49	TS 427	US 12-US 20/95TH ST @ I-294/RAMP B
50	TS 510	US 12-US 20/95TH ST @ OAK PARK AVE
51	TS 520	US 12-US 20/95TH ST @ RIDGELAND AVE
52	TS 515	US 12-US 20/95TH ST @ MELVINA AVE
53	TS 530	US 12-US 20/95TH ST @ IL 7/SOUTHWEST HWY
54	TS 465	US 12-US 20/95TH ST @ CENTRAL AVE
55	TS 445	US 12-US 20/95TH ST @ 54TH AVE
56	TS 475	US 12-US 20/95TH ST @ COOK AVE
57	TS 440	US 12-US 20/95TH ST @ 52ND AVE
58	TS 2480	IL 50/CICERO AVE @ 87TH ST
59	TS 2530	IL 50/CICERO AVE @ 91ST ST
60-61	TS 2485	IL 50/CICERO AVE @ 94TH ST
62	TS 481	US 12-US 20/95TH ST @ KEELER AVE
63	TS 495	US 12-US 20/95TH ST @ K-MART SHOPPING CENTER
64	TS 12035	CRAWFORD AVE/PULASKI RD @ 93RD ST
65	TS 4885	CRAWFORD AVE/PULASKI RD @ 99TH ST
66	TS 2490	IL 50/CICERO AVE @ 99TH ST
67	TS 2495	IL 50/CICERO AVE @ 103RD ST
68	TS 21015	IL 50/CICERO AVE @ 105TH ST
69	TS 2500	IL 50/CICERO AVE @ 107TH ST
70	TS 2505	IL 50/CICERO AVE @ 110TH ST
71	TS 2512	111TH ST @ JODAN DR / LARAMIE AVE
72	TS 12135	111TH ST @ KOSTNER AVE
73	TS 9335	CRAWFORD AVE/PULASKI RD @ 107TH ST
74	TS 3925	CRAWFORD AVE/PULASKI RD @ 103RD ST
75	TS 11855	KEDZIE AVE @ 91ST ST
76	TS 11850	KEDZIE AVE @ 99TH ST
77	TS 5860	WESTERN AVE @ 98TH ST
78	TS 5865	WESTERN AVE @ 99TH ST
79	TS 480	US 12-US 20/95TH ST @ CRAWFORD AVE/PULASKI RD
80	TS 500	US 12-US 20/95TH ST @ MILLARD AVE
81	TS 540	US 12-US 20/95TH ST @ HOMAN AVE
82	TS 11790	US 12-US 20/95TH ST @ UTICA AVE
83	TS 11785	US 12-US 20/95TH ST @ CALIFORNIA AVE
84	TS 460	US 12-US 20/95TH ST @ CAMPBELL AVE
85-86	TS 3935	IL 7 SOUTHWEST HWY @ 103RD ST/VIRGINIA L SIEGEL MEMORIAL DR
87	TS 1890	IL 7 SOUTHWEST HWY @ IL 43 HARLEM AVE
88	TS 8770	111TH ST @ OKETO AVE
89	TS 2210	111TH ST @ IL 43 HARLEM AVE
90	TS 8775	111TH ST @ OAK PARK AVE
91	TS 2215	IL 43/HARLEM AVE @ 115TH ST

- 92 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC-10)
- 93 TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC-14)

**GENERAL NOTES:**

THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 72 HOURS IN ADVANCE OF BEGINNING WORK.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION. THIS SHALL INCLUDE LOCATING THE MAST ARM FOUNDATIONS AND VERIFYING THE MAST ARMS LENGTHS.

THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ORDERING ANY MATERIALS AND STARTING ANY WORK. FOR LOCATIONS OF UTILITIES, LOCALLY OWNED EQUIPMENT, LEASED ENFORCEMENT CAMERA SYSTEM FACILITIES AND IDOT UNDERGROUND FACILITIES, CONTACT THE LOCAL COUNTIES, MUNICIPALITIES AND IDOT FOR LOCATES. THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811, IN THE CITY OF CHICAGO CONTACT DIGGER AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS NOTIFICATION REQUIRED).

IF THIS CONTRACT REQUIRES THE SERVICES OF AN ELECTRICAL CONTRACTOR, THE CONTRACTOR SHALL BE RESPONSIBLE AT HIS/HER OWN EXPENSE FOR LOCATING EXISTING IDOT ELECTRICAL FACILITIES PRIOR TO PERFORMING ANY WORK. IF THIS CONTRACT DOES NOT REQUIRE THE SERVICES OF AN ELECTRICAL CONTRACTOR, THE CONTRACTOR MAY REQUEST ONE FREE LOCATE FOR EXISTING IDOT ELECTRICAL FACILITIES FROM THE DISTRICT ONE ELECTRICAL MAINTENANCE CONTRACTOR PRIOR TO THE START OF ANY WORK. ADDITIONAL REQUESTS MAY BE AT THE EXPENSE OF THE CONTRACTOR. THE LOCATION OF UNDERGROUND TRAFFIC FACILITIES DOES NOT RELIEVE THE CONTRACTOR OF THEIR RESPONSIBILITY TO REPAIR ANY FACILITIES DAMAGED DURING CONSTRUCTION AT THEIR EXPENSE.

THE CONTRACTOR SHALL CHECK THE PROPOSED TRAFFIC SIGNAL EQUIPMENT LOCATIONS FOR OVERHEAD UTILITY CONFLICTS. THE CONTRACTOR SHALL COORDINATE ANY CONFLICTS WITH THE UTILITY COMPANIES AND THE RESIDENT ENGINEER BEFORE ORDERING MATERIALS.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LOCAL GOVERNMENT AGENCIES AND IDOT.

RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED AS THE TEST STANDARD OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.

THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE PLANS AND SHALL NOTIFY THE ENGINEER AT ONCE OF ANY DISCREPANCIES.

THE CONTRACTOR IS REQUIRED TO ATTEND AN ILLINOIS DEPARTMENT OF TRANSPORTATION (IDOT) PRECONSTRUCTION MEETING AND SHALL INFORM THE IDOT TRAFFIC ENGINEER BEFORE WORK COMMENCES.

THE CONTRACTOR SHALL KEEP PUBLIC STREET PAVEMENTS CLEAN OF DIRT AND DEBRIS.

THE CONTRACTOR SHALL BE RESPONSIBLE IN PROVIDING SAFE AND HEALTHFUL CONDITIONS THROUGHOUT THE CONSTRUCTION OF THE PROPOSED IMPROVEMENTS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND AND SURFACE UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE RESTORED TO A CONDITION EQUAL TO THAT EXISTING BEFORE THE DAMAGE INCURRED. THIS WORK SHALL BE AT THE CONTRACTOR'S EXPENSE.

NEW CONTROLLER CABINETS SHALL BE PLACED SO THAT, a) THE DOORS OPEN AWAY FROM THE CURB OR TRAVEL WAY., b) AND THE TRAFFIC MOVEMENTS AT THE INTERSECTION ARE VISIBLE FROM THE CONTROLLER.

ANY CONTROLLER CABINET WHETHER NEW OR EXISTING TO RECEIVE UPS, WILL HAVE A "L" SHAPED 3 FOOT CONCRETE MAINTENANCE PAD INSTALLED. THE COST OF INSTALLATION OF CONCRETE PAD IS INCIDENTAL TO NEW CONTROLLER AND OR UPS INSTALLATIONS.

PRIOR TO REMOVING ANY TRAFFIC SIGNAL POST SPECIFIED TO BE REPLACED IN THE SAME LOCATION, THE CONTRACTOR SHALL VERIFY THAT THE PATTERN, SPACING, AND CONDITION OF THE EXISTING BOLTS ARE SUITABLE FOR RE-USE WITH A NEW POST. IF THE BOLTS ARE NOT REUSABLE, THEN THE EXISTING POST SHALL REMAIN IN PLACE OR AS DIRECTED BY THE ENGINEER.

ALL EXISTING SIGNING SHALL BE MAINTAINED PER ARTICLE 107.25 OF THE STANDARD SPECIFICATIONS AND TRANSFERRED TO THE NEW TRAFFIC SIGNALS WHERE APPLICABLE.

CONTRACTOR SHALL REPLACE BROKEN MOUNTING BRACKETS AT ALL RETROFIT SIGNAL HEAD INTERSECTIONS OR AS DIRECTED BY THE ENGINEER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CORRESPONDING SIGNAL HEAD, LED, RETROFIT PAY ITEM OF THE TYPE AND NUMBER OF SIGNAL HEADS, FACES AND SECTIONS AS SPECIFIED IN THE PLANS.

THE CONTRACTOR SHALL RELOCATE EXISTING SIGN PANELS FROM PAINTED POSTS THAT ARE INDICATED FOR REPLACEMENT TO A NEW POSTS AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL, RELOCATION AND ANY NEW MOUNTING HARDWARE NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE TRAFFIC SIGNAL POST, GALVANIZED STEEL PAY ITEM OF THE LENGTH AS SPECIFIED ON THE PLANS.

DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA FOR THE BELOW LISTED LOCATIONS, CONTRACTOR SHALL NOTIFY THE VILLAGE AND RLR CAMERA COMPANY PRIOR TO THE START OF CONSTRUCTION. THE VILLAGE OR THE RLR CAMERA COMPANY SHALL MAKE THE CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

**RLR CAMERA LOCATIONS:**

TS# 2260 IL 43 (HARLEM AVENUE) AT 55TH STREET


VILLAGE OF SUMMIT 7321 W. 59TH STREET SUMMIT, IL 60501 708-563-4800	SAFESPEED, LLC 150 N. WACKER DRIVE CHICAGO, IL 60606 877-237-2331
--	--

TS# 2520 95TH STREET AT RIDGELAND AVENUE  
TS# 2480 CICERO AVENUE AT 87TH STREET

VILLAGE OF OAK LAWN 9446 S. RAYMOND AVENUE OAK LAWN, IL 60453 708-636-4400	REDFLEX TRAFFIC SYSTEMS 773-633-5807
---	---

TS# 1890 SOUTHWEST HIGHWAY AT HARLEM AVENUE  
TS# 2210 HARLEM AVENUE AT 111TH STREET

VILLAGE OF WORTH 7112 W. 111TH STREET WORTH, IL 60482 708-448-1181	REDSPEED ILLINOIS 400 EISENHOWER LANE NORTH LOMBARD, IL 60148 630-317-5720
---	---

FILE NAME * MICROST352187 02-INDEX.DGN	USER NAME * JGC	DESIGNED - BPT	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS</b>				 <p>PREPARED BY: <b>CEMCON, Ltd.</b> Consulting Engineers, Land Surveyors &amp; Planners 2280 White Oak Circle, Suite 100 Aurora, Illinois 60504-9675 Ph: 630.862.2100 Fax: 630.862.2199 E-Mail: cadd@cemcon.com Website: www.cemcon.com</p>
	PLOT SCALE * NOT TO SCALE	DRAWN - RDS/JGC	REVISED -		F.A.U. SECTION	COUNTY	TOTAL SHEET NO.	SHEET NO.	
	PLOT DATE * X	CHECKED - BPT	REVISED -		VAR. 2013-035TS	COOK	93	2	
		DATE - XX-XX-13	REVISED -		CONTRACT NO. 60WB1		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.