## TRAFFIC SIGNAL QUANTITIES

			38TH ST & 41ST DR CONNECTOR	41ST DR CONNECTOR & 40TH AVE	COALTOWN RD & 41ST DR CONNECTOR	38TH ST & COALTOWN RD	INTERCONNECT		
PAY CODE	ITEM	UNIT	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	TOTALS	
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1					1	
87703010	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 56 FT.	EACH	1					1	_
87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	2					2	-
87703040	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 62 FT.	EACH			1			1	-
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	4	4	8		32	
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4	4	4		16	-
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT		20				20	-
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		37	35		87	
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	63	21	21			105	
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH		1	1	3		5	
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	3	4	3		14	
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH			3	1		4	
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	8	3	4	3		18	NOTE:
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH		1				1	I. THE ADDITIONAL QUANTITY INCLUDED IN THE TEMPORARY TRAFFIC SIGNAL INSTALLATION IS FOR 41ST ST AT
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4	1	1	1		7	- 41ST AVENUE DRIVE. - 2. THIS PAY ITEM IS FOR THE
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH		2		2		4	INTERSECTION AT JOHN DEERE RD AND 38TH ST.
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		2	2		8	
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	12	6	8	6		32	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	2	6	6		22	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					2	SEE NOTE 1
89502800	DISPOSITION OF SALVAGED TRAFFIC SIGNAL EQUIPMENT	L SUM						1	SEE NOTE 2
X8140105	HANDHOLE (SPECIAL)	EACH		2				2	
X0326477	WIRELESS VEHICLE DETECTION AND WARNING SYSTEM COMPLETE	EACH	1	1	1	1		4	
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	1	1	1		4	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1					2	SEE NOTE 1
									1
									SOTY-2



DESIGNED	-	TVN	REVISED -
DRAWN	-	CJD	REVISED -
CHECKED	-	RPD	REVISED -
DATE	-	3/11/2013	REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

			_			L PLAN Antities	
SCALE:	1=20	SHEET	NO.	OF	SHEETS	STA. ·	TC