


| SUMMARY OF QUANTITIES   |  |       |          | FUNDING: 80% FED : 20% STATE |                                      |
|-------------------------|--|-------|----------|------------------------------|--------------------------------------|
| CONSTRUCTION CODE TYPE: |  |       | TOTAL    | 0004                         | 0011                                 |
| CODE NO.                | ITEM   | UNIT  | QUANTITY | ROADWAY                      | SN 098-0044 (EX)<br>SN 098-0119 (PR) |
| 40600982                | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT   | SQ YD | 486      | 486                          |                                      |
| 40603080                | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50    | TON   | 152      | 152                          |                                      |
| 40603310                | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50   | TON   | 290      | 290                          |                                      |
| 40701906                | HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/4" | SQ YD | 1488     | 1488                         |                                      |
| 44000100                | PAVEMENT REMOVAL                               | SQ YD | 146      | 146                          |                                      |
| 44004250                | PAVED SHOULDER REMOVAL                         | SQ YD | 829      | 829                          |                                      |
| 44300200                | STRIP REFLECTIVE CRACK CONTROL TREATMENT       | FOOT  | 1439     | 1439                         |                                      |
| 48102100                | AGGREGATE WEDGE SHOULDER, TYPE B               | TON   | 3        | 3                            |                                      |
| 48203021                | HOT-MIX ASPHALT SHOULDERS, 6"                  | SQ YD | 1311     | 1311                         |                                      |
| 50100100                | REMOVAL OF EXISTING STRUCTURES                 | EACH  | 1        |                              | 1                                    |
| 50200100                | STRUCTURE EXCAVATION                           | CU YD | 268      |                              | 268                                  |
| 50300225                | CONCRETE STRUCTURES                            | CU YD | 61.1     |                              | 61.1                                 |
| 50300255                | CONCRETE SUPERSTRUCTURE                        | CU YD | 210.2    |                              | 210.2                                |
| 50300260                | BRIDGE DECK GROOVING                           | SQ YD | 436      |                              | 436                                  |

141  
SPECIALTY ITEMS

|                       |                    |                               |                        |   |   |                              |                     |                            |                     |                    |                           |
|-----------------------|--------------------|-------------------------------|------------------------|---|---|------------------------------|---------------------|----------------------------|---------------------|--------------------|---------------------------|
| FILE NAME :<br>#FILE# | USER NAME : #USER# | DESIGNED - RAC<br>DRAWN - LCR | REVISED -<br>REVISED - | <b>STATE OF ILLINOIS</b><br><b>DEPARTMENT OF TRANSPORTATION</b> |  Zroka Engineering, P.C.<br>4216 North Homewood<br>Chicago, IL 60643 | <b>SUMMARY OF QUANTITIES</b> | F.A.S. RTE.<br>200  | SECTION<br>141B-2          | COUNTY<br>WHITESIDE | TOTAL SHEETS<br>77 | SHEET NO.<br>6            |
| PLOT SCALE : #SCALE#  | CHECKED - DAZ      | REVISED -                     | SCALE:                 |   |   |                              | SHEET 2 OF 5 SHEETS | STA. 283+43 TO STA. 293+50 | CONTRACT NO. 64D81  |                    | ILLINOIS FED. AID PROJECT |
| PLOT DATE : #DATE#    | DATE - 06-21-13    | REVISED -                     |                        |   |   |                              |                     |                            |                     |                    |                           |