IL 104, CLASS A PAVEMENT PATCHING

LOCATION	LENGTH (FOOT)		FOOT	SQ YD	(SQ YD)						SAW CUTS (FOOT)		TIE BARS (EACH)		PATCHING REINFORCEMENT (SQ YD)	
					TY II	TY III	TY IV	TY II	TY III	TY IV						
ADAMS COUNTY	PASSING	DRIVING	WIDTH	FULL DEPTH	PASSING			DRIVING			PASSING	DRIVING	PASSING	DRIVING	PASSING	DRIVING
IL 104, EASTBOUND																
191+50	5.00		12.00	6.7	6.7						58.0				6.7	
255+00	14.00		12.00	18.7		18.7					76.0				18.7	
377+90	25.00		12.00	33.3			33.3				98.0		13		33.3	
384+12	8.00		12.00	10.7	10.7						64.0				10.7	
395+80	5.00		12.00	6.7	6.7						58.0				6.7	
191+50		10.00	12.00	13.3				13.3				68.0				13.3
377+90		25.00	12.00	33.3						33.3		98.0		13		33.3
395+80		5.00	12.00	6.7				6.7				58.0				6.7
428+30		10.00	12.00	13.3				13.3				68.0				13.3
473+65		6.00	12.00	8.0				8.0				60.0				8.0
IL-104, WESTBOUND																
400+50	5.00		12.00	6.7	6.7						58.0				6.7	
300+00		8.00	12.00	10.7				10.7				64.0				10.7
400+50		10.00	12.00	13.3				13.3				68.0				13.3
TOTAL				181.4	30.8	18.7	33.3	65.3	0.0	33.3	412.0	484.0	13.0	13.0	82.8	98.6

FILE NAME =	USER NAME = $USER$	DESIGNED - DMS	REVISED -
$FILEL$		DRAWN - DMS	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
$MODELNAME$	PLOT DATE = $DATE$	DATE - 5-9-2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: ____ SHEET ___ OF ___ SHEETS STA. ____ TO STA. ____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
745	(103)1-3, (104)1-2	ADAMS	10	4

CONTRACT NO. 72G36

ILLINOIS FED. AID PROJECT