

SUMMARY OF QUANTITIES

90% FED
10% STATE

CONSTRUCTION CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	(25-4)R		(25-4HVB-1)BY			(25-4)BR		
				ROADWAY	ROADWAY	SIGNALS	SN 025-0111 (WB)	SN 025-8648	SN 025-0002	SN 025-0019	SN 025-0062
				0003	0005	LIGHTING 0021	SN 025-0112 (EB) 0010	0040	0014	0014	0014
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	21625	21625							
X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	11035	11035							
X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	2067	2067							
X8040500	RELOCATE ELECTRIC SERVICE	L SUM	1	1							
X8110522	CONDUIT ATTACHED TO STRUCTURE, 2" DIA. STAINLESS STEEL	FOOT	40			40					
X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	23			23					
X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1			1					
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	823			823					
X8730810	ELECTRIC CABLE IN CONDUIT, CONOGA - 30003	FOOT	1830	1830							
X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1			1					
X8360103	LIGHT POLE FOUNDATION, INTERGRAL WITH BARRIER WALL	EACH	8			8					
XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1	0.5					0.5		
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	64					36	8	20	
Z0004552	APPROACH SLAB REMOVAL	SQ YD	843	843							

CITY

*SPECIALTY ITEM REVISD 9-4-2013

FILE NAME : S:\project\408872\SP\Print\SummaryQuantity.dwg	USER NAME : *USER*	DESIGNED - ESW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL	F.A.I RTE. 57/70	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : *SCALE*	CHECKED - BRM	REVISD -	EFFINGHAM			1760	27			
PLOT DATE : *DATE*	DATE - 08-28-09	REVISD -	CONTRACT NO. 74295							
SCALE: SHEET NO. 25 OF 27 SHEETS STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT										

*25-4)R & (25-4HVB-1)BY & (25-4)BR