

PIPE UNDERDRAINS SCHEDULE

LOCATION		CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	CLASS SI CONCRETE (MISCELLANEOUS) (CU YD)	REINFORCING BARS (POUND)	RODENT SHIELDS (EACH)	PIPE DRAINS 4" (FOOT)	PIPE UNDERDRAINS 4" (FOOT)	PIPE UNDERDRAINS 4" (SPECIAL) (FOOT)	PIPE UNDERDRAINS 6" (FOOT)	PIPE UNDERDRAINS 6" (SPECIAL) (FOOT)	REMARKS
STATION TO STATION	SIDE										
NORTH RAMP G											
10+00 TO 14+49	RT		1.5	35.6	1				449	10	PLUG 10+00
14+50 TO 19+13	RT		1.5	35.6	1		462	10			PLUG 14+50
16+55 TO 19+13	LT		1.5	35.6	1		261	10			PLUG 16+55
19+14 TO 23+00	LT/RT						772				PLUGS 23+00
23+01 TO 24+58	LT/RT		3.0	71.2	2		314	20			PLUGS 24+58
I-70 EAST WESTBOUND											
2397+42 TO 2398+25	LT								166		PLUG 2398+25
2398+01 TO 2403+00	RT		1.5	35.6	1			499	10		PLUG 2398+01
2398+26 TO 2403+00	LT		1.5	35.6	1			474	10		PLUG 2398+26
2403+01 TO 2408+00	LT/RT		3.0	71.2	2			998	20		PLUGS 2403+01
2408+01 TO 2413+00	LT/RT		3.0	71.2	2			998	20		PLUGS 2408+01
I-70 EAST EASTBOUND											
2398+01 TO 2403+00	LT/RT		3.0	71.2	2			998	20		PLUGS 2398+01
2403+01 TO 2408+00	LT/RT		3.0	71.2	2			998	20		PLUGS 2403+01
2408+01 TO 2413+00	LT/RT		3.0	71.2	2			998	20		PLUGS 2408+01
SUBTOTAL			0	25.5	605.2	17	0	1809	40	6578	130
SUBTOTALS FROM PREVIOUS PAGE			4	162.0	3844.8	112	476	14125	310	52873	947
TOTAL			4	187.5	4450.0	129	476	15934	350	59451	1077
PAY TOTAL			4	188	4450*	129	476*	15934	350	59451	1077

*NOT A TOTAL QUANTITY

DELINEATORS SCHEDULE

LOCATION			DELINEATORS	
STATION	ROADWAY	SIDE	(EACH)	
2268+00.00 TO 2270+25.50	I-57/70 WB	LT	1	
2274+25.50 TO 2277+10.25	I-57/70 WB	LT	3	
2277+10.25 TO 2291+90.61	I-57/70 WB	LT	14	
2299+86.61 TO 2310+82.77	I-57/70 WB	LT	11	
2315+37.98 TO 2328+51.68	I-57/70 WB	LT	13	
SUBTOTAL			42	
2270+69.45 TO 2274+69.59	I-57/70 EB	RT	4	
2274+69.59 TO 2283+35.33	I-57/70 EB	RT	9	
2297+03.04 TO 2310+49.83	I-57/70 EB	RT	14	
2323+09.69 TO 2330+67.53	I-57/70 EB	RT	7	
2333+92.53 TO 2341+25.32	I-57/70 EB	RT	7	
2341+25.32 TO 2343+65.00	I-57/70 EB	RT	2	
SUBTOTAL			43	
12+48.00 TO 13+48.21	US 45 RAMP A	LT	1	
13+48.21 TO 18+17.59	US 45 RAMP A	LT	15	
18+17.59 TO 20+93.08	US 45 RAMP A	LT	5	
SUBTOTAL			21	
10+00.00 TO 10+71.12	US 45 RAMP B	RT	1	
10+71.12 TO 14+54.93	US 45 RAMP B	RT	4	
14+54.93 TO 19+53.06	US 45 RAMP B	RT	6	
19+53.06 TO 22+23.07	US 45 RAMP B	RT	2	
24+93.63 TO 25+94.66	US 45 RAMP B	RT	1	
25+94.66 TO 27+22.81	US 45 RAMP B	RT	2	
14+54.93 TO 19+53.06	US 45 RAMP B	LT	6	
19+53.06 TO 22+73.06	US 45 RAMP B	LT	3	
SUBTOTAL			25	
14+58.14 TO 16+57.81	US 45 RAMP C	LT	3	
16+57.81 TO 18+02.16	US 45 RAMP C	LT	3	
18+02.16 TO 23+47.16	US 45 RAMP C	LT	18	
23+47.16 TO 25+28.33	US 45 RAMP C	LT	2	
SUBTOTAL			26	
23+99.65 TO 27+39.67	US 45 RAMP D	LT	4	
27+39.67 TO 31+53.34	US 45 RAMP D	LT	5	
16+01.36 TO 17+82.53	US 45 RAMP D	RT	2	
17+82.53 TO 23+99.65	US 45 RAMP D	RT	8	
23+99.65 TO 27+39.67	US 45 RAMP D	RT	4	
27+39.67 TO 32+60.93	US 45 RAMP D	RT	6	
32+60.93 TO 35+60.95	US 45 RAMP D	RT	3	
35+60.95 TO 44+10.77	US 45 RAMP D	RT	9	
SUBTOTAL			41	
2342+13.27 TO 2355+01.91	NRDA	LT	12	
2355+01.91 TO 2356+60.34	NRDA	LT	2	
2356+60.34 TO 2368+53.25	NRDA	LT	12	
2374+89.52 TO 2383+36.93	NRDA	LT	8	
2391+07.76 TO 2398+50.69	NRDA	LT	7	
2345+62.09 TO 2355+01.91	NRDA	RT	9	
2355+01.91 TO 2356+60.34	NRDA	RT	2	
2356+60.34 TO 2368+34.52	NRDA	RT	12	
2375+55.34 TO 2383+60.34	NRDA	RT	8	
2383+60.34 TO 2385+00.69	NRDA	RT	1	
2385+00.69 TO 2386+80.76	NRDA	RT	2	
2391+04.27 TO 2398+50.69	NRDA	RT	7	
SUBTOTAL			82	
2343+65.00 TO 2349+42.48	NRDB	RT	6	
2351+17.48 TO 2352+08.85	NRDB	RT	1	
2352+08.85 TO 2382+22.75	NRDB	RT	30	
2382+22.75 TO 2397+00.73	NRDB	RT	14	
2385+34.22 TO 2397+00.73	NRDB	LT	11	
SUBTOTAL			62	
10+00.00 TO 25+63.29	NRDC	LT	15	
10+00.00 TO 28+85.82	NRDC	RT	19	
28+85.82 TO 39+23.45	NRDC	RT	10	
SUBTOTAL			44	
5342+13.79 TO 5343+81.71	NRDD	LT	2	
5347+69.23 TO 5348+60.24	NRDD	LT	1	
5348+60.24 TO 5354+76.91	NRDD	LT	6	
5354+76.91 TO 5361+49.75	NRDD	LT	6	
5356+82.39 TO 5363+10.71	NRDD	RT	6	
SUBTOTAL			21	

LOCATION			DELINEATORS	
STATION	ROADWAY	SIDE	(EACH)	
7+19.40 TO 10+00.00	N RAMP F	RT	3	
10+00.00 TO 14+52.56	N RAMP F	RT	4	
7+47.89 TO 15+76.21	N RAMP F	LT	2	
10+00.00 TO 15+76.21	N RAMP F	LT	6	
15+76.21 TO 21+92.22	N RAMP F	LT	6	
SUBTOTAL			21	
13+13.73 TO 16+58.88	N RAMP G	RT	3	
16+58.88 TO 17+98.88	N RAMP G	RT	2	
17+98.88 TO 24+57.82	N RAMP G	RT	10	
16+58.88 TO 17+98.88	N RAMP G	LT	2	
17+98.88 TO 24+57.82	N RAMP G	LT	8	
SUBTOTAL			25	
2397+00.73 TO 2400+84.22	I-70 EB	LT	4	
2400+84.22 TO 2401+60.60	I-70 EB	LT	1	
2407+47.99 TO 2413+00.00	I-70 EB	LT	2	
2397+00.73 TO 2401+00.00	I-70 EB	RT	5	
2405+50.30 TO 2413+00.00	I-70 EB	RT	2	
SUBTOTAL			14	
2397+00.73 TO 2401+40.42	I-70 WB	LT	4	
2401+40.42 TO 2406+00.61	I-70 WB	LT	1	
2397+00.73 TO 2401+40.42	I-70 WB	RT	4	
2401+41.42 TO 2406+00.40	I-70 WB	RT	1	
SUBTOTAL			10	
TOTAL			477	

RIPRAP SCHEDULE

LOCATION		STONE RIPRAP CLASS A3 (SQ YD)	STONE RIPRAP CLASS A4 (SQ YD)	STONE RIPRAP CLASS A5 (SQ YD)	FILTER FABRIC (SQ YD)
STATION TO STATION	SIDE				
I-57/70					
2270+94.71 TO 2271+21.00	RT		17		17
2271+39.32 TO 2271+65.40	LT		17		17
2287+50.00 TO 2290+75.00	RT		614		614
2293+90.40 TO 2294+18.06	LT		47		47
2339+80.00 TO 2341+25.00	RT		250		250
I-70					
2404+70.75 TO 2040+92.20	RT		45		45
2406+10.15 TO 2406+30.47	RT		44		44
US 45					
56+52.98 TO 57+16.53	RT		187		187
61+07.91 TO 61+59.06	RT		54		54
61+83.76 TO 63+38.51	RT		533		533
US 45 RAMP A					
14+63.69 TO 16+20.71	RT		723		723
16+88.04 TO 17+11.96	RT		20		20
17+74.56 TO 19+21.77	LT		430		430
19+21.77 TO 19+60.63	LT	96			
US 45 RAMP B					
23+50.00 TO 27+00.00	RT		971		971
US 45 RAMP C					
16+24.15 TO 17+38.13	LT	275			
17+38.13 TO 17+70.00	LT		86		86
US 45 RAMP D					
11+59.95 TO 14+75.00	RT		823		823
16+75.00 TO 18+25.00	RT		344		344
19+45.00 TO 19+61.00	RT		18		18
NORTH TRI ROADWAY A					
2383+01.12 TO 2383+25.24	LT		29		29
2390+43.34 TO 2390+57.53	LT		20		20
2393+00.00 TO 2394+36.00	LT			250	250
NORTH TRI ROADWAY B					
2350+85.49 TO 2351+61.59	LT		191		191
2351+61.59 TO 2352+60.12	LT	218			
2362+95.77 TO 2363+19.01	RT		30		30
2392+91.59 TO 2393+27.14	RT		70		70
2393+16.66 TO 2393+54.61	RT		154		154
2394+84.94 TO 2397+10.61	RT		280		280
NORTH TRI ROADWAY C					
16+71.70 TO 16+90.90	RT		32		32
21+03.02 TO 21+33.43	RT		50		50
24+80.00 TO 26+46.09	RT		365		365
SUBTOTAL		589	6444	250	6694
TOTAL		589	6444	250	6694

FENCE SCHEDULE

LOCATION		WOVEN WIRE FENCE, 4' (FOOT)	CABLE ROAD GUARD REMOVAL (FOOT)
STATION TO STATION	SIDE		
I-57/70			
2326+00.00 TO 2341+50.00	RT	1550	1550
ROADWAY B			
2341+50.00 TO 2360+65.56	RT	1936	1936
TOTAL		3486	3486