



STAGE CONSTRUCTION MANDATORY
LONGITUDINAL CONSTRUCTION
JOINT WITH NO. 6 TIE BARS (TYP.)

LONGITUDINAL SAWED OR
CONSTRUCTION JOINT WITH
NO. 6 TIE BARS (TYP.)

LEGEND

- +--- LONGITUDINAL SAWED OR CONSTRUCTION JOINT WITH NO. 6 TIE BARS (TYP.)
- +--- LONGITUDINAL CONSTRUCTION JOINT WITH NO. 6 TIE BARS (TYP.)
- +--- TRANSVERSE CONTRACTION JOINT AT 15' CENTERS (TYP.)
- WIDE FLANGE BEAM TERMINAL JOINT (SPECIAL)
- +++++ TRANSVERSE EXPANSION JOINT
- LONGITUDINAL KEYED JOINT (WITHOUT TIE BARS)



FILE NAME =
S:\Project\03\000725170.dgn\1\Trk\1\joint_details.dgn

USER NAME = #USER#	DESIGNED - JWS	REVISED -
PLOT SCALE = #SCALE#	DRAWN - PDB	REVISED -
PLOT DATE = #DATE#	CHECKED - BRM	REVISED -
	DATE - 6-29-09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

JOINTING DETAIL, NORTH TRI LEVEL RAMP F

SCALE: 1"=20' SHEET NO. 8 OF 10 SHEETS STA. 16+50.00 TO STA. 21+91.22

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-4R)	EFFINGHAM	1760	363
CONTRACT NO. 74295				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		