

SUMMARY OF QUANTITIES

90% FED  
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				URBAN			(25-4)R		(25-4HVB-1)BY		(25-4)BR	
				ROADWAY 0003	ROADWAY 0005	SIGNALS LIGHTING 0021	SN 025-0111 (WB) 0010	SN 025-8648 0040	SN 025-0002 0014	SN 025-0019 0014	SN 025-0062 0014	
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	222209	222209								
30201250	PROCESSING MODIFIED SOIL 24"	SQ YD	11179	11179								
30201500	LIME	TON	5091.7	5091.7								
30201800	SLAG-MODIFIED PORTLAND CEMENT	TON	845	845								
31200500	STABILIZED SUB BASE - HOT-MIX ASPHALT, 4"	SQ YD	233004	233004								
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2760	2760								
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2661		2661							
40600300	AGGREGATE (PRIME COAT)	TON	54		54							
40600655	LEVELING BINDER (MACHINE METHOD), N105	TON	173		173							
40600990	TEMPORARY RAMP	SQ YD	185		185							
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	954	954								
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	3063		3063							
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	401	401								
40603350	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	197	197								

\* (25-4)R & (25-4HVB-1)BY & (25-4)BR

FILE NAME *	USER NAME * #USER*	DESIGNED - ESW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
5/14/2009 10:27:17 AM		DRAWN - ESW	REVISED -					57/70	*	EFFINGHAM	1760	5		
	PLOT SCALE * #SCALE*	CHECKED - BRM	REVISED -					SCALE:			SHEET NO. 3 OF 27 SHEETS		STA.	TO STA.
	PLOT DATE * #DATE*	DATE - 08-28-09	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 74295						