SUMMARY OF QUANTITIES

90% FED
10% STATE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				(25-4)R			(25-4HVB-1)BY		(25-4)BR		
				ROADWAY 0003	ROADWAY 0005	SIGNALS LIGHTING 0021	SN 025-0111 (WB) SN 025-0112 (EB) 0010	SN 025-8648 0040	SN 025-0002 0014	SN 025-0019 0014	SN 025-0062 0014
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2292.7				2165.1		48.2	79.4	
50300260	BRIDGE DECK GROOVING	SQ YD	7929				7165		693	71	
50300300	PROTECTIVE COAT	SQ YD	8692.3				8367		133.2	192.1	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				1				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	24,530						9,390	9720	5420
50500505	STUD SHEAR CONNECTORS	EACH	20908				20908				
50800105	REINFORCEMENT BARS	POUND	63,020	24550				38,470			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	847,730	1150			809,510	2,680	12480	18210	3700
50800515	BAR SPLICERS	EACH	5583				5466		68	35	14
50800530	MECHANICAL SPLICERS	EACH	806				806				
50900200	STEEL RAILING, TYPE 2399	FOOT	450								450
51100100	SLOPE WALL 4 INCH	SQ YD	4775.4				3251		650.6	863.8	10
51201900	FURNISHING STEEL PILES HP14X89	FOOT	12270				12270				
51202305	DRIVING PILES	FOOT	12270				12270				

*(25-4)R & (25-4HVB-1)BY & (25-4)BR

FILE NAME = S:\Projects\483B07\53-7PI\dgn\IL 54\summary_combined.dgn	USER NAME = $USER$	DESIGNED - ESW	REVISED -
		DRAWN - ESW	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - BRM	REVISED -
	PLOT DATE = $DATE$	DATE - 08-28-09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL

SCALE: | SHEET NO. 7 OF 27 SHEETS | STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	*	EFFINGHAM	1760	9
		CONTRACT NO. 74295		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		