

SUMMARY OF QUANTITIES

90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				URBAN			(25-4)R		(25-4HVB-1)BY		(25-4)BR	
				ROADWAY 0003	ROADWAY 0005	SIGNALS LIGHTING 0021	SN 025-0111 (WB) 0010	SN 025-8648 0040	SN 025-0002 0014	SN 025-0019 0014	SN 025-0062 0014	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	231	231								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2184	2184								
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	114	114								
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	274	274								
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQ FT	1452	1452								
60900515	CONCRETE THRUST BLOCKS	EACH	8	8								
61000335	TYPE G INLET BOX, STANDARD 610001	EACH	1	1								
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	8300	8100								200
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	17	17								
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	13	13								
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4									4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	24	20								4
63200310	GUARDRAIL REMOVAL	FOOT	11533	11124								409
63200400	CABLE ROAD GUARD REMOVAL	FOOT	3486	3486								

* SPECIALTY ITEM

FILE NAME :	USER NAME : #USER#	DESIGNED - ESW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMBINED SUMMARY OF QUANTITIES, NORTH TRI LEVEL	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
5/14/2009 10:27:57 AM		DRAWN - ESW	REVISED -			57/70		EFFINGHAM	1760	14	
		CHECKED - BRM	REVISED -			SCALE:		SHEET NO. 12 OF 27 SHEETS		STA.	TO STA.
		DATE - 08-28-09	REVISED -							CONTRACT NO. 74295	