

SUMMARY OF QUANTITIES

90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				URBAN		(25-4)R			(25-4HVB-1)BY		(25-4)BR		
				ROADWAY 0003	ROADWAY 0005	SIGNALS LIGHTING 0021	SN 025-0111 (WB) 0010	SN 025-8648 0040	SN 025-0002 0014	SN 025-0019 0014	SN 025-0062 0014		
X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	188	188									
X0325379	DIRECTIONAL BORING	FOOT	250	250									
X0325571	TRAFFIC CONTROL SUPERVISOR	CAL DA	650	650									
X0358300	REMOVE AND RELAY END SECTIONS	EACH	4	4									
X4063500	PRELIMINARY TEST STRIP	EACH	1		1								
X4211080	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE (SPECIAL)	EACH	5	5									
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	11546	11546									
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	34044		34044								
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	338	338									
X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	42443	42443									
X4421000	PARTIAL DEPTH PATCHING	TON	257	257									
X4422000	PARTIAL DEPTH REMOVAL (VARIABLE DEPTH)	SQ YD	3913	3913									
X5000015	REMOVE AND RE-INSTALL PIPE CULVERTS	FOOT	158	158									
X5040100	PRECAST BRIDGE APPROACH SLAB	SQ FT	9680				9680						