

SUMMARY OF QUANTITIES

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				BRIDGE 025-0002 0014	BRIDGE 025-0019 0014	BRIDGE 025-0062 0014	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1013.6	434	579.6		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1013.6	434	579.6		
42000540	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	442	442			
42001200	PAVEMENT FABRIC	SQ YD	442	442			
42001300	PROTECTIVE COAT	SQ YD	442	442			
44004250	PAVED SHOULDER REMOVAL	SQ YD	442	442			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	137		137		
50102400	CONCRETE REMOVAL	CU YD	90.7	48.1	42.6		
50104650	SLOPE WALL REMOVAL	SQ YD	1353.6	571	768	14.6	
50157300	PROTECTIVE SHIELD	SQ YD	450	286	164		
50200100	STRUCTURE EXCAVATION	CU YD	37.7	19	9.1	9.6	
50300225	CONCRETE STRUCTURES	CU YD	113.8	48.5	39.8	25.5	
50300254	RUBBED FINISH	SQ FT	377	172	205		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	127.6	48.2	79.4		
50300260	BRIDGE DECK GROOVING	SQ YD	764	693	71		
50300300	PROTECTIVE COAT	SQ YD	325.3	133.2	192.1		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	24490	9350	9720	5420	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	34390	12480	18210	3700	
50800515	BAR SPLICERS	EACH	125	76	35	14	
50900200	STEEL RAILING, TYPE 2399	FOOT	450		450		
51100100	SLOPE WALL 4 INCH	SQ YD	1524.4	650.6	863.8	10	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	409.5	221	188.5		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	46	18	8	20	
52100505	ANCHOR BOLTS, 5/8"	EACH	16		16		
52100520	ANCHOR BOLTS, 1"	EACH	152	72		80	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	32		32		
58700300	CONCRETE SEALER	SQ FT	4675	2332	1304	1039	
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	200		200		
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4		4		
63200310	GUARDRAIL REMOVAL	FOOT	409		409		
67100100	MOBILIZATION	L SUM	0.1		0.1		
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1		1		
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1		1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7	1	1	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	228	228			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	228	228			
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4		4		
78200420	GUARDRAIL MARKERS, TYPE B	EACH	6		6		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4		
X0321778	SEISMIC RESTRAINER	EACH	38	12	16	10	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	0.03	0.01	0.01	0.01	

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				BRIDGE 025-0002 0014	BRIDGE 025-0019 0014	BRIDGE 025-0062 0014	
XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	0.5		0.5		
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	46	18	8	20	
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1			1	
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1			1	
Z0012111	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE OVERLAY, 2 1/2"	SQ YD	658	658			
Z0012144	BRIDGE DECK SCARIFICATION 2 1/2"	SQ YD	658	658			
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	383	178	205		
Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	13.9	10	3.9		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE ID)	SQ YD	27	27			
Z0018800	DRAINAGE SYSTEM	L SUM	0.25		0.25		