

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE: 0040 FUNDING: 80% FED 20% STATE
20200100	EARTH EXCAVATION	CU YD	595
20700220	POROUS GRANULAR EMBANKMENT	CU YD	280
* 25000200	SEEDING, CLASS 2	ACRE	0.25
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2
25100630	EROSION CONTROL BLANKET	SQ YD	503
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	11
28000400	PERIMETER EROSION BARRIER	FOOT	676
28100107	STONE RIPRAP, CLASS A4	SQ YD	66
28200200	FILTER FABRIC	SQ YD	66
40603092	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N90	TON	69
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	10

*SPECIALTY
ITEM

FILE NAME =	USER NAME = walkerr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\walkerr\0326424\783	2-Design\dn	DRAWN -	REVISED -			332	2B-2	WHITE	23	3
Default	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -		SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____					
	PLOT DATE = 5/26/2013	DATE -	REVISED -							