

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FAP 103 (NHPP)	ROADWAY	ROADWAY
				0021 URBAN	0005 URBAN	0005 RURAL
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3,278		394	2,884
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	9		9	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	5,796		668	5,128
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	6	6		
60604500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (ABUTTING EXISTING PAVEMENT)	FOOT	816	816		
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	107	107		
60605300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (MODIFIED)	FOOT	80		80	
66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	1	1		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	31	31		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3		
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	1		
* 66901002	ON-SITE MONITORING OF REGULATED SUBSTANCES	CAL DA	4	4		
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		1	2

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				FAP 103 (NHPP)	ROADWAY	ROADWAY
				0021 URBAN	0005 URBAN	0005 RURAL
67100100	MOBILIZATION	L SUM	1	0.33	0.25	0.42
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.33	0.25	0.42
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		0.25	0.75
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.33	0.25	0.42
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		0.1	0.9
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	18	18		
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	56		56	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	12,074		4,866	7,208
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	4,023		1,622	2,401
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1,227		1,118	109
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	127,148		33,668	93,480
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	83		83	0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,391		1,087	304
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	588		588	0
* 78004350	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - INLAID - LETTERS AND SYMBOLS	SQ FT	1,227		1,118	109

* SPECIALTY ITEM

MODEL: Default
FILE NAME: 76J16 04-5ht-Quan-Summary-01.dgn

REV. - MS

USER NAME = gowens	DESIGNED - GDO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. = 103	SECTION = (27,25,38,56)RS	COUNTY = ST. CLAIR	TOTAL SHEETS = 87	SHEET NO. = 4
PLOT SCALE = 2.0000' / in.	CHECKED - STS	REVISED -					SCALE: 2.0000' / in.	SHEET 2 OF 3 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	
PLOT DATE = 3/22/2019	DATE = 3/22/2019	REVISED -									