

SUMMARY OF QUANTITIES				0005	0021	
Code No.	Item	Unit	Total Quantity	80 % FED 20 % STATE	80 % FED 20 % STATE	
70300251	TEMPORARY PAVEMENT MARKING - LINE 8"- PAINT	FOOT	1458	1458	0	0
70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	3816	3816	0	0
70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	1245	1245	0	0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	444.8	444.8	0	0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27998	27998	0	0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	986	986	0	0
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	486	486	0	0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1272	1272	0	0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	415	415	0	0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	798	798	0	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	639	639	0	0
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	37343	37343	0	0
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	64	0	64	0
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3	0	3	0
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	346	0	346	0
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1325	0	1325	0
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	117	0	117	0
* 87900200	DRILL EXISTING HANDHOLE	EACH	4	0	4	0
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4	0	4	0
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	3	0	3	0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1017	0	1017	0
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	2	0	2	0

SUMMARY OF QUANTITIES				0005	0021	0005
Code No.	Item	Unit	Total Quantity	80 % FED 20 % STATE	80 % FED 20 % STATE	100 % STATE
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	59	0	59	0
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	0	2	0
* 89502376	REBUILD EXISTING HANDHOLE	EACH	2	0	2	0
* X1400378	PEDESTRIAN SIGNAL POST, 5 FT.	EACH	1	0	1	0
X4060995	TEMPORARY RAMP (SPECIAL)	SQ YD	806.5	806.5	0	0
X4400501	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET	FOOT	800	800	0	0
X4400503	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT GREATER THAN 10 FEET	FOOT	4000	4000	0	0
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1200	0	0	1200
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	27	27	0	0
X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	12	12	0	0
X8760200	ACCESSIBLE PEDESTRIAN SIGNALS	EACH	8	0	8	0
X8780012	CONCRETE FOUNDATION, TYPE A 12-INCH DIAMETER	FOOT	20	0	20	0
X03020050	CONSTRUCTION LAYOUT SPECIAL	L SUM	1	1	0	0
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	120	0	0	120
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8	0	0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	0	0

MODEL: SOQ 8 (Sheet)
FILE NAME: c:\pw\work\123022-shl-SOQ.dgn

USER NAME = addis.abeaw	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 6/27/2024	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET OF SHEETS STA. TO STA.

⚠️ REVISED SHEET 9/4/2024

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	FAP 0330 22 RS	COOK	38	4
CONTRACT NO. 62T06			ILLINOIS FED. AID PROJECT	

* SPECIALTY ITEMS

REV-SEP