



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 4, 2024

SUBJECT FAU Route 1332A (Oakton Street)  
Project BR-5I3V(749)  
Section FAU 1332 A 22 BJ  
Cook County  
Contract No. 62T37  
Item No. 8, September 20, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added page 89 to the Special Provisions
4. Revised sheets 4 & 18 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

PERFORMANCE GRADED ASPHALT BINDER (BDE) ..... 72  
PORTLAND CEMENT CONCRETE (BDE) ..... 77  
PERFORMED PLASTIC PAVEMENT MARKING (BDE) ..... 77  
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)..... 78  
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE) ..... 80  
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) ..... 83  
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) ..... 84  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 84  
SUBMISSION OF PAYROLL RECORDS (BDE) ..... 85  
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)..... 86  
WEEKLY DBE TRUCKING REPORTS (BDE) ..... 86  
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) ..... 86  
WORKING DAYS (BDE) ..... 88  
CLEANING EXISTING DRAINAGE STRUCTURES (D1) ..... 89

Revised 9/4/2024

**CLEANING EXISTING DRAINAGE STRUCTURES (D1)**

Effective: September 30, 1985

Revised: May 1, 2022

All existing storm sewers, pipe culverts, manholes, catch basins and inlets shall be considered as drainage structures insofar as the interpretation of this Special Provision is concerned. When specified for payment, the location of drainage structures to be cleaned will be determined in the field by the Engineer.

All existing drainage structures which are to be adjusted or reconstructed shall be cleaned according to Article 602.15 of the Standard Specifications. This work will be paid for according to accordance with Article 602.16 of the Standard Specifications.

All other existing drainage structures which are specified to be cleaned by the Engineer will be cleaned according to Article 602.15 of the Standard Specifications.

Basis of Payment. This work will be paid for at the contract unit price each for DRAINAGE STRUCTURES TO BE CLEANED, and at the contract unit price per foot (meter) for STORM SEWERS TO BE CLEANED, of the diameter specified.

Added 9/4/2024