

SUMMARY OF QUANTITIES				CONSTR. CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FEDERAL 10% STATE ROADWAY	
				0005	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	19010	19010	
<del>40600370</del>	<del>LONGITUDINAL JOINT SEALANT</del>	<del>FOOT</del>	<del>9610</del>	<del>9610</del>	
40600372	LONGITUDINAL JOINT SEALANT, HALF WIDTH	FOOT	19010	19010	
40600990	TEMPORARY RAMP	SQ YD	63	63	
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	1900	1900	
40605034	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 12.5, MIX "E", N80	TON	3300	3300	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	42250	42250	
44200629	CLASS A PATCHES, TYPE I, 15 INCH	SQ YD	4	4	
44200630	CLASS A PATCHES, TYPE II, 15 INCH	SQ YD	70	70	
44200631	CLASS A PATCHES, TYPE III, 15 INCH	SQ YD	62	62	
44200632	CLASS A PATCHES, TYPE IV, 15 INCH	SQ YD	42	42	
44200633	CLASS A PATCHES, TYPE I, 17 INCH	SQ YD	6	6	
44200637	CLASS A PATCHES, TYPE II, 17 INCH	SQ YD	96	96	
44200641	CLASS A PATCHES, TYPE III, 17 INCH	SQ YD	85	85	
44200643	CLASS A PATCHES, TYPE IV, 17 INCH	SQ YD	58	58	

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES				CONSTR. CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FEDERAL 10% STATE ROADWAY	
				0005	
44213000	PATCHING REINFORCEMENT	SQ YD	423	423	
44213200	SAW CUTS	FOOT	2180	2180	
44213204	TIE BARS 3/4"	EACH	125	125	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	130	130	
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	19010	19010	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	14	14	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5150	5150	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	1150	1150	
70300241	TEMPORARY PAVEMENT MARKING - LINE 6" - PAINT	FOOT	21390	21390	

REVISED 9-3-2024

REV - MS

MODEL: SDC (Sheet)  
FILE NAME: c:\pwworkspace\hills\msd59880219\071855-ah-SDC.dgn

USER NAME = laah.hille	DESIGNED - LMH	REVISED -
	DRAWN - LMH	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 6/7/2024	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF  
QUANTITIES

SCALE: NO SCALE SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.I. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(18-45)RS-6	CUMBERLAND	8	3
CONTRACT NO. 74B52				
ILLINOIS FED. AID PROJECT				