

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES					CONSTRUCTION CODE 80% FEDERAL / 20% LOCAL	
SPLTY	Code Number	Description	Unit	Total Quantity	BIKE PATH	TRAINEES
					0028 URBAN	0042 URBAN
*	25200100	SODDING	SQ YD	8800	8800	
*	25200200	SUPPLEMENTAL WATERING	UNIT	480	480	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	360	360	
	28000400	PERIMETER EROSION BARRIER	FOOT	220	220	
	28000510	INLET FILTERS	EACH	44	44	
	28100203	STONE RIPRAP, CLASS A2	TON	14	14	
	28200200	FILTER FABRIC	SQ YD	18	18	
	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	100	100	
	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	830	830	
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	390	390	
	35102100	AGGREGATE BASE COURSE, TYPE B 9"	SQ YD	5000	5000	
	35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	1250	1250	
	40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	13500	13500	
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	4000	4000	
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2	
	40602985	HOT-MIX ASPHALT BINDER COURSE IL-9.5, N70	TON	460	460	△
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	460	460	△

Drawing File: M:\Projects\19-00052-00-01\190225B - 25th Avenue Shared-Use Path Phase II\Summary of Quantities.dwg 2/17/2024 10:47:00am

SHEET PROJECT NO. 120-03-2801

HANCOCK ENGINEERING
 125 Years of Experience
 • Civil Engineers
 • Municipal Consultants
 • Established 1911

9933 Rosewell Road
 Wheeling, IL 60184-2795
 Phone: 708-466-0000
 www.hancock.com

DESIGNED -	MWW, AA	REVISED -	
DRAWN -	DMM, SFB, GD	REVISED -	9-5-24 △
CHECKED -	JGG	REVISED -	9-12-24 △
DATE -	5-17-24	REVISED -	7-17-24

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2714	19-00052-00-BT	COOK	102	5
CONTRACT NO. 61K72			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	