

SUMMARY OF QUANTITIES

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	1000-2A			J000-2A		X27-A2A		Y007		Y030-1E		Y031-1F								Y031-3D			Y032-1F
				SAUNDERS RD / FIELD DR ROADWAY			ROADWAY		IL RTE 60 BRIDGE		RETAINING WALL		LIGHTING		TRAFFIC SIGNALS				EMERGENCY VEHICLE PREEMPTION		TRAFFIC SURVEILLANCE					
				CPQA (FIELD DR.)	OPUS (SAUNDERS RD)	EDP	IL RTE 60/ I-94 RAMP		IL RTE 60 & I-94 RAMP/UNDERPASS					RIVERWOODS RD/BLVD		SAUNDERS RD / FIELD DR		I-94 RAMP/ INTERCONNECT		RIVERWOODS RD/BLVD / I-94 SB RAMP	SAUNDERS RD/ I-94 NB RAMP					
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	100% LAKE COUNTY		
* 50200410	ROCK EXCAVATION FOR STRUCTURES (SPECIAL)	CU YD	150				75	75																		
50300225	CONCRETE STRUCTURES	CU YD	608.0						304.0	304.0																
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1154.0						577.0	577.0																
50300260	BRIDGE DECK GROOVING	SQ YD	3186						1593	1593																
50300280	CONCRETE ENCASEMENT	CU YD	32						16	16																
50300300	PROTECTIVE COAT	SO YD	5362						2681	2681																
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1						0.5	0.5																
50500505	STUD SHEAR CONNECTORS	EACH	13860						6930	6930																
50700207	TREATED TIMBER LAGGING	SQ FT	2053						1026.5	1026.5																
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	310100						155050	155050																
50800515	BAR SPLICERS	EACH	1786						893	893																
50901730	BRIDGE FENCE RAILING	FOOT	529						264.5	264.5																
50901750	PARAPET RAILING	FOOT	295						147.5	147.5																
51100100	SLOPEWALL, 4 INCH	SO YD	1554						777	777																
51201800	FURNISHING STEEL PILES HP 14X73	FOOT	7022						3511	3511																
51202305	DRIVING PILES	FOOT	7022						3511	3511																
51203800	TEST PILE STEEL HP 14X73	FOOT	3						1.5	1.5																
51204650	PILE SHOES	EACH	130						65	65																
51205200	TEMPORARY SHEET PILING	SO FT	3670						1835	1835																
51500100	NAME PLATES	EACH	1						0.5	0.5																
52100540	ANCHOR BOLTS, 1 1/2"	EACH	44						22	22																
542A1063	PIPE CULVERTS, CLASS A, TYPE 2, 18"	FOOT	268				134	134																		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2, 24"	FOOT	71				35.5	35.5																		
542A1075	PIPE CULVERTS, CLASS A, TYPE 2, 30"	FOOT	185				92.5	92.5																		
542A2749	PIPE CULVERTS, CLASS A, TYPE 4, 24"	FOOT	184				92	92																		
542A2761	PIPE CULVERTS, CLASS A, TYPE 4, 36"	FOOT	269				134.5	134.5																		
54213447	END SECTIONS, 12"	EACH	3				1.5	1.5																		
54213450	END SECTIONS, 15"	EACH	4				2	2																		
54213459	END SECTIONS, 24"	EACH	4				2	2																		
54213465	END SECTIONS, 30"	EACH	2				1	1																		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	EACH	12				6	6																		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	2				1	1																		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	EACH	2				1	1																		
54215412	CAST IN PLACE REINFORCED CONCRETE END SECTION - 12"	EACH	3				1.5	1.5																		

* - SPECIALTY ITEM

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 3 OF 12

SCALE: NONE
DATE: MAY 8, 2007
DRAWN BY: CBS
CHECKED BY: MPG

Rev. 8-31-07
Rev. 7-25-07