F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	13
STA. 432+83.12		TO STA. 470+56.84		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60B01

SUMMARY OF QUANTITIES

	IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	I000-2A SAUNDERS RD / FIELD DR ROADWAY CPOA (FIELD DR.) 100% LAKE FOREST	I000-2A OPUS (SAUNDERS RD.) 100% LAKE FOREST	I000-2A EDP 100% LAKE FOREST	J000-2A ROADWAY IL RTE 60/ I-94 RAMPS 80% FEDERAL 20% STATE	J000-2A ROADWAY IL RTE 60/ I-94 RAMPS 100% ISTHA	X2711-2A IL RTE 60 BRIDGE 80% FEDERAL 20% STATE	X2711-2A IL RTE 60 BRIDGE 100% ISTHA	Y007 RETAINING WALL 80% FEDERAL 20% STATE	Y007 RETAINING WALL 100% ISTHA	Y030-1E LIGHTING IL RTE 60 & I-94 RAMPS/UNDERPASS 80% FEDERAL 20% STATE	Y030-1E LIGHTING IL RTE 60 & I-94 RAMPS/UNDERPASS 100% ISTHA	Y031-1F TRAFFIC SIGNALS RIVERWOODS RD/BLVD 80% FEDERAL 20% STATE	Y031-1F RIVERWOODS RD/BLVD 100% ISTHA	Y031-1F RIVERWOODS RD/BLVD 100% METTAWA	Y031-1F RIVERWOODS RD/BLVD 100% LAKE COUNTY	Y031-1F SAUNDERS RD / FIELD DR 80% FEDERAL 20% STATE	Y031-1F SAUNDERS RD / FIELD DR 100% ISTHA	Y031-1F SAUNDERS RD / FIELD DR 100% LAKE FOREST	Y031-1F I-94 RAMPS/ INTERCONNECT 80% FEDERAL 20% STATE	Y031-1F I-94 RAMPS/ INTERCONNECT 100% ISTHA	Y031-3D EMERGENCY VEHICLE PREEMPTION RIVERWOODS RD/BLVD / I-94 SB RAMPS 100% LIBERTY-VILLE F.D.	Y031-3D EMERGENCY VEHICLE PREEMPTION RIVERWOODS RD/BLVD / I-94 SB RAMPS 100% LINCOLN-SHIRE F.D.	Y031-3D EMERGENCY VEHICLE PREEMPTION SAUNDERS RD/ I-94 NB RAMPS 100% LAKE FOREST	Y032-1F TRAFFIC SURVEILLANCE 100% LAKE COUNTY
*	84200800	POLE FOUNDATION, REMOVED	EACH	15										0.5	14.5												
*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1										0.5	0.5												
*	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1											1												
*	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1											1												
*	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1											1												
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1																0.45	0.45	0.10					
*	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET (SPECIAL)	EACH	2																			1	1			
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	3																0.45	0.45	0.10	1	1			
*	87100160	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F	FOOT	11415																			5269	5269			877
*	87301205	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 1C	FOOT	4819																			2409.5	2409.5			
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2652 △1											△1	285.75	285.75	31.75	31.75						378.5	378.5	807	453
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2838 △1											△1									△1	672.50	672.50	1040	453
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	10,612 △1											△1	1423.35	1423.35	158.15	158.15	2665.35	2665.35	592.3	4763	4763				
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2519 △1											△1	391.95	391.95	43.55	43.55				824	824				
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	23,868 △1											△1	2704.95	2704.95	300.55	300.55	2792.25	2792.25	620.5	5825	5825				
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	169																14.4	14.4	3.2	68.5	68.5				
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14FT.	EACH	10																			5	5				
△1 *	~~87502500~~	~~TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.~~	~~EACH~~	~~1~~												~~0.45~~	~~0.45~~	~~0.05~~	~~0.05~~									
*	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2																			1	1				
*	87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1																			0.5	0.5				
*	87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1																0.45	0.45	0.1						
*	87700200	STEEL MAST ARM ASSEMBLY AND POLE , 32 FT.	EACH	1																0.45	0.45	0.1						
*	87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1																			0.5	0.5				
*	87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1																			0.5	0.5				
*	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	3																0.45	0.45	0.1	1	1				
*	87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	3																0.9	0.9	0.2	0.5	0.5				
*	87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT	EACH	3												0.45	0.45	0.05	0.05	0.9	0.9	0.2						
△1 *	~~87700320~~	~~STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.~~	~~EACH~~	~~1~~																~~0.45~~	~~0.45~~	~~0.1~~						
*	87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1												0.45	0.45	0.05	0.05									
*	87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1												0.45	0.45	0.05	0.05									
△1 *	87704405	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS 34 FT. AND 55 FT.	EACH	1												0.45	0.45	0.05	0.05									
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	60 △1																			28	28				
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8																			4	4				
*	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4																1.8	1.8	0.4						

* - SPECIALTY ITEM

△1 8-31-07

TY·LIN INTERNATIONAL

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 9 OF 12

SCALE: NONE DRAWN BY: CBS
DATE: MAY 8, 2007 CHECKED BY: MPG