F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	8
STA. 432+83.12		TO STA. 470+56.84		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60B01

SUMMARY OF QUANTITIES

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	I000-2A			J000-2A		X271-2A		Y007		Y030-1E		Y031-1F										Y031-3D			Y032-1F
				SAUNDERS RD / FIELD DR ROADWAY			ROADWAY						LIGHTING		TRAFFIC SIGNALS										EMERGENCY VEHICLE PREEMPTION			
				CPOA (FIELD DR.)	OPUS (SAUNDERS RD.)	EDP	IL RTE 60/ I-94 RAMPS		IL RTE 60 BRIDGE		RETAINING WALL		IL RTE 60 & I-94 RAMPS/UNDERPASS		RIVERWOODS RD/BLVD			SAUNDERS RD / FIELD DR			I-94 RAMPS/ INTERCONNECT				RIVERWOODS RD/BLVD / I-94 SB RAMPS		SAUNDERS RD/ I-94 NB RAMPS	TRAFFIC SURVEILLANCE
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% METTAWA	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LIBERTY-VILLE F.D.	100% LINCOLN-SHIRE F.D.	100% LAKE FOREST	100% LAKE COUNTY
54215448	CAST IN PLACE REINFORCED CONCRETE END SECTION - 48"	EACH	1				0.5	0.5																				
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	636		247	389																						
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	55				27.5	27.5																				
550A0120	STORM SEWERS, CLASS A, TYPE 1, 24"	FOOT	7				3.5	3.5																				
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	2832		228		1302	1302																				
550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	518		8		255	255																				
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	209		209																							
550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	327				163.5	163.5																				
550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	184				92	92																				
550A0450	STORM SEWERS, CLASS A, TYPE 2, 36"	FOOT	425				212.5	212.5																				
550A0480	STORM SEWERS, CLASS A, TYPE 2, 48"	FOOT	140				70	70																				
550A0710	STORM SEWERS, CLASS A, TYPE 3, 24"	FOOT	245				122.5	122.5																				
550A1050	STORM SEWERS, CLASS A, TYPE 4, 36"	FOOT	314				157	157																				
550A1080	STORM SEWERS, CLASS A, TYPE 4, 48"	FOOT	116				58	58																				
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2, 12"	FOOT	148				74	74																				
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2, 15"	FOOT	62				31	31																				
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	164		60		52	52																				
55100500	STORM SEWER REMOVAL 12"	FOOT	789			424	182.5	182.5																				
55100900	STORM SEWER REMOVAL 18"	FOOT	15				7.5	7.5																				
55101100	STORM SEWER REMOVAL 21"	FOOT	10				5	5																				
55101600	STORM SEWER REMOVAL 36"	FOOT	420				210	210																				
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	1		1																							
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2		2																							
58700300	CONCRETE SEALER	SQ FT	4730						2365	2365																		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	286						143	143																		
59300100	CONTROLLED LOW STRENGTH MATERIAL	CU YD	181				90.5	90.5																				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	7				1.5	1.5	2	2																		
60107700	PIPE UNDERDRAIN 6"	FOOT	1789				894.5	894.5																				
60108200	PIPE UNDERDRAIN 6" (SPECIAL)	FOOT	194				97	97																				
60109582	PIPE UNDERDRAINS FOR STRUCTURES, 6"	FOOT	1189						189.5	189.5	405	405																
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	72			3	34.5	34.5																				
60205010	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	1				0.5	0.5																				
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	9				4.5	4.5																				

* - SPECIALTY ITEM

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 4 OF 12

SCALE: NONE DRAWN BY: CBS

DATE: MAY 8, 2007 CHECKED BY: MPG