

PROPOSED SIGNING SCHEDULE

SIGN NO.	ALIGNMENT	SIGN INFORMATION								SUPPORT INFORMATION					SIGN DESCRIPTION	
		EX. STATION	OFFSET	PROP. STATION	OFFSET	TYPE	WIDTH (FT)	HEIGHT (FT)	AREA (FT)	TYPE	POST QUANTITY	POST LENGTH (FT)	BASE FOR TELES. STEEL (EACH)	STRUCTURAL STEEL SIGN SUPPOR-BREAKAWAY (POUND)		CONCRETE FOUNDATIONS (CY)
	ILLINOIS 60			432+92.4	54.1' LT	2	6	2.5	15	MAST ARM						RIVERWOODS RD (LEFT ARROW)/RIVERWOODS BLVD (RIGHT ARROW)
	ILLINOIS 60			433+96.3	107.5' LT	1	2	2.5	5	TELESCOPING STEEL	1	14.5	1			R4-7
	ILLINOIS 60			434+29.3	114.9' RT	1	2	2	4	TELESCOPING STEEL	1	16				M1-I100 ("ILLINOIS 60")
				SAME AS ABOVE		1	3	0.75	2.25							Townline RD
				SAME AS ABOVE		1	1.75	1.25	2.1875							M6-4
	ILLINOIS 60			434+34.4	116.1' RT	1	2	2	4	TELESCOPING STEEL	1	15				M1-5 ("LAKE COUNTY, W24")
				SAME AS ABOVE		1	2	1	2							M4-6
	ILLINOIS 60			434+33.9	129.6' LT	1	1.5	2	3	TELESCOPING STEEL	1	17.5				R2-1 (30)
				SAME AS ABOVE		1	2	2	4							R5-2
				SAME AS ABOVE		1	2	1.5	3							"TRUCK TRAFFIC PROHIBITED ON BRADLEY RD"
	ILLINOIS 60			434+80.0	6.0' RT	1	2	2.5	5	TELESCOPING STEEL	1	15				R4-7
	ILLINOIS 60			SAME AS ABOVE		1	2.5	3	7.5	TELESCOPING STEEL						R3-5L
	ILLINOIS 60			434+35.9	100.4' RT	1	2	2.5	5	SIGNAL POST						R10-5
	ILLINOIS 60			434+45.5	95.5' LT	1	2	2.5	5	MAST ARM						R10-5
				SAME AS ABOVE		1	5	1.5	7.5							ILL RTE 60
				SAME AS ABOVE		1	5	1.5	7.5							ILL RTE 60
	ILLINOIS 60			434+85.4	67.3' LT	1	2	2	4	SIGNAL POST						M1-5 ("LAKE COUNTY, W24")
				SAME AS ABOVE		1	3	0.75	2.25							"Riverwoods RD"
				SAME AS ABOVE		1	1.75	1.25	2.1875							M6-1L
	ILLINOIS 60			434+65.1	72.2' LT	1	2	2.5	5	MAST ARM						R10-5
	ILLINOIS 60			434+94.8	69.5' RT	1	2	2.5	5	MAST ARM						R10-5
				SAME AS ABOVE		2	6	2.5	15							RIVERWOODS BLVD (LEFT ARROW)/RIVERWOODS RD (RIGHT ARROW)
	ILLINOIS 60			435+36.4	67.4' LT	1	2	2	4	TELESCOPING STEEL	1	15.5				R5-2
				SAME AS ABOVE		1	2	1.5	3							"NORTHBOUND RIVERWOODS BLVD EXCEPT DELIVERIES"
				SAME AS ABOVE		1	2	2.5	5							"SAINT BASIL S.O. CHURCH"
	ILLINOIS 60			436+38.6	70.4' RT	1	2.5	2.5	6.25	TELESCOPING STEEL	1	14.5				R3-7R
	ILLINOIS 60			436+83.0	79.1' RT	3	9.5	10.5	99.75	BREAKAWAY POST			720	1.4		I-94 NORTH TOLLWAY WISCONSIN (THRU ARROW)
																I-94 SOUTH TOLLWAY INDIANA (RIGHT ARROW)
	ILLINOIS 60			437+24.1	74.6' RT	1	2	1	2	WOOD SIGN SUPPORT	1	17.25				M3-1
				SAME AS ABOVE		1	2	1	2							M4-I100
				SAME AS ABOVE		1	2	2	4							M1-1 (94)
				SAME AS ABOVE		1	1.75	1.25	2.1875							M6-1
	ILLINOIS			437+24.1	74.6' RT	1	2	1	2	WOOD SIGN SUPPORT	1	17.25				M3-3
				SAME AS ABOVE		1	2	1	2							M4-I100
				SAME AS ABOVE		1	2	2	4							M1-1 (94)
				SAME AS ABOVE		1	1.75	1.25	2.1875							M6-3
	ILLINOIS 60			437+98.3	72.5' LT	1	3	3	9	TELESCOPING STEEL	1	15				I-I107 "ADOPT A HIGHWAY AVAILABLE"
				SAME AS ABOVE		1	3	3	9							W21-I111 "CLEANUP CREW WORKING" (FOLDING SIGN)
	ILLINOIS 60			438+94.7	71.3' LT	1	2	2	4	TELESCOPING STEEL	1	15.5				R5-2
				SAME AS ABOVE		1	2	1.5	3							"NORTHBOUND RIVERWOODS BLVD EXCEPT DELIVERIES"
	ILLINOIS 60			439+32.0	68.8' LT	1	1.75	1.25	2.1875	TELESCOPING STEEL	1	17.25				M2-1
				SAME AS ABOVE		1	2	2	4							M1-5 ("LAKE COUNTY, W24")
				SAME AS ABOVE		1	3	0.75	2.25							"Riverwoods RD"
				SAME AS ABOVE		1	1.75	1.25	2.1875							M5-1L
	ILLINOIS 60			440+19.5	98.0' LT	2	4	4	16	WOOD SIGN SUPPORT	1	16				R5-1
	ILLINOIS 60			440+67.2	72.1' LT	1	3	1	3	MAST ARM						R6-1 (LEFT)
	ILLINOIS 60			441+01.2	10.2' LT	1	2	2.5	5	TELESCOPING STEEL	1	14.5				R4-7
	ILLINOIS 60			441+19.5	67.7' RT	1	1.5	2	3	TELESCOPING STEEL	1	14				W1-8
	ILLINOIS 60			441+24.3	94.9' LT	2	4	4	16	WOOD SIGN SUPPORT	1	16				R5-1
	ILLINOIS 60			441+97.3	69.5' LT	1	2	2	4	WOOD SIGN SUPPORT	1	14				R3-1
	ILLINOIS 60			442+08.3	0.11' LT	1	2.5	2.5	6.25	TELESCOPING STEEL	1	9.5	1			R3-8 (MODIFIED)
				SAME AS ABOVE		1	2	2.5	5							R4-7
	ILLINOIS 60			441+25.0	85.2' RT	3	7.5	6.5	48.75	BREAKAWAY POST			333	1.4		I-94 SOUTH TOLLWAY INDIANA (RIGHT ARROW)
				SAME AS ABOVE		3	7.5	6.5	48.75							I-94 SOUTH TOLLWAY INDIANA (LEFT ARROW)
	ILLINOIS 60			442+25.8	75.7' RT	1	2	1	2	WOOD SIGN SUPPORT	1	17.25				M3-1

NOTES:

- ALL RELOCATION WORK ON THIS SCHEDULE IS GOVERNED BY ARTICLE 107.25 UNLESS NOTED.
- REFER TO PROPOSED SIGNING PLANS FOR PROPOSED SIGN LOCATIONS.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS RTE 60 OVER I-94
PROPOSED SIGNING SCHEDULE
1 OF 3

SCALE: NONE DRAWN BY: CBS
DATE: MAY 8, 2007 CHECKED BY: AMB