


CONTRACT NO. 60B82

| | | | | |
|---------------------|-----------|------------------|--------------|-----------|
| F.A.U. ROUTE NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1320 | 581EXT-BR | COOK | 46 | 4 |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

SUMMARY OF QUANTITIES *URBAN*
100-1 STATE

| ENGLISH | PAY ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | IL 58 1000 | IL 59 1000 | BRIDGE X081-2A |
|----------|---|-------|----------------|------------|------------|----------------|
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 2,865 | 1,300 | 1,565 | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 326 | 182 | 144 | |
| 70300520 | PAVEMENT MARKING TAPE, TYPE III 4" | FOOT | 949 | 949 | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 278 | 278 | | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 255 | 255 | | |
| 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 146 | 73 | 73 | |
| 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 3,835 | 1,807 | 2,028 | |
| 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 1,433 | 650 | 783 | |
| 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 163 | 91 | 72 | |
| 78008210 | POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | FOOT | 438 | 438 | | |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 92 | 43 | 49 | |
| 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 9 | 9 | | |
| 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 11 | 11 | | |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 2 | 2 | | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 101 | 52 | 49 | |
| 81000600 | CONDUIT IN TRENCH, 2" DIA, GALVANIZED STEEL | FOOT | 190 | 190 | | |
| 81018500 | CONDUIT PUSHED, 2" DIA, GALVANIZED STEEL | FOOT | 155 | 155 | | |
| 81100600 | CONDUIT ATTACHED TO STRUCTURE, 2" DIA, GALVANIZED STEEL | FOOT | 96 | 96 | | |
| 81100700 | CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA, GALVANIZED STEEL | FOOT | 96 | 96 | | |
| 81400100 | HANDHOLE | EACH | 1 | 1 | | |
| 81400200 | HEAVY DUTY HANDHOLE | EACH | 3 | 3 | | |
| 81603040 | UNIT DUCT, 600V, 2-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA POLYETHYLENE | FOOT | 389 | 389 | | |
| 81800330 | AERIAL CABLE, 3-1/C NO 6 WITH MESSENGER WIRE | FOOT | 360 | 360 | | |
| 82057350 | LIGHT POLE, WOOD, 60 FOOT, CLASS 4 | EACH | 1 | 1 | | |
| 87301305 | ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR | FOOT | 395 | 395 | | |
| 87900200 | DRILL EXISTING HANDHOLE | EACH | 4 | 4 | | |
| 88600100 | DETECTOR LOOP, TYPE I | FOOT | 639 | 639 | | |
| 89000100 | TEMPORARY TRAFFIC SIGNAL INSTALLATION | EACH | 1 | | 1 | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 102 | 51 | 51 | |
| X0325303 | STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5") | SQ FT | 14 | | | 14 |
| X0325305 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5") | SQ FT | 248.5 | | | 248.5 |
| X0712400 | TEMPORARY PAVEMENT | SQ YD | 366 | 366 | | |
| X5030305 | CONCRETE WEARING SURFACE, 5" | SQ YD | 754.4 | | | 754.4 |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 0.2 | 0.2 | 0.6 |
| Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 3 | | 3 | |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3 | EACH | 2 | 2 | | |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3 | EACH | 2 | 2 | | |
| Z0037100 | TEMPORARY WALL BRACING SYSTEM | L SUM | 1 | | | 1 |

* SPECIALTY ITEMS

| | | |
|--|------|--|
| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION FAU 1320 (IL 58 GOLF ROAD) OVER POPLAR CREEK SUMMARY OF QUANTITIES DATE: 7/20/07 DRAWN BY: LT CHECKED BY: RS |
| NAME | DATE | |
| | | |
| | | |
| | | |
|  GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC. CHICAGO, ILLINOIS | | |