

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3528	2001-143RS	COOK	20	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT # 62322

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		80% FED. 20% STATE 1000	80% FED. 10% STATE 10% CHICAGO Y025 (PARKING)	80% FED. 20% STATE SFTY-2A SN 016-0610	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	8	2		
40600300	AGGREGATE (PRIME COAT)	TON	45	39	6		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	6	1		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	331	331			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	83	83			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1928	1610	246	72	
42001300	PROTECTIVE COAT	SQ YD	450	450			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	852			852	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	21895	19028	2867		
44000915	<del>HOT-MIX ASPHALT SURFACE REMOVAL (DECK)</del>	<del>SQ YD</del>	<del>852</del>			<del>852</del>	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1000	1000			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	657	657			
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	6	6			
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	510	510			
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	10	10			
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	21	21			
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4			
60262900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		80% FED. 20% STATE 1000	80% FED. 10% STATE 10% CHICAGO Y025 (PARKING)	80% FED. 20% STATE SFTY-2A SN 016-0610	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2705	2705			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6919	6919			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1977	1977			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4801	4801			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	254	254			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	915	915			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6919	6919			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1977	1977			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4801	4801			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	254	254			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
X0322748	BICYCLE LANE MARKING	EACH	20	20			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	945	824	121		
XX001306	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	1000	1000			
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	74	58	16		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
© Z0076600	TRAINEES	HOUR	1000	1000			

7/23/2007 10:50:00 AM session: qd.dcn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
ELSTON AVENUE

© Y880  
NP = NON-PARTICIPATING  
REV.

PLOT DATE: 7/23/2007