

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	COOK	52	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
* (0101,0203B & 0303) RS-10				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN COOK CO. IL-394 STATE 100% 1000	IL-394 OVER EJE R.R. X631-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	915	915					
21400100	GRADING AND SHAPING DITCHES	FOOT	1400	1400					
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	29.4	29.4					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18.2	18.2					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12.6	12.6					
25100630	EROSION CONTROL BLANKET	SQ YD	1583	1583					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	82	82					
40600300	AGGREGATE (PRIME COAT)	TON	402	402					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	61	61					
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	940	940					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	386	386					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	567	567					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	8305	8305					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7410	7410					
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	65900	65900					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	111240	111240					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	22305	22305					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1682	1682					
44002218	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4 1/2"	SQ YD	751	751					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1073	1073					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	180	180					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN COOK CO. IL-394 STATE 100% 1000	IL-394 OVER EJE R.R. X631-2A				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	826	826					
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	355	355					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2421	2421					
60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	2	2					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	637	637					
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2					
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2					
63200310	GUARDRAIL REMOVAL	FOOT	150	150					
64200105	SHOULDER RUMBLE STRIP	FOOT	69760	69760					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1					
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1					
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	93,685	93,685					
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	9,361	9,361					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3030	3030					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2860	2860					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	990	990					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	245,230	245,230					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	728	728					

* SPECIALTY ITEMS

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 IL ROUTE 394
 FROM JOE ORR RD TO STEGER RD