

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	"	COOK	54	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
* (0101,0203B & 0303) RS-10				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN COOK CO. IL-394 STATE 100% 1000	IL-394 OVER EJE R.R. X631-2A				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	606	606					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4180	4180					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	728	728					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	91405	91405					
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	9076	9076					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3030	3030					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2860	2860					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	990	990					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	606	606					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	900	900					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	510	510					
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	10	10					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3361	3361					
X0320887	POLYMER CONCRETE	CU FT	14.5		14.5				
X0321744	SILICONE JOINT SEALER, 2"	FOOT	172		172				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	128	128					
X0322729	MATERIAL TRANSFER DEVICE	TON	25,590	25,590					
X4063000	PRELIMINARY TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2					
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	12795	12795					
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	12795	12795					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN COOK CO. IL-394 STATE 100% 1000	IL-394 OVER EJE R.R. X631-2A				
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	60	60					
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	30		30				
Z0014800	CULVERT TO BE CLEANED	FOOT	1225	1225					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	19	19					
Z0037620	PAVEMENT RELIEF JOINT, REMOVE AND REPLACE	SQ FT	3195	3195					
78300105	PAVEMENT MARKING REMOVAL	FOOT	790	790					
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10					
78006110	PERFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	700	700					
78006120	PERFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	88	88					

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 IL ROUTE 394  
 FROM JOE ORR RD TO STEGER RD

Rev.

7/18/2007 11:41:18 AM I:\2005\2042\204206.dwg