

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2003-106LS	COOK	59	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 62699				

SEEDING CL 4 (M2500310)

STATION	STATION	AREA (SQ M)	HECTARE
*****			
LSM-16A			0.01
GATEWAY DETAIL			
TOTAL =			0.1

MOWING (M2500750)

STATION	WIDTH(m)	STATION	WIDTH(m)	HECTARE
*****				
NOMINAL QUANTITY				21.0
TOTAL =				21.0

INTERSEEDING CL 4 (M2503310)

STATION	STATION	AREA (SQ M)	HECTARE	
*****				
NOMINAL QUANTITY				0.20
TOTAL =				0.2

EROSION CONTR BLANKET (M2510630)

STATION	WIDTH(m)	STATION	WIDTH(m)	SQ METER
*****				
NOMINAL QUANTITY				5,000.0
LSM-16A				70.0
TOTAL =				5,070

MULCH PLACEMENT 100 (MX032651)

STATION	OFFSET	STATION	OFFSET	SQ METER
*****				
LSNS-29				
I-94				
30+567		- 30+245		290.0
LSNS-34				
19+816.000 RT		- 19+760.000 RT		175.0
LS170-40 RT				
MULCH BEDS AND MULCH RINGS				150.0
LSM-13				
MULCH RINGS AT TREES 8SQM X 4EA				32.0
6+450.000 LT				
TOTAL =				647

PERENNIAL PLANT CARE (MX032675)

STATION	OFFSET	STATION	OFFSET	SQ METER
*****				
NOMINAL QUANTITY				480 X 3CYCLES= 1,440.0
TOTAL =				1440

WEED CONTR PRE-EM GRN (MX032680)

STATION	OFFSET	STATION	OFFSET	SQ METER
*****				
RATE				112 KG / HA
2442.0 SQ M				2.44HA
TOTAL =				274
				274

WEED CONT N SEL/N RES (MX033189)

STATION	OFFSET	STATION	OFFSET	SQ M	LITER
*****					
RATE = 0.022467 LITER / m <sup>2</sup>					
LSM-9					
50+075.000		- 50+090.000		40.00	0.90
LSM-16					
7+600.000		- 7+950.000		160.00	3.59
LS83-19					
50+105.000		- 50+120.000		40.00	0.90
LSNS-29					
30+567		- 30+245.000		290.00	6.52
LSNS-33					
19+600.000		- 19+625.000		20.00	0.45
19+675.000		- 19+700.000		20.00	0.45
19+760.000		- 19+785.000		20.00	0.45
19+840.000		- 19+865.000		20.00	0.45
LSNS-35					
19+250.000		- 19+275.000		20.00	0.45
19+340.000		- 19+365.000		20.00	0.45
19+425.000		- 19+450.000		20.00	0.45
19+515.000		- 19+540.000		20.00	0.45
LSNS-36					
18+960.000		- 18+985.000		20.00	0.45
19+060.000		- 19+085.000		20.00	0.45
19+170.000		- 19+195.000		20.00	0.45
LSNS-37					
18+650.000		- 18+675.000		20.00	0.45
18+750.000		- 18+775.000		20.00	0.45
18+860.000		- 18+885.000		20.00	0.45
LSNS-38					
0+000.000		- 0+025.000		20.00	0.45
LS170-39					
350+025.000		- 350+050.000		45.00	1.01
89+825.000		- 89+850.000		12.00	0.27
TOTAL =					20

COARSE SAND PLACE 100 (MX033323)

STATION	OFFSET	STATION	OFFSET	SQ METER	
*****					
LSM-9					
50+075.000		- 50+090.000		0.000	
40.00					
LS83-19					
50+105.000		- 50+120.000		0.000	
40.00					
LSNS-33					
19+600.000		- 19+625.000		20.00	
19+675.000		- 19+700.000		20.00	
19+760.000		- 19+785.000		20.00	
19+840.000		- 19+865.000		20.00	
LSNS-35					
19+250.000		- 19+275.000		20.00	
19+340.000		- 19+365.000		20.00	
19+425.000		- 19+450.000		20.00	
19+515.000		- 19+540.000		20.00	
LSNS-36					
18+960.000		- 18+985.000		20.00	
19+060.000		- 19+085.000		20.00	
19+170.000		- 19+195.000		20.00	
LSNS-37					
18+650.000		- 18+675.000		20.00	
18+750.000		- 18+775.000		20.00	
18+860.000		- 18+885.000		20.00	
LSNS-38					
0+000.000		- 0+025.000		20.00	
LS170-39					
350+025.000		- 350+050.000		45.00	
89+825.000		- 89+850.000		12.00	
TOTAL =					437.0

PERENNIAL PLT-GAL POT (X0301407)

SHEET	OFFSET	UNIT
*****		
LSM-16A	RT	2.0
LSNS-35	RT	5.0
LSNS-36	RT	5.0
LSNS-37	RT	2.0
LSNS-38	RT	5.0
LS170-39	RT	0.5
LS170-39	LT	2.0
TOTAL =		21.5

CONSTRUCTION LAYOUT (Z0013798)

L SUM	
*****	
NOMINAL QUANTITY	1.0
TOTAL =	

06/27/2007 8:53:39 AM E:\Project\20140801\CADD\Contract\AWB\lsch001.ras

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-80/94/US 6  
KINGERY-BORMAN EXPRESSWAY  
BURNHAM ROAD TO US 41  
LANDSCAPING PLAN  
SCHEDULE OF QUANTITIES

SCALE 1:500 DRAWN BY ACE/CAD  
DATE 06/07 CHECKED BY TJW

**AMERICAN**  
CONSULTING ENGINEERS

REVISIONS	
NAME	DATE