

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
533	2004-117 RS	MCHENRY	26	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY I000-2A					
20200100	EARTH EXCAVATION	CU YD	53	53					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	368	368					
20400800	FURNISHED EXCAVATION	CU YD	16	16					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	431	431					
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10					
25100630	EROSION CONTROL BLANKET	SQ YD	431	431					
25200200	SUPPLEMENTAL WATERING	UNIT	6	6					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10					
28000300	TEMPORARY DITCH CHECKS	EACH	30	30					
28000400	PERIMETER EROSION BARRIER	FOOT	355	355					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	240	240					
35600704	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	SQ YD	240	240					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	11	11					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19					
40600300	AGGREGATE (PRIME COAT)	TON	95	95					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	5	5					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	262	262					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	35	35					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	5740	5740					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE "C", N50	TON	90	90					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3830	3830					
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	875	875					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	45,550	45,550					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	200	200					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	200	200					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	16,800	16,800					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1472	1472					

\* - SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY I000-2A					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10300	10300					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41,500	41,500					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	340	340					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	18	18					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	18206	18206					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	10	10					
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	41,500	41,500					
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	340	340					
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	18	18					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8					
* XX006257	RECESSED REFLECTIVE PAVMENT MARKER	EACH	273	273					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev. 9-4-07

PLOT DATE: 7/20/2007