

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(2HB-2, 2HB-1)D	WINNEBAGO	107	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ITEM CODE	PAY ITEM	UNIT	1000 ROADWAY QUANTITY	X271-2A STRUCTURE QUANTITY	80% FED 20% STATE TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1180		1180
<b>20100110</b>	<b>TREE REMOVAL (6 TO 15 INETS DIAMETER)</b>	<b>UNIT</b>	<b>12</b>		<b>12</b>
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD		527	527
25000210	SEEDING, CLASS 2A	ACRE	0.5		0.5
25100115	MULCH, METHOD 2	ACRE	0.5		0.5
25100630	EROSION CONTROL BLANKET	SQ YD	2420		2420
<b>25301500</b>	<b>TREES</b>	<b>EACH</b>	<b>2</b>		<b>2</b>
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300		300
28000300	TEMPORARY DITCH CHECKS	EACH	10		10
28000400	PERIMETER EROSION BARRIER	FOOT	2700		2700
28000500	INLET AND PIPE PROTECTION	EACH	2		2
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	4626		4626
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N80	TON	<b>887</b>		<b>887</b>
40600962	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	320		320
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	538		538
40803570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N80	TON	406		406
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	1040		1040
42001300	PROTECTIVE COAT	SQ YD	1248		1248
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (POC)	SQ YD	208		208
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	4827		4827
44000700	APPROACH SLAB REMOVAL	SQ YD	427		427
44004250	PAVED SHOULDER REMOVAL	SQ YD	2816		2816
48203020	HOT-MIX ASPHALT SHOULDERS, 5 3/4"	SQ YD	4224		4224
50102400	CONCRETE REMOVAL	CU YD		200.3	200.3
50104850	SLOPE WALL REMOVAL	SQ YD		2509	2509
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH		4	4
<b>50157300</b>	<b>PROTECTIVE SHIELD</b>	<b>SQ YD</b>		<b>1176</b>	<b>1176</b>
50200100	STRUCTURE EXCAVATION	CU YD		<b>907.3</b>	<b>907.3</b>
50300225	CONCRETE STRUCTURES	CU YD		351.6	351.6
50300255	CONCRETE SUPERSTRUCTURES	CU YD		875.6	875.6
50300260	BRIDGE DECK GROOVING	SQ YD		2648	2648
50300280	CONCRETE ENCASEMENT	CU YD		8.4	8.4
50300300	PROTECTIVE COAT	SQ YD		3380	3380
50501140	STRUCTURAL STEEL REMOVAL	POUND		11489	11489
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	<b>L SUM</b>		<b>1</b>	<b>1</b>
50500505	STUD SHEAR CONNECTORS	EACH		15060	15060
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH		40	40
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM		1	1
<b>5060401</b>	<b>CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1</b>	<b>L SUM</b>		<b>1</b>	<b>1</b>
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM		1	1
<b>5060402</b>	<b>CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2</b>	<b>L SUM</b>		<b>1</b>	<b>1</b>
50600800	CLEANING AND PAINTING STEEL BRIDGE NO. 3	L SUM		1	1
<b>5060403</b>	<b>CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 3</b>	<b>L SUM</b>		<b>1</b>	<b>1</b>
50600900	CLEANING AND PAINTING STEEL BRIDGE NO. 4	L SUM		1	1
<b>5060404</b>	<b>CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 4</b>	<b>L SUM</b>		<b>1</b>	<b>1</b>
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND		<b>270,880</b>	<b>270,880</b>
50800515	BAR SPLICERS	EACH		376	376

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 US 20 OVER  
 PRAIRIE AND SIMPSON ROADS

SUMMARY OF QUANTITIES

SCALE: VERT.  
 HORIZ.  
 DATE 06/22/07

DRAWN BY AJP  
 CHECKED BY SPF