

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(2HB-2, 2HB-1D)	WINNEBAGO	107	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

28000300 TEMPORARY DITCH CHECKS	
LOCATION	
839+90	1
840+90	1
842+90	1
843+90	1
844+90	1
845+90	1
846+90	1
847+90	1
850+90	1
851+90	1
TOTAL 10 EACH	

28000400 PERIMETER EROSION BARRIER		
LOCATION	EB	WB
839+00 to 852+50	1350	1350
TOTAL	1350	1350
TOTAL BARRIER 2700 FEET		

28000500 INLET AND PIPE PROTECTION	
LOCATION	
840+62	1
847+92	1
TOTAL 2 EACH	

35101800 AGGREGATE BASE COURSE, TYPE B, 6"		
LOCATION	EB	WB
839+00 to 840+80	460.3	460.3
842+95 to 848+10	1316.1	1316.1
850+40 to 852+50	536.6	536.6
TOTAL	2313	2313
TOTAL BASE COURSE 4626 SQ YD		

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A	
LOCATION	
WESTBOUND (N. SIDE)	
839+00 to 840+46	150
843+08 to 848+34	525
851+17 to 853+70	262.5
WESTBOUND (S. SIDE)	
839+00 to 840+55	162.5
843+17 to 847+99	487.5
850+82 to 852+00	125
EASTBOUND (N. SIDE)	
839+00 to 840+63	162.5
843+25 to 847+72	450
850+55 to 852+00	150
EASTBOUND (S. SIDE)	
839+00 to 840+72	175
844+33 to 847+37	312.5
850+20 to 853+70	350
TOTAL GUARDRAIL 3312.5 FEET	

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	
EB SIMPSON	4
WB SIMPSON	4
EB PRAIRIE	4
WB PRAIRIE	4
TOTAL 16 EACH	

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	
LOCATION	
838+50	2
852+50	2
854+20	2
TOTAL	6 EACH

63200310 GUARDRAIL REMOVAL	
LOCATION	
WESTBOUND (N. SIDE)	
839+00 to 841+20	220
842+30 to 849+00	670
850+30 to 854+20	390
WESTBOUND (S. SIDE)	
842+40 to 845+20	280
850+00 to 852+80	280
EASTBOUND (N. SIDE)	
838+50 to 841+40	290
845+65 to 848+50	285
EASTBOUND (S. SIDE)	
839+00 to 841+50	250
842+50 to 848+10	560
849+50 to 854+20	470
TOTAL REMOVAL 3695 FEET	

63500105 DELINIATORS	
LOCATION	
838+50	2
852+50	2
854+20	2
TOTAL 6 EACH	

64200105 SHOULDER RUMBLE STRIP		
LOCATION	EB	WB
839+00 to 840+80	360	360
842+95 to 848+10	1030	1030
850+40 to 852+50	420	420
TOTAL	1810	1810
TOTAL RUMBLE STRIP 3620 FEET		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
US 20 OVER  
PRAIRIE AND SIMPSON ROADS

SCHEDULE OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE 06/22/07

DRAWN BY AJP  
CHECKED BY SPF

PLOT DATE = 6/28/2007  
FILE NAME = P:\2273-00 - IDOT US 20 Bridges\VP20696-Roadway\ZB69655C1.dwg  
PLOT SCALE = #SCALE#  
USER NAME = #USER#