

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(2HB-2, 2HB-1)D	WINNEBAGO	107	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

70400100 TEMPORARY CONCRETE BARRIER	
LOCATION	
(ALONG CENTERLINE)	
817+25 to 864+25	4700
(BETWEEN STRUCTURES)	
842+70 to 845+70	300
850+00 to 855+80	580
TOTAL BARRIER 5580 FEET	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	
820+00 to 867+00	4700
TOTAL BARRIER 4700 FEET	

78100100 RAISED REFLECTIVE PAVEMENT MARKERS (80 FEET O.C., DOUBLE MARKER)		
LOCATION	EB	WB
839+00 to 840+80	4	4
842+95 to 848+10	14	14
850+40 to 852+50	4	4
TOTAL	22	22
TOTAL MARKERS 44 EACH		

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)		
LOCATION	EB	WB
840+80 to 842+95	6	6
848+10 to 850+40	6	6
TOTAL	12	12
TOTAL MARKERS 24 EACH		

78200410 GUARDRAIL MARKERS, TYPE A		
LOCATION	EB	WB
838+50 to 841+00	8	8
842+75 to 848+50	8	8
850+10 to 852+50	8	8
TOTAL	24	24
TOTAL MARKERS 48 EACH		

78200520 BARRIER WALL MARKERS, TYPE B		
LOCATION	EB	WB
SIMPSON	4	4
PRAIRIE	4	4
TOTAL MARKERS 16 EACH		

78201000 TERMINAL MARKER DIRECT APPLIED	
LOCATION	
838+50	2
852+50	2
854+20	2
TOTAL MARKERS 6 EACH	

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	
LOCATION	
817+20	1
845+90	1
855+80	1
864+30	1
TOTAL ATTENUATORS 4 EACH	

Z0030350 RELOCATE IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	
LOCATION	
819+90	1
866+80	1
TOTAL ATTENUATORS 2 EACH	

ITEM	DESCRIPTION	UNIT	STAGE I	STAGE II	PERMANENT	TOTAL
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	16500	16500		33000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		5500		5500
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT			700	700
78008310	POLYUREA PAVEMENT MARKING, TYPE II, 4"	FOOT			5400	5400
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2250			2250

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
US 20 OVER  
PRAIRIE AND SIMPSON ROADS

SCHEDULE OF QUANTITIES

SCALE: VERT.      HORIZ.  
DATE: 06/22/07

DRAWN BY AJP  
CHECKED BY SPF

PLOT DATE = 6/20/2007  
FILE NAME = P:\2273-00 - IDOT US 20 Bridges\VP2269-05-Roadway\2269-05SCH.dwg  
PLOT SCALE = MISFILE  
USER NAME = WISEN9