

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------------|-----------|---------------------------|--------------|-----------|
| 220 | (23-BR) I | MERCER | 50 | 8 |
| STA. 99+71 | | TO STA. 109+76 | | |
| FED. ROAD DIST. NO. 7 | | ILLINOIS FED. AID PROJECT | | |

| PERMANENT SURVEY MARKERS, TYPE I | |
|----------------------------------|----------|
| LOCATION | EACH |
| WINGWALL @ THE BRIDGE | 1 |
| TOTAL | 1 |

| BITUMINOUS RESURFACING SCHEDULE | | | | | | | | |
|---------------------------------|-------------|------------|----------------------|--|---------------------------------------|----------------------------|--|--|
| STATION TO STATION | LENGTH (FT) | WIDTH (FT) | SURFACE AREA (SQ FT) | HOT-MIX ASPHALT BASE COURSE WIDENING, 8" (SQ YD) | BITUMINOUS MATERIALS PRIME COAT (TON) | AGGREGATE PRIME COAT (TON) | HOT - MIX ASPHALT SURF. CSE. SUPERPAVE MIX "D," N=50 (TON) | HOT-MIX ASPHALT SURFACE REMOVAL BUTT-JOINT (SQ YD) |
| STA 99+71.00 TO STA 102+94.29 | 323.29 | 22 | 7,112 | 359.2 | 0.25 | 1.6 | 67 | 37.0 |
| STA 106+53.21 TO STA 109+76.00 | 322.79 | 22 | 7,101 | 358.6 | 0.25 | 1.6 | 67 | 37.0 |
| TOTAL | | | | 718 | 0.5 | 3 | 134 | 74 |

| RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | |
|---|----------|
| LOCATION | EACH |
| STA 100+20 | 1 |
| STA 101+80 | 1 |
| STA 102+60 | 1 |
| STA 106+40 | 1 |
| STA 107+20 | 1 |
| STA 108+00 | 1 |
| STA 108+80 | 1 |
| STA 109+60 | 1 |
| TOTAL | 8 |

| TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 | |
|---|----------|
| LOCATION | EACH |
| SEC. (23-BR) I | 1 |
| TOTAL | 1 |

| SHORT-TERM PAVEMENT MARKING | |
|-----------------------------|------------|
| LOCATION | FOOT |
| STA 99+71 TO STA 109+76 | 335 |
| TOTAL | 335 |

| IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3 | |
|--|----------|
| LOCATION | EACH |
| STAGE I | |
| RT STA 101+74.75 TO STA 101+83.75 | 1 |
| RT STA 107+63.75 TO STA 107+72.75 | 1 |
| TOTAL | 2 |

| TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | |
|---|----------|
| LOCATION | L. SUM |
| SEC. (23-BR) I | 1 |
| TOTAL | 1 |

| TEMPORARY PAINT PAVEMENT MARKING LINE, 4" | |
|---|-------------|
| LOCATION | FOOT |
| LT STA 99+71 TO STA 109+76 (WHITE) | 1005 |
| CTR STA 99+71 TO STA 109+76 (C) (YELLOW) | 251 |
| RT STA 99+71 TO STA 109+76 (WHITE) | 1005 |
| TOTAL | 2261 |

| IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3 | |
|---|----------|
| LOCATION | EACH |
| STAGE II | |
| LT STA 101+54.75 TO STA 101+63.75 | 1 |
| LT STA 107+83.75 TO STA 107+92.75 | 1 |
| TOTAL | 2 |

| TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | |
|---|----------|
| LOCATION | L. SUM |
| SEC. (23-BR) I | 1 |
| TOTAL | 1 |

| RAISED REFLECTIVE PAVEMENT MARKER | |
|-----------------------------------|----------|
| LOCATION | EACH |
| STA 100+20 | 1 |
| STA 101+00 | 1 |
| STA 101+80 | 1 |
| STA 102+60 | 1 |
| STA 106+40 | 1 |
| STA 107+20 | 1 |
| STA 108+00 | 1 |
| STA 108+80 | 1 |
| STA 109+60 | 1 |
| TOTAL | 9 |

| TRAINEES | |
|--------------|------------|
| LOCATION | EACH |
| JOB SITE | 500 |
| TOTAL | 500 |

| TRAFFIC CONTROL SURVEILLANCE | |
|------------------------------|----------|
| LOCATION | CAL DA |
| SEC. (23-BR) I | 2 |
| TOTAL | 2 |

| TEMPORARY BRIDGE TRAFFIC SIGNALS | |
|----------------------------------|----------|
| LOCATION | EACH |
| S.N. 066-0008 | 1 |
| TOTAL | 1 |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES