



CONTRACT NO. 74166

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
716	(130BR-1)B-1	MACON	95	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

APPURTENANCE ADJUSTMENT SCHEDULE

LOCATION	VALVE BOXES TO BE ADJUSTED	MH TO BE ADJUSTED	MH TO BE ADJUSTED WITH F&G (SPECIAL)	CB TO BE ADJUSTED WITH TYPE 11V F&G	CB TO BE ADJUSTED WITH TYPE 9 F&G
	EACH	EACH	EACH	EACH	EACH
STA 133+04, 25.64' LT				1	
STA 133+40, 26.72' LT				1	
STA 133+68, 54.2' RT			1		
STA 133+81, 28' RT	1				
STA 133+81, 40' RT	1				
STA 134+30, 51.3' RT			1		
STA 135+02, 49' RT		1			
STA 136+96, 32.56' LT					1
STA 137+00, 45' RT		1			
STA 138+21, 32.76' LT				1	
STA 138+47, 32.76' RT				1	
STA 138+75, 32.76' LT				1	
STA 138+86, 32.76' LT				1	
TOTALS	2	2	2	6	1

TRENCH BACKFILL SCHEDULE

LOCATION	CU YD
12" SS REMOVAL S. OF SN 058-0135	23
PR 12" SS N. OF BRIDGE	13
PR 12" SAN. SEWER N. OF SN 058-0135	20
TOTAL	56

SANITARY SEWER SCHEDULE

LOCATION	SANITARY MH, 4' TYPE 1F, CL1D	SANITARY SEWER DUCTILE IRON 12"	SANITARY SEWER, SPECIAL	PIPE SUPPORT	TEMPORARY SUPPORT SYSTEM	PLUG EX SANITARY SEWERS
	EACH	FOOT	FOOT	EACH	EACH	EACH
SN 058-0135				16		
STAGE I		398	356		1	1
STA 134+60, 42' LT	1					
STA 136+55, 42' LT	1					
STA 138+14, 57' LT	1					
STA 138+14, 20' LT	1					
TOTALS	4	398	356	16	1	1

COMBINATION CURB AND GUTTER SCHEDULE

LOCATION	CCC&G TYPE B6.24	CCC&G TYPE M2.06
	FOOT	FOOT
STA 133+00 TO MCKINLEY, RT	96	
STA 133+00 TO SN 058-0135, LT	146	
MCKINLEY TO STA 134+50, RT	77	
STA 137+05 TO STA 138+93, LT	189	
SN 058-0135 TO STA 139+00, RT	189	
STA 134+50 TO SN 058-0135, RT		56
SN 058-0135 TO STA 137+05, LT		53
TOTALS	697	109

ESCA
CONSULTANTS, INC.

DESIGNED BY:	ELH	05/07
DRAWN BY:	JPC	05/07
CHECKED BY:	ELH	06/07
APPROVED BY:	RDP	06/07

SCHEDULES OF QUANTITIES
FAP ROUTE 716 (IL 48)
OAKLAND AVENUE
SECTION (130BR-1)B-1
MACON COUNTY