

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET, LOCATION MAP
2	INDEX OF SHEETS, LEGEND OF SYMBOLS, AND STANDARD DRAWINGS
3	SUMMARY OF QUANTITIES
4	SITE PLAN
5	LIGHTING AND P.C.C. SIDEWALK, 5" DETAILS
6-8	OVERPASS LIGHTING PLAN AND LIGHTING DETAILS
9-10	CHAIN LINK FENCE DETAILS
11	PIER/ABUTMENT MOUNTED UNDERPASS LUMINAIRE INSTALLATION DETAILS
12	PORTLAND CEMENT CONCRETE/COMPOSITE CONCRETE DETAILS
13	SIGN PANEL MOUNTING DETAILS
14	SIGN PANEL ERECTION DETAILS
15	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

GENERAL NOTES

FIELD OFFICE

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE OR VILLAGE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT OR THE VILLAGE.

BARRICADES

THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED, ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.

SAW CUTTING

THE CONTRACTOR SHALL SAW CUT SIDEWALK AS INDICATED ON THE PLANS TO SEPARATE THE EXISTING SIDEWALK TO BE REMOVED BY APPROVED MEANS OR AN APPROVED CONCRETE SAW TO A DEPTH AS DIRECTED BY THE ENGINEER. SUITABLE GUIDELINES OR DEVICES SHALL BE USED TO ASSURE CUTTING A NEAT, STRAIGHT LINE AS SHOWN ON THE PLANS. CARE SHALL BE TAKEN BY THE CONTRACTOR AS NOT TO DAMAGE THE REMAINING SIDEWALK DIRECTLY ADJACENT TO THE SIDEWALK TO BE REMOVED. ANY DAMAGE TO THE EXISTING SIDEWALK RESULTING FROM SIDEWALK REMOVAL OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. THE COST OF SAW CUTTING SHALL BE INCLUDED IN THE ITEM BEING REMOVED.

STANDARDS

ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARD OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION AS SHOWN ON THE INDEX OF SHEETS IN THE PLANS.

UNDERGROUND UTILITIES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRICAL, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED).

THE LOCATIONS OF THE UNDERGROUND UTILITIES IF SHOWN ON THE PLANS HAVE BEEN OBTAINED BY FIELD SURVEYS AND SEARCHES OF AVAILABLE RECORDS. IT IS BELIEVED THAT THE DATA IS ESSENTIALLY CORRECT, BUT THE VILLAGE OF BROOKFIELD, THE ILLINOIS DEPARTMENT OF TRANSPORTATION AND/OR OTHER OFFICES AND AGENCIES ASSOCIATED WITH THE DEVELOPMENT OF THESE PLANS DO NOT GUARANTEE THEIR ACCURACY OR COMPLETENESS OF THIS INFORMATION. THE CONTRACTOR WILL BE REQUIRED TO VERIFY THE EXACT LOCATION OF EACH FACILITY WITH THE RESPECTIVE UTILITY COMPANY, AND SHALL TAKE DUE CARE IN ALL PHASES OF THE CONSTRUCTION TO PROTECT ANY SUCH FACILITIES WHICH MAY BE AFFECTED BY THE WORK. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF BELLWOOD.

LEGEND OF SYMBOLS

EXISTING	PROPOSED	DESCRIPTION
		COMBINATION SEWER
		COMBINED RELIEF SEWER
		STORM SEWER
		WATER MAIN
		MANHOLE, TYPE A, 4' DIAMETER
		INLET, TYPE A
		CATCH BASIN
		FIRE HYDRANT
		WATER MAIN VALVE BOX
		WATER SERVICE BOX
		ELECTRIC HANDHOLE
		CURB & GUTTER TO BE REMOVED & REPLACED
		LIGHT STANDARD
		UNDERPASS BRIDGE LIMIT
		FENCE POST
		FENCE
		CONDUIT ATTACHED TO STRUCTURE
		CONDUIT IN TRENCH
		UNDERPASS LUMINAIRE
		JUNCTION BOX
		UNIT DUCT

I.D.O.T. STANDARD DRAWINGS

STANDARD NO.	TITLE OR DESCRIPTION
000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
664001-01	CHAIN LINK FENCE
720001	SIGN PANEL MOUNTING DETAILS
720006-01	SIGN PANEL ERECTION DETAILS
814001-01	HANDHOLES