

SECTION 18, TOWNSHIP 37, RANGE 13
SECTION 19, TOWNSHIP 37, RANGE 13

F. A. N. I. N.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2955	05-00052-00-LT	COOK	009	002
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT # 83963

S.I.		CODE NO.	PAY ITEM	UNIT	QUAN
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1540
		21300010	EXPLORATION TRENCH, SPECIAL	FOOT	500
		25200110	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	1540
		25200200	SUPPLEMENTAL WATERING	UNIT	100
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	125
		44000600	SIDEWALK REMOVAL	SQ FT	125
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
		70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
		80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
		80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
		81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	765
		81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4395
		XX006936	UNIT DUCT, WITH 3-1/C NO. 6 AND 1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	5160
		81702440	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 1/0	FOOT	100
		82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	28
		82500520	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 480VOLT	EACH	1
		83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	19
		83008600	LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. MAST ARM	EACH	5
		83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	175
		83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	8
		83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	24
		84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE (SPECIAL)	EACH	4
		67100100	MOBILIZATION	L SUM	1

* - INDICATES SPECIALTY ITEMS

GENERAL NOTES

1. ALL WORK TO CONFORM TO THE NATIONAL ELECTRICAL CODE AND ANY APPLICABLE LOCAL CODES.
2. CONTRACTOR TO VERIFY LOCATION OF ALL UNDERGROUND UTILITIES BEFORE TRENCHING OR AUGERING.
3. BEFORE INSTALLING STANDARDS NEAR OVERHEAD FACILITIES CALL C.E. Co. FOR APPROVAL OF LOCATION.
4. FOR LOCATION OF EXISTING UNDERGROUND ELECTRICAL CABLE CALL C.E. Co.
5. SIZE ALL CONDUIT AS SPECIFIED ON DRAWINGS.
6. CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO RESTORE ANY SPECIALIZED LANDSCAPING, (I.E. DECORATIVE ROCKS, SHRUBS, PLANTS, ECT.) OR SHALL REPLACE IT, THE COST OF WHICH SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**OAK PARK AVENUE
STREET LIGHTING
SUMMARY OF QUANTITIES & GENERAL NOTES**

SCALE: VERT. NA
 HORIZ. NA
DATE: 4-6-07

DRAWN BY PS
CHECKED BY TRL/DWS