

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3509	00-00173-00-FP	COOK	246	11
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

PLOT DATE = 7/12/2007  
 FILE NAME = G:\N\0805\0805\road\shades\SUMQT.dwg  
 USER NAME = b.johnson

SUMMARY OF QUANTITIES				1000-2A ROADWAY WILMETTE 70% STU 30% STATE	1000-2A ROADWAY EVANSTON 70% STU 30% STATE	Y030-1E LIGHTING WILMETTE 70% STU 30% LA	Y030-1E LIGHTING EVANSTON 70% STU 30% LA	Y031-IF SIGNALS WESTERFIELD 70% STU 30% LA	Y031-IF SIGNALS LAKE 70% STU 30% LA	Y031-IF SIGNALS ISABELLA 70% STU 30% LA	Y003-TEA ENHANCEMENTS WILMETTE 80% ITEP 20% LA	Y060 WATER WILMETTE NON-PART 100% LA	Y060 WATER EVANSTON NON-PART 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY										
XX005434	WATER SERVICE LINE, SPECIAL	FOOT	3,598									3,598	
XX005642	• GATEWAY MONUMENT SIGN COMPLETE	EACH	4								4		
XX005929	• TRAFFIC SIGNAL POST, 14 FOOT, (SPECIAL)	EACH	5								4		
XX005930	• TRAFFIC SIGNAL POST, 15 FOOT, (SPECIAL)	EACH	1							1			
XX005931	• TRAFFIC SIGNAL POST, 16 FOOT, (SPECIAL)	EACH	2							1			
XX005932	• TRAFFIC SIGNAL POST, 18 FOOT, (SPECIAL)	EACH	1								1		
X8620020	• UNINTERRUPTABLE POWER SUPPLY	EACH	3					1	1	1			
XZ127900	RETAINING WALL REMOVAL	FOOT	436	436									
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	54,762	46,611	8,151								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1									
Z0019600	DUST CONTROL WATERING	UNIT	300	300									
Z0056800	SANITARY SEWER 6"	FOOT	6,185	6,185									
Z0056900	SANITARY SEWER 8"	FOOT	29	29									
Z0057000	SANITARY SEWER 10"	FOOT	1,281	1,281									
Z0057100	SANITARY SEWER 12"	FOOT	715	715									
Z0057200	SANITARY SEWER 15"	FOOT	909	909									
Z0057300	SANITARY SEWER 18"	FOOT	203	203									
Z0057500	SANITARY SEWER 24"	FOOT	675	675									
Z0076600	△ TRAINEES	HOUR	3,000	3,000									
XX007066	• EVERGREEN, JUNIPERUS SABINE 'CALGARY CARPET', #5, CONTAINER	EACH	24								24		
XX007067	• EVERGREEN, TAXUS X MEDIAN 'RUNYANII', 30" BALLED AND BURLAPPED	EACH	18								18		
XX007068	• SHRUB, ROSA RED RIBBONS (RED RIBBONS ROSE), 18" HEIGHT, CONTAINER	EACH	56								56		
XX007069	• PERENNIAL, ALCHEMILLA MOLLIS, #1, CONTAINER	EACH	69								69		
XX007070	• PERENNIAL, HEMEROCALLIS 'CUSTARD CANDY', #1, CONTAINER	EACH	38								38		
XX007071	• PERENNIAL, HEMEROCALLIS 'HUSH LITTLE BABY', #1, CONTAINER	EACH	38								38		
XX007072	• PERENNIAL, HEMEROCALLIS 'JOVIAL', #1, CONTAINER	EACH	38								38		
XX007073	• PERENNIAL, HOSTA VENTRICOSA 'AUREO-MARGINATA', #1, CONTAINER	EACH	68								68		
XX007074	• LANTANA CAMARA (COMMON VERBENA), 1 QUART POT	EACH	46								46		
XX007075	• PERENNIAL, SEDUM SPECTABILE 'AUTUMN FIRE', #1, CONTAINER	EACH	81								81		
XX007076	• PERENNIAL, SORGHASTRUM NUTANS 'SIOUX BLUE', #2, CONTAINER	EACH	23								23		
XX007077	• BULB, ALLIUM 'GLOBEMASTER', TOPSIZE, BULB	EACH	27								27		
XX007078	VALVE VAULTS TO BE LINED	EACH	2										2
XX007079	• CONCRETE RIBBON	FOOT	1,410								1,410		
XX007080	COMBINED SEWER REMOVAL 10"	FOOT	1,362	1,362									
XX007081	SEWER LATERAL CLEANOUT	EACH	166	166									
XX007082	STORM SEWER (WATER MAIN REQUIREMENTS) 33 INCH	FOOT	204	204									
XX007083	MANHOLES, SANITARY, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
XX007084	• LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. DAVIT ARM (SPECIAL)	EACH	13								13		
XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	2										
* 1 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	296	296									

• SPECIALTY ITEM  
△ Y080

1 Revised 9-7-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 SHERIDAN ROAD  
 DATE 7/13/07  
 DRAWN BY LTD  
 CHECKED BY B.J.L