

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3509 00-00173-00-PP		COOK	246	4
STA.		TO STA.		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

PLOT DATE = 7/13/07
 FILE NAME = C:\Users\Bjohman\Documents\83964\83964.dwg
 PLOT SCALE = 50.0000 / 1" = 100'
 USER NAME = Bjohman

1051 PERIMETER DRIVE, SUITE 1025
 SCHAUMBURG, ILLINOIS 60173
 (647) 905-9600



SUMMARY OF QUANTITIES				1000-2A ROADWAY WILMETTE 70% STU 30% STATE	1000-2A ROADWAY EVANSTON 70% STU 30% STATE	Y030-1E LIGHTING WILMETTE 70% STU 30% LA	Y030-1E LIGHTING EVANSTON 70% STU 30% LA	Y031-1F SIGNALS WESTERFIELD 70% STU 30% LA	Y031-1F SIGNALS LAKE 70% STU 30% LA	Y031-1F SIGNALS ISABELLA 70% STU 30% LA	Y003-TEA ENHANCEMENTS WILMETTE 80% ITP 20% LA	Y060 WATER WILMETTE NON-PART 100% LA	Y060 WATER EVANSTON NON-PART 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY										
20100110	• TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	34	34									
20100210	• TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	50	18	32								
20101000	TEMPORARY FENCE	FOOT	26,461	21,336	5,125								
20101200	• TREE ROOT PRUNING	EACH	366	304	62								
20101300	• TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	172	129	43								
20101350	• TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	194	174	20								
20200100	EARTH EXCAVATION	CU YD	28,015	23,352	4,663								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,585	4,135	450								
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	15	15									
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3,500	3,150	350								
20800150	TRENCH BACKFILL	CU YD	16,998	16,220	778								
20800250	TRENCH BACKFILL, SPECIAL	CU YD	18,672	11,319								7,336	17
21101615	• TOPSOIL FURNISH AND PLACE, 4"	SQ YD	17,216	14,396	2,820								
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	700	500								100	100
25000400	• NITROGEN FERTILIZER NUTRIENT	POUND	218	181	37								
25000500	• PHOSPHORUS FERTILIZER NUTRIENT	POUND	218	181	37								
25000600	• POTASSIUM FERTILIZER NUTRIENT	POUND	218	181	37								
25200110	• SODDING, SALT TOLERANT	SQ YD	17,216	14,396	2,820								
25200200	• SUPPLEMENTAL WATERING	UNIT	510	450	60								
25300500	• TOP SOIL FOR PLANTING	CU YD	270								270		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	680	600	80								
28000510	INLET FILTERS	EACH	136	105	31								
35300100	PORTLAND CEMENT CONCRETE BASE COURSE 6"	SQ YD	3,614		3,614								
35300210	PORTLAND CEMENT CONCRETE BASE COURSE 7 1/2"	SQ YD	47,647	43,393	4,254								
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	506	419	87								
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	180	180									
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	17,896	15,217	2,679								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	317	60	257								
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7,313	6,111	1,202								
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	121	104	17								
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,301	3,656	645								
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1,534	1,282	252								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	775	691	84								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	44,784	35,827	8,957								
42400800	DETECTABLE WARNINGS	SQ FT	800	540	260								
44000100	PAVEMENT REMOVAL	SQ YD	53,581	44,942	8,639								
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	63	63									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,740	2,328	412								
44000300	CURB REMOVAL	FOOT	208	161	47								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	22,648	18,781	3,867								
44000600	SIDEWALK REMOVAL	SQ FT	41,378	33,102	8,276								

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHERIDAN ROAD
 DATE 7/13/07
 DRAWN BY LTD
 CHECKED BY BJL
 NO SCALE