

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
3509 00-00173-00-FP		COOK	246 5
STA.		TO STA.	
FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT	

PLOT DATE = 7/12/07
 FILE NAME = I:\cadd\83964\summary\summary.dwg
 PLOT SCALE = 5/8" = 1' IN.
 USER NAME = bjohnson

SUMMARY OF QUANTITIES				1000-2A ROADWAY WILMETTE 70% STU 30% STATE	1000-2A ROADWAY EVANSTON 70% STU 30% STATE	Y030-1E LIGHTING WILMETTE 70% STU 30% LA	Y030-1E LIGHTING EVANSTON 70% STU 30% LA	Y031-1F SIGNALS WESTERFIELD 70% STU 30% LA	Y031-1F SIGNALS LAKE 70% STU 30% LA	Y031-1F SIGNALS ISABELLA 70% STU 30% LA	Y003-TEA ENHANCEMENTS WILMETTE 80% ITEP 20% LA	Y060 WATER WILMETTE NON-PART 100% LA	Y060 WATER EVANSTON NON-PART 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY										
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	166	154	12								
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	23	23									
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	2,267	2,267									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	168	168									
48301000	PROTECTIVE COAT	SQ YD	56,086	51,716	4,370								
50102400	CONCRETE REMOVAL	CU YD	9.5	9.5									
50200100	STRUCTURE EXCAVATION	CU YD	264	264									
50202901	COFFERDAM (LOCATION - 1)	EACH	1	1									
50202902	COFFERDAM (LOCATION - 2)	EACH	1	1									
50300225	CONCRETE STRUCTURES	CU YD	112.8	112.8									
50401205	• PRECAST CONCRETE CAPS	EACH	38								38		
50401215	• PRECAST CONCRETE PANEL	SQ FT	1,510								1,510		
50500505	STUD SHEAR CONNECTORS	EACH	272	272									
50700209	UNTREATED TIMBER LAGGING	SQ FT	1,531	1,531									
51202230	FURNISHING SOLDIER PILES (W SECTION)	FOOT	862	862									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16,580	16,580									
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,065	935	130								
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	206	86	120								
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	157		157								
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	555		555								
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	953	638	315								
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	938	938									
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	415	415									
550A0440	STORM SEWERS, CLASS A, TYPE 2 33"	FOOT	441	441									
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	1,342	1,342									
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	55	55									
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	33	33									
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	805	805									
550A0770	STORM SEWERS, CLASS A, TYPE 3 42"	FOOT	1,370	1,370									
550A1070	STORM SEWERS, CLASS A, TYPE 4 42"	FOOT	653	653									
55100300	STORM SEWER REMOVAL 8"	FOOT	1,771	1,766	5								
55100500	STORM SEWER REMOVAL 12"	FOOT	429	306	123								
55100700	STORM SEWER REMOVAL 15"	FOOT	35	35									
552A1100	STORM SEWERS JACKED IN PLACE, CLASS A 30"	FOOT	130	130									
552A1500	STORM SEWERS JACKED IN PLACE, CLASS A 42"	FOOT	145	145									
56100600	WATER MAIN 6"	FOOT	684									678	6
56100700	WATER MAIN 8"	FOOT	1,821									1,821	
56100800	WATER MAIN 10"	FOOT	20									10	10
56100900	WATER MAIN 12"	FOOT	5,362									5,347	15
56101000	WATER MAIN 16"	FOOT	4,379									4,379	

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHERIDAN ROAD
 DATE 7/13/07
 DRAWN BY LTD
 CHECKED BY B.J.L